

TYPICAL FLOOR
(10TH FLOOR TO 16TH FLOOR)
(18TH FLOOR TO 19TH FLOOR)
(TOWER-F)



TYPICAL (10TH TO 16TH & 18TH TO 19TH) FLOOR TOWER-F

AREA CALCULATION OF TYPICAL (10th TO 16th,18th TO 19TH) FLOOR (TOWER-F)							
GROSS - A							
a	4	X	1.825	X	3.830	=	27.959 SQM
b	4	X	4.460	X	8.230	=	131.579 SQM
c	4	X	1.700	X	2.465	=	16.762 SQM
d	4	X	1.700	X	0.425	=	4.922 SQM
e	4	X	2.995	X	0.750	=	8.965 SQM
f	4	X	4.425	X	0.400	=	7.080 SQM
g	4	X	4.300	X	1.500	=	25.800 SQM
h	4	X	3.700	X	1.075	=	15.910 SQM
i	4	X	6.365	X	0.425	=	10.821 SQM
j	4	X	4.460	X	0.750	=	13.395 SQM
k	2	X	4.550	X	0.400	=	3.640 SQM
l	2	X	4.563	X	1.500	=	13.878 SQM
m	2	X	3.775	X	1.075	=	8.118 SQM
n	2	X	35.180	X	0.475	=	33.421 SQM
o	1	X	31.880	X	0.425	=	13.559 SQM
p	4	X	1.200	X	0.450	=	2.160 SQM
q	2	X	1.100	X	3.302	=	8.745 SQM
					TOTAL	=	1112.794 SQM
GROSS - B							
a	12	X	0.400	X	0.850	=	4.080 SQM
b	12	X	0.275	X	0.560	=	1.815 SQM
d	4	X	1.575	X	0.800	=	5.040 SQM
f	1	X	5.100	X	2.700	=	13.770 SQM
g	1	X	1.475	X	1.200	=	1.770 SQM
h	1	X	0.825	X	1.350	=	0.844 SQM
i	1	X	1.575	X	1.350	=	4.561 SQM
k	1	X	0.800	X	1.000	=	0.800 SQM
m	1	X	0.700	X	1.450	=	1.015 SQM
n	1	X	0.700	X	3.475	=	2.541 SQM
p	4	X	2.550	X	2.300	=	23.500 SQM
q	1	X	1.650	X	0.750	=	1.238 SQM
r	1	X	1.650	X	0.350	=	0.908 SQM
s	1	X	1.650	X	0.350	=	0.908 SQM
u	1	X	0.400	X	1.200	=	0.480 SQM
v	1	X	5.100	X	2.700	=	13.770 SQM
w	2	X	1.175	X	0.800	=	0.940 SQM
					TOTAL	=	100.854 SQM

TOTAL FAR AREA OF TYPICAL (10TH TO 16th,18th TO 19th) FLOOR (TOWER-F)	=	GROSS - A	-	GROSS - B
	=	1112.794	-	100.854
	=	1011.941	SQM	

BUILTUP AREA							
GROSS - C							
f	1	X	5.100	X	2.700	=	13.770 SQM
g	1	X	1.475	X	1.200	=	1.770 SQM
u	1	X	0.400	X	1.200	=	0.480 SQM
v	1	X	5.100	X	2.700	=	13.770 SQM
					TOTAL	=	29.790 SQM

TOTAL BUILTUP AREA OF TYPICAL (10TH TO 16th,18th TO 19th) FLOOR (TOWER-F)	=	FAR AREA	+	GROSS - C
	=	1011.941	+	29.790
	=	1041.731	SQM	

TOTAL NON FAR AREA OF TYPICAL (10th TO 16th,18th TO 19TH) FLOOR (TOWER-F)	=	BUILTUP AREA	-	FAR AREA		
	=	1041.731	-	1011.941		
	=	29.790	SQM			

DOOR AND WINDOW SCHEDULE (TYPICAL AND REFUSE FLOOR)							
SR. NO.	NAME	ROUGH OPENING	ROUGH OPENING HEIGHT	SILL LVL	LINTEL LVL	LOCATION	TYPE
1	D1	900	2420	0	2420	KITCHEN	UPVC
2	D2	800	2420	0	2420	TOILETS & UTILITY& POWDER ROOM	UPVC
3	D2a	800	2200	0	2200	STAFF TOILET	UPVC
4	D3	1000	2420	0	2420	BEDROOMS, UTILITY, UNISEX TOILET	UPVC
5	D3a	1000	2200	0	2200	UTILITY BALCONY	UPVC
6	SD1	2495	2600	0	2600	MASTER BEDROOM	UPVC
7	SD2	1700	0	0	0	BEDROOM 2,3, MULTIPURPOSE PLAYROOM	UPVC
8	SD3	3700	2600	0	2600	LIVING ROOM	UPVC
9	SD4	2165	2600	0	2600	BEDROOM 4	UPVC
10	DW1	1500	1550	1050	2600	KITCHEN	UPVC
11	W1	600	1100	1350	2450	TOILET	UPVC
12	W2	700	1550	1050	2600	MASTER BEDROOM	UPVC
13	W3	600	1550	1050	2600	UTILITY TOILET	UPVC
14	W4	1000	1150	1050	2200	SERVICE AREA, STORE ROOM	UPVC
15	W7	600	1450	1350	2800	MASTER BEDROOM TOILET	UPVC
16	FD	1200	2420	0	2420	ENTRANCE DOOR	2HR FIRE RATED
17	FDa	1200	2420	0	2420	FIRE TOWER	2HR FIRE RATED
18	FD1	1200	2150	0	2150	STAIRCASE	2HR FIRE RATED
19	FD4	750	2050	100	2150	SERVICE & LIV SHAFT	2HR FIRE RATED
20	FD5	1000	2050	100	2150	ELEC. SHAFT	2HR FIRE RATED
21	FC1	900	2050	100	2150	FHC	A/VENDOR
22	FD8	1000	2420	0	2420	CORRIDOR	2HR FIRE RATED
23	FD9	2000	2420	0	2420	SOCIALIZED AREA	2HR FIRE RATED



17th REFUGE FLOOR

REFUGE AREA CALCULATION - 17TH. REFUGE FLOOR								
GROSS – A								
r1	=	1	X	2.060	X	5.230	=	10.775 SQM
r2	=	1	X	4.510	X	7.240	=	32.675 SQM
r3	=	1	X	4.400	X	0.325	=	1.430 SQM
						TOTAL	=	44.880 SQM
GROSS – B								
s1	=	1	X	1.200	X	0.900	=	1.080 SQM
						TOTAL	=	1.080 SQM

	=	GROSS – A	-	GROSS – B
TOTAL REFUGE AREA	=	44.880		1.080
	=	43.800	SQM	
GROSS AREA OF 17TH FLOOR	=	788.471	SQM	
GROSS AREA OF TYPICAL 18TH FLOOR	=	1004.675	SQM	
TOTAL	=	1793.146	SQM	

TOTAL NO. OF OCCUPANTS	=	GROSS AREA	/	OCCUPANT FACTOR		
	=	1793.146	/	12.5	=	143 PERSONS
REFUGE AREA REQUIRED	=	0.3 SQM PER PERSON	+	0.9 SQM ADDITIONAL SPAE TO ACCOMMODATE WHEEL CHAIR		
	=	0.3	X	143	=	0.9
	=	42.900				0.9
PROPOSED REFUGE AREA	=	43.800	SQM.			
	=	43.800	SQM.			



17TH FLOOR
LVL. +63900
(TOWER-F)



17th (REFUGE) FLOOR AREA
TOWER-F

AREA CALCULATION OF 17TH REFUGE FLOOR (TOWER-F)							
GROSS – A							
1	3	X	1.150	X	0.400	=	1.485 SQM
2	3	X	2.995	X	0.425	=	3.597 SQM
3	3	X	2.995	X	0.750	=	6.739 SQM
4	3	X	4.425	X	0.400	=	5.310 SQM
5	3	X	4.300	X	1.500	=	19.350 SQM
6	3	X	3.700	X	1.075	=	11.933 SQM
7	3	X	6.365	X	0.425	=	8.119 SQM
8	3	X	4.460	X	0.750	=	14.546 SQM
9	1	X	4.550	X	0.400	=	1.820 SQM
10	1	X	4.313	X	1.500	=	6.455 SQM
11	1	X	3.775	X	1.075	=	4.059 SQM
12	3	X	1.825	X	3.830	=	20.969 SQM
13	3	X	4.460	X	7.375	=	98.678 SQM
14	1	X	35.180	X	7.375	=	259.533 SQM
15	1	X	31.880	X	2.975	=	94.843 SQM
17	1	X	2.235	X	1.810	=	4.045 SQM
18	1	X	5.600	X	0.800	=	4.480 SQM
20	1	X	0.900	X	1.880	=	1.692 SQM
21	1	X	2.550	X	1.350	=	3.443 SQM
22	1	X	20.545	X	3.485	=	63.479 SQM
23	1	X	22.845	X	3.420	=	6.136 SQM
24	1	X	22.845	X	3.485	=	10.632 SQM
26	1	X	6.725	X	6.350	=	40.698 SQM
27	1	X	16.040	X	3.445	=	55.255 SQM
28	1	X	17.690	X	7.375	=	128.693 SQM
29	1	X	1.985	X	1.075	=	5.134 SQM
30	1	X	2.263	X	1.500	=	3.395 SQM
31	1	X	2.313	X	0.800	=	1.850 SQM
32	4	X	1.200	X	0.450	=	2.160 SQM
33	1	X	1.100	X	1.500	=	1.650 SQM
					TOTAL	=	894.593 SQM
GROSS – B							
a	9	X	0.400	X	0.850	=	3.060 SQM
b	9	X	0.275	X	0.550	=	1.361 SQM
d	3	X	1.575	X	0.800	=	3.780 SQM
e	3	X	1.575	X	1.350	=	4.151 SQM
f	1	X	0.625	X	1.350	=	0.844 SQM
g	1	X	5.100	X	2.700	=	13.770 SQM
h	1	X	0.800	X	1.000	=	0.800 SQM
i	1	X	0.700	X	1.450	=	1.015 SQM
k	1	X	0.700	X	1.450	=	1.015 SQM
m	1	X	0.700	X	3.475	=	2.541 SQM
n	4	X	2.550	X	2.300	=	23.500 SQM
o1	4	X	1.300	X	2.300	=	7.475 SQM
p	1	X	5.850	X	1.200	=	6.780 SQM
q	1	X	5.100	X	1.500	=	7.650 SQM
r	1	X	1.250	X	1.600	=	2.000 SQM
s	1	X	1.650	X	0.750	=	1.238 SQM
t	1	X	1.650	X	0.550	=	0.908 SQM
u	1	X	2.550	X	2.700	=	6.885 SQM
w1	1	X	1.900	X	0.350	=	0.665 SQM
w2	1	X	1.175	X	0.800	=	0.940 SQM
					TOTAL	=	96.343 SQM
GROSS – C							
a	1	X	5.100	X	2.700	=	13.770 SQM
b	1	X	5.850	X	1.200	=	6.780 SQM
c	1	X	5.100	X	1.500	=	7.650 SQM
d	1	X	1.250	X	1.600	=	2.000 SQM
e	1	X	1.650	X	0.750	=	1.238 SQM
f	1	X	1.650	X	0.550	=	0.908 SQM
g	1	X	2.550	X	2.700	=	6.885 SQM
w1	1	X	1.900	X	0.350	=	0.665 SQM
w2	1	X	1.175	X	0.800	=	0.940 SQM
					TOTAL	=	41.834 SQM

TOTAL BUILTUP AREA OF 17TH REFUGE FLOOR (TOWER-F)	=	FAR AREA	+	GROSS – C	
	=	797.711	+	289.607	
	=	1087.318	SQM		
TOTAL NON FAR AREA OF 17TH REFUGE FLOOR (TOWER-F)	=	BUILTUP AREA	-	FAR AREA	
	=	1087.318	-	797.711	
	=	289.607	SQM		

DIMENSION LEGEND	
1525	ARCHITECTURE DIM
1525	AREA DIM

LIFT CAPACITY			
S/N. NO.	Shaft Size (mm)	Car Size (mm)	Capacity
1	2600x2400	2000x1550x2700	20PY 1900Kg
2	1900x3000	1100x2300x2700	16PY 1088Kg
3	2650x2450	1800x1900x2700	20PY 1362Kg

FLOORS	TOWER–F
10TH FLOOR	+40100
11TH FLOOR	+43500
12th FLOOR	+46900
13th FLOOR	+50300
14th FLOOR	+53700
15th FLOOR	+57100
16TH FLOOR	+60500
18th FLOOR	+67300
19th FLOOR	+70700



PART PLAN (POWDER ROOM)



SECTION : A-A

TYPICAL MECHANICAL VENTILATION CALCULATION FOR POWDER ROOM							
S. NO.	LOCATION	AREA	HEIGHT	VOLUME	DESIGN CFM	SELECTED EXHAUST FAN	FAN SIZE	EXHAUST DUCT SIZE
		(SQ.M)	(FT.)	(CU.FT)	CFM		N/A	SHANK DIA (mm)
1	TYPICAL MECHANICAL VENTILATION FOR POWDER ROOM							
	POWDER ROOM	26.4	9	238	47.60	18*150cfm cassette in line fan	150	150NOS

LEGEND :-

SW	①	160 OD uPVC SWR CLASS B SOIL / WASTE & VENT PIPE
SW	②	110 OD uPVC SWR CLASS B ANTISYPHONIC PIPE
SW	④	160 OD uPVC SWR CLASS B ANTISYPHONIC PIPE
SW	⑤	160 OD uPVC SWR CLASS A RAIN WATER DOWNTAKE PIPE
SW	⑦	DOMESTIC WATER SUPPLY DOWNTAKE PIPE (CLASS-D)
SW		DOMESTIC WATER SUPPLY DOWNTAKE PIPE (CLASS-D)
SW		110 OD uPVC SWR CLASS A BALCONY DRAIN PIPE
FD		FLOOR DRAIN
DWS		DOMESTIC WATER SUPPLY
FWS		FLUSHING WATER SUPPLY
PRS		PRESSURE REDUCING VALVE STATION

Note :-

1. BUILDING WILL BE DESIGNED (STRUCTURES) AS PER RELEVANT IS CODES FOR EARTH QUAKE RESISTANCE.

PROJECT

REVISED(1ST REVISION) BUILDING PLANS OF PHASE-I(PRIVANA-SOUTH) FALLING UNDER RESIDENTIAL COLONY
UNDER NEW INTEGRATED LICENSING POLICY(NILP) DATED 11.05.2022 ON LAND MEASURING 116.29625 ACRES (LICENCE NO. 219 OF 2023.DATED 25-10-23.) (AN AREA MEASURING 103.05625 ACRES MIGRATION FROM LICENCE NO. 27 OF 2012 DATED 02.04.2012 AND 13.24 ACRES AS FRESH AS FRESH APPLIED AREA) IN SECTOR -76 & 77, GURUGRAM MANESAR URBAN COMPLEX BEING DEVELOPED BY DLF LTD.IN COLLABORATION WITH LAND OWNERS AND IT`S ASSOCIATE COMPANIES

DESIGN ARCHITECTS

Arcop Associates Pvt. Ltd.,
Plot No.–36B,Institutional Area,
Sector–32,Gurgaon,
Haryana–122001.

SUBMISSION ARCHITECTS

RSMS ARCHITECTS PVT. LTD.
69,Nora Niwas Bhawani Kunj
(Behind D2), Vasant Kunj,
New Delhi–110070.
Tel.: 011–26898616,26898617
www.rsms–arch.com



TOWER–F
KEY PLAN

This is a "PROVISIONAL BUILDING PLAN" approved only for the purpose of inviting Objections from the journal public

S.T.P.(HQ.) Manohar Dudeja B.P.A.C.

S.T.P.(G) Member B.P.A.C.

DTP(HQ)

ATP(HQ)

PA

JD.

DINESH KUMAR JDT(HQ)
PA(HQ) Manager B.P.A.C.

TO BE READ IN CONJUNCTION WITH LETTER OF INTENT OFFICE MEMORANDUM NO. 14325 DATED 13.11.2023

ARCHITECTS SEAL & SIGNATURE

OWNER'S SEAL & SIGNATURE

Council of Architecture Registration No. CA/2005/72207

DLF Limited
Authorised Signatory

Land and Hand on the Public Health Engineering Department is requested to submit its comments in forwarding letter no. 3552/10 dated 31.12.2024

Superintending Engineer (HQ)
HSVP, Panchkula

JAN.–2025 | Scale : 1:100 | NORTH

Drawing Title:–
TYPICAL 10TH TO 16TH,18TH TO 19TH FLOOR PLAN
17TH REFUGE FLOOR
OF AREA CALCULATION
(TOWER-F)

Drawing No:
TF-03

1–06052025