From Director General

Fire Service, Haryana Panchkula

To **M/s** Essel Housing Projects Pvt Ltd

Sector 28 Gurugram

Memo No. FS/2020/196 dated : 10/08/2020

Subject : Approval of fire fighting scheme 15 mtrs. and Above from the fire safety point of view for Group A-Residential Building at meas. 5.56875 acres in Sector 28, Gurugram of M/s Essel Housing Projects Pvt. Ltd. :

Reference your Transaction Id 050262023002107 dated: 20/07/2020 on the subject cited above.

Your case for the approval of fire fighting scheme has been examined by the team of Fire Station Officers, Gurgaon Sector-29, .The means of escape and Fire Protection system were checked and found as per the National Building Code of India, Part- IV guidelines.Therefore your proposed fire fighting scheme is hereby approved as per following detail from the fire safety point of view with the following conditions:-

Tower Name	*Floor Detail*	*Terrace Height of Last Livable Floor(In Meters)*	*Ground Coverage*
Q1 (A)	G+21	80.25 Mtr.	972.108 Sq. Mtr.
Q2 (F)	G+21	80.25 Mtr.	972.108 Sq. Mtr.
R1 (B)	S+23	80.30 Mtr.	609.248 Sq. Mtr.
R2 (C)	S+23	80.30 Mtr.	656.341 Sq. Mtr.
R3 (D)	S+23	80.30 Mtr.	656.341 Sq. Mtr.
R4 (E)	S+23	80.30 Mtr.	609.248 Sq. Mtr.
S1 (EWS)	S+03	12.85 Mtr.	99.616 Sq. Mtr.

Tower Name	*Basement Level*	*Basement Area*	*Basement Remarks*
	Basement- 01	13685.909 Sq. Mtr.	
	Basement- 02	13286.882 Sq. Mtr.	

1) The proposed fire fighting scheme is approved as submitted in the building plan subject to the approval of building plan by the competent authority.
2) The approval of fire scheme by this office doesn't absolve the firm from his responsibility from all consequences, in case of fire due to any deficiencies or anything left out in the scheme submitted by you.
3) Overhead & underground water tanks provided for firefighting shall be so constructed in such a way that the domestic water tank shall filled from overflow of the fire Water tanks.
4) As soon as the installations of fire fighting arrangements are completed, the same may be got inspected/ tested and clearance should be obtained from this office.
5) If the infringement of Byelaws remains un- noticed the Authority reserves the right to amend the Plans/Fire Fighting Scheme as and when any such infringement comes to notice after giving an opportunity of being heard and the Authority shall stand Indemnified against any claim on this account.
6) If you fail to comply with any of the above terms & conditions you will be liable to be punished as per Chapter-III Section 31 Sub-Section 1 & 2 of Fire Act 2009 i.e. imprisonment for a term which may extend to three month or fine which may extend to five thousand rupees or both.
7) The staircase shall be made with the specified material enabling it non-slippery.
8) If the gap between ceiling and false ceiling is more than 800 mm then upright sprinkler and detectors above false ceiling & pendent sprinkler below false ceiling shall be installed in the building

Remarks:- Application Updated

Deputy Director (Technical)-I,
for Director General, Fire
Service, Haryana

Panchkula

Exercising the power of Director,Fire Services,Haryana

Digitally signed by GULSHAN KALRA
Date: 2020.08.10 10:41:26 +05:30
Reason: Digital Verification