


This is to certify that, the location of the project Suncity Heights Rohtak (Copy of license no. 65 of 2010 enclosed), situated at Khasra no. 7320 (3-2), 7475 (2-14), 7283 (1-0), 7286 (0-7), 7285 (0-6), 7287 (1-11), 10462/7288 (1-1), 10463/7289 (0-6), 7317 (4-7), 7319 (2-7), 16352/7322 (2-9), 16351/7322 (1-6), 16353/7323 (1-3), 16354/7323 (1-15) in Village Rohtak, Tehsil & Distt. Rohtak, Haryana is shown by 13 points (refer Map below)



ZONED AREA=42499.489 SQM.

## ZONING PLAN OF GROUP HOUSING COLONY AREA MEASURING 14.813 ACRES (LICENSE NO 65 OF 2010 DATED 21.08.2010) IN SECTOR 36-A, ROHTAK BEING DEVELOPED BY M/s SONIKA PROPERTIES PVT. LTD, M/S DIPESH REALTORS PVT. LTD., M/S SAMDASRSHI PROMOTERS & DEVELOPERS PVT. LTD. AND M/S NACHIKETA PROJECT PVT. LTD. IN COLLABORATION WITH M/s SONIKA PROPERTIES PVT. LTD.

### ZONING CLAUSES FOR GROUP HOUSING COLONY

#### FOR THE PURPOSE OF RULE 38(XIII) AND 48 (2) OF THE PUNJAB SCHEDULED ROADS AND CONTROLLED AREAS RESTRICTION OF UNREGULATED DEVELOPMENT RULES, 1965.

##### 1. SHAPE & SIZE OF SITE

The shape and size of the Group Housing Colony is in accordance with the demarcation plan shown as 1 to 43 as confirmed by DTP Rohtak via Encls No. 10421 dated 24.08.2010.

##### 2. TYPE OF BUILDING PERMITTED

The type of building permitted on this site shall be buildings designated in the form of attached residential purpose of any ancillary or apartment building, including community facilities, public amenities and public utility as may be prescribed and approved by the Director, Town and Country Planning, Haryana.

##### 3. GROUND COVERAGE AND FAR

a. Building shall only be permitted within the portion of the site marked as buildable zone and nowhere else.

b. The maximum coverage on ground floor shall be 35% and that on subsequent floors shall be 30% on the area of 14.813 acres.

c. The maximum FAR shall not exceed 175 on the area of 14.813 acres. However, it shall not include community buildings which shall be as per the prescribed norms, the building plan of which shall have to be approved from the Director, Town and Country Planning, Haryana.

##### 4. HEIGHT OF BUILDING

The height of the building block, subject of course to the provisions of the site coverage and FAR, shall be governed by the following:

a. The maximum height of the buildings shall not be more than as allowed by National Airport Authority and shall not exceed 1.3 times (the width of the road abutting) plus the front open space.

b. If a building abuts two or more streets of different widths, the building shall be deemed to face upon the street that has the greater width and the height of the building shall be regulated by the width of the street and may be continued to the height to a depth of 24 ft along the narrow street.

c. Building structures which rise to 30 meters or more in height shall be constructed if an objection certificate has been obtained from the National Airport Authority.

d. All building block(s) shall be constructed so as to maintain an intense distance not less than the set back required for each building according to the table below-

S.No	HEIGHT OF BUILDING (in meters)	SET BACK / OPEN SPACE TO BE LEFT AROUND BUILDINGS (in meters)
1	10	3
2	15	5
3	18	6
4	21	7
5	24	8
6	27	9
7	30	10
8	35	11
9	40	12
10	45	13
11	50	14
12	55 & above	15

e. To ensure fire safety and structural stability of the buildings of more than 60 meters in height, the developer shall submit the structural drawings duly vetted from reputed Institute like IIT Delhi, IIT Roorkee, IIT Chandigarh or IIT Kanpur etc. Fire safety plans needs to be vetted by the Institute of Engineers at Roorkee these certificates are to be obtained prior to starting the construction work of site.

f. If such interior or exterior open space is intended to be used for the benefit of more than one building belonging to the same owner, then the width of such open air space shall be the one specified for the tallest building as specified above.

##### 5. SUB-DIVISION OF SITE

a. The site of the Group Housing Colony shall be governed by the Haryana Apartment Ownership Act.

b. The site shall not be sub divided or fragmented in any manner whatsoever.

##### 6. GATE POST AND BOUNDARY WALL

Such boundary wall, railing or their combination, hedges or fences along with gates, and gate posts shall be constructed as per design approved by DTP Haryana. In addition to the perimeter an additional 100ft gate post exceeding 1.25 meters width may be allowed in the front and side boundary wall provided that no main gate shall be allowed to open on the sector road/public open space.

##### 7. DENSITY

a. The minimum density of the population provided in the colony shall be 100 FPA and the maximum be 600 FPA on the area of 14.813 acres.

b. For computing the density, the occupancy per main dwelling unit shall be taken as 1.0 persons and for service dweller one person per locum or one person per 60 sq. feet of living area whichever is more.

##### 8. ACCOMMODATION FOR SERVICE POPULATION

Adequate accommodation shall be provided for domestic servants and other service population of EWS. The number of such dwelling units for domestic servants shall not be less than 10% of the number of main dwelling units and the carpet area of such a unit if adjusted to the main units shall not be less than 143 sq.ft. In addition 15% of the total number of dwelling units having a minimum area of 200 sq.ft shall be earmarked for EWS category.

##### 9. PARKING

a. Parking spaces shall be provided @ 15 Equivalent Car Space for each dwelling unit. These parking spaces shall be allotted only to the flat holders and shall not be allotted, leased, sold or transferred to any third party. The area for parking per car shall be as under:-

- i) Basement - 55 sq.m.
- ii) Stalls - 30 sq.m.
- iii) Open - 25 sq.m.

b. At least 75% of the equivalent car spaces shall be provided in the form of covered parking. Further minimum 5% of the total parking will be made available to the EWS category flats.

c. The covered parking in the basement or in the form of multi level parking above ground level shall not be counted towards FAR. However, in case of multi level parking above the ground level the foot print of respective parking building block shall be counted towards ground coverage. In case of provision of mechanical parking in the basement floor upper stories, the total building height of the basement / upper floor shall not be more than 4.5 mtr. Other than the mechanical parking the floor to ceiling height in lower floor shall not be more than 2.4 mtr. below the tanking beam.

##### 10. LIFTS AND RAMPS

Ramps would be provided in Group Housing Building in case of 100% stand by generators along with adequate shelter over the provided ramping of lifts along with stairs. However, in case of buildings having more than four floors with 100% stand by generators along with sufficient generator would be provided. At least one lift shall be provided with minimum size of 1.89 M X 3.00 M. The clear width of the pump leading to the basement shall be 4.00 meters with an adequate slope not steeper than 1:12. The entry and exit shall be separate preferably at opposite ends.

##### 11. OPEN SPACES

Walks all the open spaces including those between the blocks and wings of buildings shall be developed, developed and landscaped according to the plan approved by the BTCP, Haryana. At least 10% of the total site area shall be developed as organized open space for walks and play ground.

##### 12. APPROVAL OF BUILDING PLANS

The building plans of the buildings to be constructed at site shall have to be got approved from the DTCP, Haryana (under section 8(2) of the Act 44 of 1965) before taking up the construction.

##### 13. BUILDING BY-LAWS

The construction of the building buildings that has governed by the building rules, applicable in the part IV of the Punjab Scheduled Roads and Controlled Areas, Restriction of Unregulated Development Rules, 1965. On the parts where such rules are silent or ambiguous or vague, the model building by-laws issued by the LSC, and given to the HBC shall be followed as may be approved by DTCP, Haryana.

##### 14. CONVENIENT SHOPPING

0.5% of the total area shall be reserved for local essential convenience shopping with the following conditions

a. The ground coverage of 100% with FAR of 100 is not permissible. However this will be a part of the permissible ground coverage and FAR of the Group Housing Colony.

b. The size of Kiosk/Shops shall not be more than 2.75 mtr x 2.75 mtr and 2.75 mtr x 8.25 mtr.

c. The height of Kiosk/Shops/Depot/Small Shop shall not exceed 4.00 meter.

##### 15. PROVISION OF COMMUNITY BUILDINGS

The community building shall be provided as per the composite norms in the Group Housing Scheme.

##### 16. BASEMENT

Four floor basements within the building area of the site provided a buffer with the ground and its property landscaped may be allowed. The basement may in addition to parking could be utilized for generator room, 1st floor, fire fighting pumps, water reservoir, electric substation, air compressing plants and laboratories. If they satisfy the public health requirements and for other purposes. Area under stairs (only for parking) and to personnel shall not be counted towards FAR. Basement shall not be used for storage/commercial purposes but will be used only for parking and auxiliary services of the main building and it is further stipulated that no other portions of basement will be permissible for uses other than those specified above.

##### 17. APPROACH TO SITE

The vehicle approach to the site and parking lots shall be planned and provided giving due consideration to the junctions of road with the surrounding roads to the satisfaction of the DTCP, Haryana.

##### 18. FIRE SAFETY MEASURES

a. The owner will ensure the provision of proper fire safety measures in the multi story buildings conforming to the provisions of Rules 1965 HBC and the same should be got certified from the competent authority.

b. Electric S.B. Station / generator room if provided shall be on solid ground near DTP. Control panel in ground floor in upper basement and it should be located on outer periphery of the building. The same should be got approved from the Civil Electrical Inspector Haryana.

##### 19. SOLAR WATER HEATING SYSTEM

The provision of solar water heating system shall be as per norms specified by HUDA and shall be made operational in each building block before applying for completion certificate.

##### 20. RAIN WATER HARVESTING SYSTEM

The rain water harvesting system shall be provided as per Central Ground Water Authority norms/Haryana Govt. norm as applicable.

21. The colonist shall obtain the clearance HBC as per the provisions of the Notification No. S.O. 1535(E) Dated 14.9.2006 issued by Ministry of Environment and Forest, Government of India before starting the construction/reconstruction works as per.

22. The colonist/owner shall use only Compacted Fluorescent Lamps/Fluorescent lamps for internal lighting as well as campus lighting.

23. You shall convey the ultimate power load requirement of your power utility to enable the provision of power to the concerned sites for transmission/distribution network. Job sheet as per the norms prescribed by the power utility in your project at the time of approval of Building plan.

DRG. NO. D.T.C.P. - 03002.

DATED - 04-11-2010

(P.S. SINGH)  
DTP (HO)  
Bhadrak

(U.S. REDHU)  
CTP (HR)

(T.G. GUPTA (AS))  
DTPC (HR)