


- NOTES  
 (1). ALL DIMENSIONS ARE IN M.M. UNLESS OTHERWISE SPECIFIED.  
 (2). INTERNAL WALL HT. OF TOILETS IS 2.1 M.  
 (3). ENTIRE BLDG. IS FULLY MECHANICALLY LIGHTED AND AIR CONDITIONED WITH 100% POWER BACKUP.  
 (4). CFL. WILL BE USED IN INTERNAL LIGHTING AS WILL AS CAMPUS LIGHTING  
 (5) FIRE SPRINKLING AS PER N.B.C. RULE.  
 (6) THIS BUILDING IS FULLY SPRINKLED

P1=(18.424x41.073)/2=378.364  
 P2=80.223x2.758=221.255  
 P3=6.985x16.137=112.716  
 P4=12.595x2.857=35.983  
 P5=(6.985x15.458)/2=53.987

PARKING AREA DETAIL :-  
 REQUIRED PARKING @1ECS/50=9736.72/50  
 =194.73 SAY 195 NOS.  
 REQ. PARKING AREA AT STREET LEVEL @ 15% OF 195=29.25 SAY 30  
 PARKING PROVIDED IN 1st BASEMENT=50X2=100 NOS. (AS SHOWN)  
 (TWIN LEVEL MECH. PARKING)

PARKING PROVIDED IN IInd BASEMENT=50X2=100 NOS. (AS SHOWN)  
 (TWIN LEVEL MECH. PARKING)

PROVIDED PARKING AREA AT STREET LEVEL  
 =P1+P2+P3+P4+P5  
 =378.364+221.255+112.716+35.983+53.987=802.305/25  
 = 32.09 SAY 32 NOS. (AS SHOWN)



SITE PLAN (SCALE 1:300)


The provision of solar water heating system shall be as per norms specified by HAREDA and shall be made operational in each building block before applying for an occupation certificate.  
 The rain water harvesting system shall be provided as per Central Ground Water Authority norms/Haryana Govt. notification as applicable.

The coloniser/owner shall use only Compact Fluorescent Lamps fittings for internal lighting as well as campus lighting.

**STRUCTURAL STABILITY CERTIFICATE**  
 THIS IS TO CERTIFY THAT THE STRUCTURAL DESIGN AND CONSTRUCTION OF THIS BUILDING SHALL BE CARRIED OUT AND PROVISIONS INCORPORATED IN ACCORDANCE WITH NATIONAL BUILDING CODES OF INDIA WITH RESPECT TO CONSTRUCTIONAL PRACTICES AND SAFETY NORMS FROM NATURAL HAZARDS INCLUDING EARTHQUAKES BASED ON PLOTS SOIL CONDITIONS,

**STANDARD GENERAL NOTES:-**

1. THE OWNER SHALL BE RESPONSIBLE FOR THE SAFETY FACTOR OF STRUCTURE AND FIRE
2. TOP OF WATER METER CHAMBER SHALL BE KEPT 6" ABOVE GROUND LVL.
3. LAST I.C. WILL BE CONNECTED TO THE MAIN SEWER IN ACCORDANCE WITH THE FLOW OF MAIN SEWER.
4. THE SEWER OF THE FACTORY WILL BE LAID IN SUCH A WAY THAT ITS LEVEL WITH THE SEWER OF CORPORATION AT LVL. OR HIGHER THAN THE INVERT LVL. OF CORPORATION.
5. ADEQUATE RAINWATER DISPOSAL PERCOLATING PITS OF 10000 SHALL BE PROVIDED ON GROUND LVL. & RAINWATER PIPES SHALL BE CONNECTED TO THE SAME.



**NOTE:-**

1. THE MALBA OF THE CONSTRUCTION WILL BE REMOVED WITH IN 15 DAYS OF THE STARTING NOT DONE IN THAT CASE THE LOCAL BODY SHALL REMOVE THE MALBA AND COST SHALL BE BORNE BY THE OWNER OF PLOT
2. DURING CONSTRUCTION IT IS MANDATORY ON THE PART OF THE OWNER TO PROPERLY SCREEN THE CONSTRUCTION SITE OF MAIN ROAD BY PLANS OF ERECTING A SCREEN WALL NOT LESS THAN 8'-0" IN HEIGHT FROM GROUND LEVEL WHICH IS TO BE PAINTED TO AVOID IN PLEASANT LOOK FROM ROAD SIDE IN ADDITION TO THIS A NET OR SAME OTHER PROTECTIVE MATERIAL SHALL BE HOISTED AT THE FACADES OF THE BUILDING TO ENSURE THAT ANY
3. NOISE RELATED ACTIVITIES WILL NOT BE TAKEN UP FOR CONSTRUCTION AT NIGHT AFTER 10 pm.
4. THE LIFT AND MACHINE ROOM SHALL BE AT PER IS: STANDARD

4. Gate of the well as per S/D

AREA DETAIL										BASEMENT AREA		
S.NO.	GR.FL.AR.	1ST FL.	2ND FL.	3RD FL.	4TH FL.	5TH FL.	6TH FL.	7TH FL.	8TH FL.	MUMTY	1ST BAS	2ND BAS
COVERED AREA	1679.042	1435.213	1497.879	1497.879	1497.879	1497.879	1130.21	687.67	139.674	38.415	2582.825	2582.825
FAR	1679.042	1435.213	1497.879	1497.879	1497.879		1130.21	687.67	139.674			
TOTAL PLOT AREA = 2.362 AC. OR			9558.66	SQ.MTS.								
PERMISSIBLE FAR @ 150% OF 1.604 ACRES = 649.15					9736.721	SQ.MTS.						
PERMISSIBLE G.F.L. AR. @ 40% OF 1.604 ACRES = 649.15					2596.459	SQ.MTS.						
PROPOSED GROUND FLOOR COVERED AREA =					1679.042	SQ.MTS.						
TOTAL ACHIEVED FAR					=	9565.446	SQ.MTS.					
TOTAL PROPOSED COVERED AREA					=	16267.39	SQ.MTS.					

**PROPOSED BUILDING PLAN OF COMMERCIAL COLONY**  
**MEASURING 2.362 ACRES (LICENCE NO. 278 OF 2007 DATED**  
**17.12.2007) IN SECTOR 61, GURGAON MANESAR URBAN**  
**COMPLEX BEING DEVELOPED BY ERA RESORTS PVT. LTD.**

SCALE:-

1:300

OWNER'S SIGN:-

For ERA Resorts Pvt. Ltd.  
 Director

ARCHITECT'S SIGN:-

For Amandeep (B.Arch)  
 CA/2000/20845  
 116, AKD Tower, Sector 14, Gurgaon  
 Ph: 9810322519/2376745

DRG. TITLE:- SITE PLAN