STATE ENVIRONMENT IMPACT ASSESSMENT AUTHORITY HARYANA Bay No. 55-58, Prayatan Bhawan, Sector-2, PANCHKULA.

Tel: 0172-2565232

E-mail Id: sciaa.hry@gmail.com

No. SEIAA(124)/HR/2020/384

Dated: <u>63</u>/09/2020

To

M/s French Build Mart Pvt. Ltd, Capital Group, 4th Floor, Veritas Tower, Sector-53, Golf Course Road, Gurugram, Haryana- 122002

Email Id- it@capitallimited.in

Subject:

Environment Clearance for Revision and Expansion of proposed Commercial Complex at Sector 66, Maidawas, Gurugram Haryana.

This letter is in reference to your application dated 07.11.2019 addressed to Member Secretary, SEIAA, Haryana received on 25.11.2019 and subsequent letter dated 18.12.2019 & 16.01.2020 seeking prior Environmental Clearance for the above project under the EIA Notification, 2006. The proposal has been appraised as per prescribed procedure in the light of provisions under the EIA Notification, 2006 on the basis of the mandatory documents enclosed with the application viz., Form-1, Form1-A, Conceptual Plan and additional clarifications furnished in response to the observations of the State Expert Appraisal Committee (SEAC) constituted by MoEF & CC, GoI vide their Notification dated 30.01.2019, in its meeting held on 04.12.2019 & 16.01.2020 awarded "Gold" rating / grading to the project.

[2] It is inter-alia, noted that the project involves Revision and Expansion of proposed Commercial Complex at Sector 66, Maidawas, Gurugram Haryana. The details of the project as given below:

given	·T		Expansion	Total			
Sr.	Particulars	Existing	l				
No.	Online Proposal No.	SIA/HR/MIS/124351/2019 A, 28°24' 13.13" N					
2.	Latitude	A. 28°24 13.13 N B. 28°24' 11.15" N C. 28°24' 09.98" N D. 28°24' 10.27" N E. 28°24' 11.17" N					
3.	Longitude	A. 77° 03' 35.36" E B. 77° 03' 36.96" E C. 77° 03' 31.45" E D. 77°03' 29.70" E E. 77°03' 35.39" E					
4.	Plot Area	8186.373 sqm					
	Net Plot Area	8186.372	8186.373	8186.373 sqm			
5. 6.	Proposed Ground Coverage	3272.129	1630.72	4907,118 sqm (59.9%)			
7.	Proposed FAR	28647.712 sqm					
8.	Non-FAR Area	15883.577 sqm					
9.	Total Built Up area	28755 sqm 12111.529 sqm 44531.289 sqm					



10.	Total Green Area with Percentage		1585.44	6 sqm	53.298 sqm	1638.744 sqm (20.017% of TPA)	
11.	Rain Water Harvesting Pits		06 No's				
12.	Total Parking		356 ECS		90 ECS	446 ECS	
13.	Organic Waste Converter		01 No's				
14.	Maximum Height of the Building		46.6 Meter				
15.	Power Requirement		1200KV	1200KW 175.31KW 1375.31		1375.310 KW	
16.	Power Backup (DG Sets)		750 X 1 250 X 1		1500X2	3000 KVA + 1000 KVA	
17.	Total Water Requirement		128		23	151 KLD	
18.	Domestic Water Requirement		116	-	04	120 KLD	
19.	Fresh Water Requirement		35		10.	36 KLD	
20.	Treated Water		39		63	102 KLD	
21.	Waste Water Generated		43		70	113 KLD	
22.	STP Capacity		52KLD		88KLD	140 KLD	
23.	Solid Waste Generated		435		251.48	686.48 Kg/Day	
24.	Biodegradable Waste		217.5		125.74	343.24Kg/Day	
25.	Number of Towers		A		В	A+B (2 No's)	
26.	Basement		03 No's				
27.	Stories		G+8 Floors		1 Floor	G+9 Floors	
28.	I .		Roof: 2. Wall:1.		Roof: 2.91 Wall:1.81	Roof: 2.91 W/sqm K Wall:1.81 W/sqm K	
. "	Total Cost of	i) Land) Land Cost		2.50 Crores		
29.	the project	ii) Const Cost		45.50 Crores			
30.	CER	CER		96 lakhs (2% of the total project cost)			
:	Incremental Load in respect of:						
31.	i) - PM ₁₀		0.810/ μg/m³				
31.	ii) SO ₂		0.760/ μg/m³				
	iii) NO ₂		0.21 / μg/m ³				
	iv) CO		0.236 μg/m ³				

[3] The State Expert Appraisal Committee, Haryana after due consideration of the relevant documents submitted by the project proponent and additional clarification furnished in response to its observations, have recommended the grant of Environmental Clearance for the project mentioned above, subject to compliance with the stipulated conditions. The State Environment Impact Assessment Authority in its 124th meeting held on 22.07.2020 after due deliberations the Authority decided to agree with the recommendations of SEAC to accord necessary Environmental Clearance for the project under Category 8(a) of EIA Notification 2006 subject to the strict compliance with the with the following stipulations mentioned below:-

Specific conditions:-

Sewage shall be treated in the STP based on latest Technology with tertiary treatment i.e. Ultra Filtration to achieve standards ordered by NGT. The Treated effluent from STP shall be recycled /reused for flushing. DG cooling and

The Project Proponent would devise a monitoring plan to the satisfaction of the State Pollution Control Board so as to continuously monitor the treated waste water being used for flushing in terms of faecal coli forms and other pathogenic

The Project Proponents would commission a third party study on the implementation of conditions related to quality and quantity of recycle and reuse 3. of treated water, efficiency of treatment systems, quality of treated water being supplied for flushing (specially the bacterial counts), comparative bacteriological studies from toilet seats using recycled treated waters and fresh waters for flushing, and quality of water being supplied through spray faucets attached to toilet seats

Separate wet and dry bins must be provided in each unit and at ground level for facilitating segregation of waste. Solid Waste shall be segregated into wet garbage and inert materials. Wet Garbage shall be composted in Organic waste convertor. Adequate area shall be provided for solid waste management within the premises which will include area for segregation, composting. The Inert waste from the

project will be sent to dumping site.

Traffic Management Plan as submitted shall be implemented in letter and spirit. Apart, a detailed traffic management and traffic decongestion plan shall be drawn up to ensure that the current level of service of the roads within a 05 kms radius of the project is marinated and improved upon after the implementation of the project. This plan should be based on cumulative impact of all development and increased habilitation being carried out or purpose to be carried out by the project or other agencies in this 05kms radius of the site in different scenarios of space and time

No tree cutting has been proposed in the instant project. A minimum of 1 tree for every 80sqm of land should be planted and maintained. The Existing trees will be counted for this purpose. The landscape planning should include plantation of native species. The species with heavy foliage, broad leaves and wide canopy cover are desirable. Water intensive and/or invasive species should not be used for landscaping. As proposed 1638.744 sqm (20.017% of Total Plot Area) shall be provided for green area development.

The Project Proponent shall obtain all necessary clearance/permission from all relevant agencies including town planning authority before commencement of work. All the construction shall be done in accordance with the local building

Consent to establish/operate for the project shall be obtained from the State Pollution Control Board as required under the Air (Prevention and Control of pollution) Act, 1981 and the Water (Prevention and control of pollution) Act,

The Approval of the Competent Authority shall be obtained for structural safety of building code due to earthquakes, adequacy of firefighting equipments etc. as per 9. National Building Code including protection measures from lightening etc.

The PP shall submit the approval of FAR under TOD Policy.

The PP shall use CER amount as per the schedule and undertaking submitted.

The PP shall not give occupation or possession before the water supply and sewage connection permitted by the competent authority.

The PP shall not give occupation or possession before the electricity connection

permitted by the competent Authority.

The PP shall obtain the permission regarding withdrawal of ground water from CGWA before the start of the project and also obtained the CTO from HSPCB after the approval from CGWA.


The PP shall carry out the quarterly awareness programs for the stakeholders of the

commercial colony/project.

06 Rain Water Harvesting pits shall be provided for rainwater usages as per the

COWB norms.

The PP shall install Digital water level recorder for monitoring the water recharge and carry out quarterly maintenance and cleaning af no RWH pits



The PP shall provide the Anti smog gun mounted on truck in the project for suppression of dust during construction & operational phase and shall use the treated water.

19. The PP shall take all preventive measures including water sprinkles to control dust during construction and operational phase.

The PP shall provide the mechanical ladder for use in case of emergency.

Any change in stipulations of EC will lead to Environment Clearance void-abinitio and PP will have to seek fresh Environment Clearance.

While carrying out the Air Dispersion Modeling, 25 PCU/hr in bound & out bound vehicles along with the emission & running hours of DG sets (6 hours) has been

considered as such project is existing.

Proposed capacity of 4 numbers of DG sets is 4000 KVA (2X1500 KVA, 1X750 KVA and 1X250 KVA) with HSD as fuel, follow the related Guidelines of Graded Response Action Plan (GRAP), National Clean Air Programme (NCAP) & strictures/injunctions passed by Hon'ble EPCA/NGT in regard of operation and nature of fuel for DG sets. The same stands for the running of DG sets during construction phase.

Required studies for Traffic Density & LOS of approach roads have been undertaken to ascertain that there would not be any congestion due to upcoming

Retrofitted emission control equipment will be installed having minimum specified PM capturing efficiency of atleast 70%, approved by one of the CPCB recognized

Total 6 numbers of rain water harvesting pits has been proposed considering rain fall intensity 90 mm/hr and taking run-off coefficient 0.9, 0.2 and 0.7 for roof-top area, green area and paved area respectively. Volume of twin bore recharge pit is 32.0 m3 having dimensions 4.0 m, 4.0 m and 2.0 m (1x b x h) respectively.

B. Statutory Compliance:

The project proponent shall obtain all necessary clearance/ permission from all [1] relevant agencies including town planning authority for ground coverage, FAR and should be in accordance with zoning plan approved by Competent Authority before commencement of work. All the construction shall be done in accordance with the local building byelaws. [2]

The approval of the Competent Authority shall be obtained for structural safety of buildings due to earthquakes, adequacy of firefighting equipment etc as per

National Building Code including protection measures from lightening etc.

The project proponent shall obtain forest clearance under the provisions of Forest [3] (Conservation) Act, 1986, in case of the diversion of forest land for non-forest purpose involved in the project.

The project proponent shall obtain clearance from the National Board for Wildlife,

if applicable:

The project proponent shall obtain Consent to Establish/Operate under the [5] provisions of Air (Prevention & Control of Pollution) Act, 1981 and the Water (Prevention & Control of Pollution) Act, 1974 from the Haryana State Pollution Control Board.

The project proponent shall obtain the necessary permission for drawl of ground water /surface water required for the project from the competent authority.

A certificate of adequacy of available power from the agency supplying power to the project along with the load allowed for the project should be obtained.

All other statutory clearances such as the approvals for storage of diesel from Chief Controller of Explosives, Fire Department, Civil Aviation Department shall be obtained, as applicable, by project proponents from the respective competent

The provisions of the Solid Waste (Management) Rules, 2016, e-Waste (Management) Rules, 2016, and the Plastics Waste (Management) Rules, 2016 shall be followed.

[10] The project proponent shall follow the ECBC Act/ECBC-Rules prescribed by Bureau of Energy Efficiency, Ministry of Power strictly in addition of bylaws of the State Government.

Air Quality Monitoring and Preservation I.

Notification GSR 94(E) dated 25.01.2018 of MoEF&CC regarding Mandatory Implementation of Dust Mitigation Measures for Construction and Demolition i) Activities for projects requiring Environmental Clearance shall be complied with.

A management plan shall be drawn up and implemented to contain the current ii)

exceedance in ambient air quality at the site.

The project proponent shall install system to carryout Ambient Air Quality monitoring for common/criterion parameters relevant to the main pollutants iii) released (e.g. PM₁₀ and PM_{2.5}) covering upwind and downwind directions during

Diesel power generating sets proposed as source of backup power should be of enclosed type and conform to rules made under the Environment (Protection) Act, iv) 1986. The height of stack of DG sets should be equal to the height needed for the combined capacity of all proposed DG sets. Use of ultra lowsulphur diesel. The location of the DG sets may be decided with in consultation with State Pollution

Construction site shall be adequately barricaded before the construction begins. Dust, smoke & other air pollution prevention measures shall be provided for the building as well as the site. These measures shall include screens for the building v) under construction, continuous dust/ wind breaking walls all around the site (at least 3 meter height). Plastic/tarpaulin sheet covers shall be provided for vehicles bringing in sand, cement, murram and other construction materials prone to causing dust pollution at the site as well as taking out debris from the site.

Sand, murram, loose soil, cement, stored on site shall be covered adequately so as

to prevent dust pollution.

Wet jet shall be provided for grinding and stone cutting.

Unpaved surfaces and loose soil shall be adequately sprinkled with water to vii)

viii)

All construction and demolition debris shall be stored at the site (and not dumped on the roads or open spaces outside) before they are properly disposed. All ix) demolition and construction waste shall be managed as per the provisions of the Construction and Demolition Waste Rules 2016.

The diesel generator sets to be used during construction phase shall be ultra lowsulphur diesel type and shall conform to Environmental (Protection) prescribed x)

for air and noise emission standards.

The gaseous emissions from DG set shall be dispersed through adequate stack height as per CPCB standards. Acoustic enclosure shall be provided to the DG sets xi) to mitigate the noise pollution. Ultra low sulphur diesel shall be used. The location of the DG set and exhaust pipe height shall be as per the provisions of the Central Pollution Control Board (CPCB) norms.

For indoor air quality the ventilation provisions as per National Building Code of xii)

India.

Water Quality Monitoring and Preservation

The natural drain system should be maintained for ensuring unrestricted flow of water. No construction shall be allowed to obstruct the natural drainage through i) the site, on wetland and water bodies. Check dams, bio-swales, landscape, and other sustainable urban drainage systems (SUDS) are allowed for maintaining the drainage pattern and to harvest rain water.

Buildings shall be designed to follow the natural topography as much as possible.


Minimum cutting and filling should be done.

Total fresh water use shall not exceed the proposed requirement as provided in the project details. The per capita supply should adhere to NBC 2016 and CGWA

Notification dated 12.12.2018.

The quantity of fresh water usage, water recycling and rainwater harvesting shall be measured and recorded to monitor the water balance as projected by the project proponent. The record shall be submitted to the Regional Office, MoEF&CC as well as to SEIAA, Haryana along with six monthly Monitoring reports.

A certificate shall be obtained from the local body supplying water, specifying the total annual water availability with the local authority, the quantity of water



øi)

already committed, the quantity of water allotted to the project under consideration and the balance water available. This should be specified separately for ground water and surface water sources, ensuring that there is no impact on other users.

vi) At least 20% of the open spaces as required by the local building bye-laws shall be pervious. Use of Grass pavers, paver blocks with at least 50% opening, landscape

etc. would be considered as pervious surface.

Installation of dual pipe plumbing for supplying fresh water for drinking, cooking and bathing etc and other for supply of recycled water for flushing, landscape irrigation, car washing, thermal cooling, conditioning etc. shall be done.

Use of water saving devices/ fixtures (viz. low flow flushing systems; use of low flow faucets tap aerators etc.) for water conservation shall be incorporated in the

building plan.

Separation of grey and black water should be done by the use of dual plumbing ix) system. In case of single stack system separate recirculation lines for flushing by giving dual plumbing system be done. x)

Water demand during construction should be reduced by use of pre-mixed

concrete, curing agents and other best practices referred.

The local bye-law provisions on rain water harvesting should be followed. If local byelaw provision is not available, adequate provision for storage and recharge should be followed as per the Ministry of Urban Development Model Building Byelaws, 2016. Rain Water Harvesting pits shall be provided for ground water recharging as per the CGWB norms.

A rain water harvesting plan needs to be designed where the recharge bores of minimum one recharge bore per 5,000 square meters of built up area and storage capacity of minimum one day of total fresh water requirement shall be provided. In areas where ground water recharge is not feasible, the rain water should be harvested and stored for reuse. The ground water shall not be withdrawn without approval from the Competent Authority.

All recharge should be limited to shallow aquifer. (iiix

No ground water shall be used during construction phase of the project. xiv)

Any ground water dewatering should be properly managed and shall conform to the approvals and the guidelines of the CGWA in the matter. Formal approval shall be taken from the CGWA for any ground water abstraction or dewatering.

The quantity of fresh water usage, water recycling and rainwater harvesting shall be measured and recorded to monitor the water balance as projected by the project proponent. The record shall be submitted to the Regional Office, MoEF&CC along with six monthly Monitoring reports.

xvii) Sewage shall be treated in the STP with tertiary treatment. The treated effluent from STP shall be recycled/re-used for flushing, AC make up water and gardening. As proposed, no treated water shall be disposed in to municipal drain.

xviii) No sewage or untreated effluent water would be discharged through storm water

Onsite sewage treatment of capacity of treating 100% waste water to be installed. The installation of the Sewage Treatment Plant (STP) shall be certified by an independent expert and a report in this regard shall be submitted to the Ministry before the project is commissioned for operation. Treated waste water shall be reused on site for landscape, flushing, cooling tower, and other end-uses. Excess treated water shall be discharged as per statutory norms notified by Ministry of Environment, Forest and Climate Change. Natural treatment systems shall be

Periodical monitoring of water quality of treated sewage shall be conducted. Necessary measures should be made to mitigate the odour problem from STP.

Sludge from the onsite sewage treatment, including septic tanks, shall be collected, conveyed and disposed as per the Ministry of Urban Development; Central Public Health and Environmental Engineering Organization (CPHEEO) Manual on Sewerage and Sewage Treatment Systems, 2013.

III. Noise Monitoring and Prevention

Ambient noise levels shall conform to residential area/commercial area both i) during day and night as per Noise Pollution (Control and Regulation) Rules, 2000. Incremental pollution loads on the ambient air and noise quality shall be closely monitored during construction phase. Adequate measures shall be made to reduce ambient air and noise level during construction phase, so as to conform to the

Noise level survey shall be carried as per the prescribed guidelines and report in this regard shall be submitted to Regional Officer of the Ministry as a part of sixii)


Acoustic enclosures for DG sets, noise barriers for ground-run bays, ear plugs for operating personnel shall be implemented as mitigation measures for noise impact iii) due to ground sources.

Energy Conservation Measures IV.

- Compliance with the Energy Conservation Building Code (ECBC) of Bureau of Energy Efficiency as per ECBC Act, 2017 read with ECBC Rules, 2018 shall be ensured. Buildings in the States which have notified their own ECBC, shall i) comply with the State ECBC also which is in no case should be less than 25% as prescribed.
- Outdoor and common area lighting shall be LED.
- Concept of passive solar design that minimize energy consumption in buildings by using design elements, such as building orientation, landscaping, efficient building ii) iii) envelope, appropriate fenestration, increased day lighting design and thermal mass etc. shall be incorporated in the building design. Wall, window, and roof R & Uvalues shall be as per ECBC specifications.
- Energy conservation measures like installation of CFLs/ LED for the lighting the area outside the building should be integral part of the project design and should be iv)
- in place before project commissioning. Solar, wind or other Renewable Energy shall be installed to meet electricity generation equivalent to 1% of the demand load or as per the state level/ local v) building bye-laws requirement, whichever is higher.
- Solar power shall be used for lighting in the apartment to reduce the power load on grid. Separate electric meter shall be installed for solar power. Solar water heating vi) shall be provided to meet 20% of the hot water demand of the commercial and institutional building or as per the requirement of the local building bye-laws, whichever is higher. Residential buildings are also recommended to meet its hot water demand from solar water heaters, as far as possible.
- The PP will submit report indicating compliance of each parameter of ECBC requirement and submit quantification saving report for each component.

Waste Management ٧.

- A certificate from the competent authority handling municipal solid wastes, indicating the existing civic capacities of handling and their adequacy to cater to i) the M.S.W. generated from project shall be obtained.
- Disposal of muck during construction phase shall not create any adverse effect on the neighboring communities and be disposed taking the necessary precautions for ii) general safety and health aspects of people, only in approved sites with the approval of competent authority.
- Separate wet and dry bins must be provided in each unit and at the ground level for facilitating segregation of waste. Solid waste shall be segregated into wet garbage iii) and inert materials.
- Organic Waste Converter within the premises with a minimum capacity of 0.5 kg /person/day must be installed. Leaves to be put in earmarked pits for converting iv) them into compost to be used as manure.
- All non-biodegradable waste shall be handed over to authorized recyclers for which a written tie up must be done with the authorized recyclers.
 - Any hazardous waste generated during construction phase, shall be disposed of as per applicable rules and norms with necessary approvals of the State Pollution Control Board.
 - Use of environment friendly materials in bricks, blocks and other construction materials, shall be required for at least 20% of the construction material quantity. These include Fly Ash bricks, hollow bricks, AACs, Fly Ash Lime Gypsum blocks, Compressed earth blocks, and other environment friendly materials.



- viii) Fly ash should be used as building material in the construction as per the provision of Fly Ash Notification of September, 1999 and amended as on 27th August, 2003 and 25th January, 2016. Ready mixed concrete must be used in building
- Any wastes from construction and demolition activities related thereto shall be ix) managed so as to strictly conform to the Construction and Demolition Rules, 2016.
- Used CFLs and TFLs should be properly collected and disposed off/sent for x) recycling as per the prevailing guidelines/ rules of the regulatory authority to avoid mercury contamination.

VI. Green Cover

i) No tree can be felled/transplant unless exigencies demand. Where absolutely necessary, tree felling shall be with prior permission from the concerned regulatory authority. Old trees should be retained based on girth and age regulations as may be prescribed by the Forest Department. Plantations to be ensured species (cut) to species (planted).

ii) A minimum of 1 tree (5' tall) for every 80 sqm of land should be planted and maintained. The existing trees will be counted for this purpose. The landscape planning should include plantation of native species. The species with heavy foliage, broad leaves and wide canopy cover are desirable. Water intensive and/or

invasive species should not be used for landscaping.

Where the trees need to be cut with prior permission from the concerned local iii) Authority, compensatory plantation in the ratio of 1:10 (i.e. planting of 10 trees for every 1 tree that is cut) shall be done and maintained. Plantations to be ensured species (cut) to species (planted). Area for green belt development shall be provided as per the details provided in the project document. iv)

Topsoil should be stripped to a depth of 20 cm from the areas proposed for buildings, roads, paved areas, and external services. It should be stockpiled appropriately in designated areas and reapplied during plantation of the proposed

vegetation on site.

Transport VII.

A comprehensive mobility plan, as per MoUD best practices guidelines (URDPFI), i) shall be prepared to include motorized, non-motorized, public, and private networks. Road should be designed with due consideration for environment, and safety of users. The road system can be designed with these basic criteria.

a) Hierarchy of roads with proper segregation of vehicular and pedestrian

traffic.

Traffic calming measures. b)

c) Propen design of entry and exit points

d) Parking norms as per local regulation

- Vehicles hired for bringing construction material to the site should be in good ii) condition and should have a pollution check certificate and should conform to applicable air and noise emission standards be operated only during non-peak hours.
- A detailed traffic management and traffic decongestion plan shall be drawn up to ensure that the current level of service of the roads within a 05 kms radius of the project is maintained and improved upon after the implementation of the project. This plan should be based on cumulative impact of all development and increased habitation being carried out or proposed to be carried out by the project or other agencies in this 05 Kims radius of the site in different scenarios of space and time and the traffic management plan shall be duly validated and certified by the State Urban Development department and the P.W.D./ competent authority for road augmentation and shall also have their consent to the implementation of components of the plan which involve the participation of these departments.

VIII. Human Health Issues

All workers working at the construction site and involved in loading, unloading, i) carriage of construction material and construction debris or working in any area with dust pollution shall be provided with dust mask.

For indoor air quality the ventilation provisions as per National Building Code of ii)

Emergency preparedness plan based on the Hazard identification and Risk Assessment (HIRA) and Disaster Management Plan shall be implemented. iii)

Provision shall be made for the housing of construction labour within the site with all necessary infrastructure and facilities such as fuel for cooking, mobile toilets, iv) mobile STP, safe drinking water, medical health care, crèche etc. The housing may be in the form of temporary structures to be removed after the completion of the

Occupational health surveillance of the workers shall be done on a regular basis.

A First Aid Room shall be provided in the project both during construction and v) vi) operations of the project.

Corporate Environment Responsibility IX.

The project proponent shall comply with the provisions contained in this Ministry's OM vide F.No. 22-65/2017-IA.III dated 1st May 2018, as applicable, regarding i)

The company shall have a well laid down environmental policy duly approved by the Board of Directors. The environmental policy should prescribe for standard operating procedures to have proper checks and balances and to bring into focus ii) any infringements/ deviation/ violation of the environmental/ forest/ wildlife norms/ conditions. The company shall have defined system of reporting infringements/ deviation/ violation of the environmental/ forest/ wildlife norms/ conditions and/ or shareholders/ stake holders. The copy of the board resolution in this regard shall be submitted to the MoEF&CC as a part of six-monthly report.

A separate Environmental Cell both at the project and company head quarter level, with qualified personnel shall be set up under the control of senior Executive, who iii)

will directly to the head of the organization. Action plan for implementing EMP and environmental conditions along with responsibility matrix of the company shall be prepared and shall be duly approved by competent authority. The year wise funds earmarked for environmental iv) protection measures shall be kept in separate account and not to be diverted for any other purpose. Year wise progress of implementation of action plan shall be reported to the Ministry/Regional Office along with the Six Monthly Compliance

PP must submit the Balance sheet/Account statement duly attested & signed by the Chartered Accountant showing the dispersal of funds in said schemes along with the "Six Monthly Compliance Report" positively.

Miscellaneous X.

ii)


The project proponent shall prominently advertise it at least in two local newspapers of the District or State, of which one shall be in the vernacular i) language within seven days indicating that the project has been accorded environment clearance and the details of MoEF&CC/SEIAA website where it is

The copies of the environmental clearance shall be submitted by the project proponents to the Heads of local bodies, Panchayats and Municipal Bodies in addition to the relevant offices of the Government who in turn has to display the same for 30 days from the date of receipt.

The project proponent shall upload the status of compliance of the stipulated environment clearance conditions, including results of monitored data on their website and update the same on half-yearly basis.

The project proponent shall submit six-monthly reports on the status of the compliance of the stipulated environmental conditions on the website of the ministry of Environment, Forest and Climate Change at environment clearance portal and soft copy of the same to the SEIAA, Haryana.

The project proponent shall submit the environmental statement for each financial year in Form-V to the concerned State Pollution Control Board as prescribed under the Environment (Protection) Rules, 1986, as amenast subsequently and put on the



website of the company.

The project proponent shall inform the Regional Office as well as the Ministry, the date of financial closure and final approval of the project by the concerned authorities, commencing the land development work and start of production operation by the project.

The project authorities must strictly adhere to the stipulations made by the State

Pollution Control Board and the State Government.

The project proponent shall abide by all the commitments and recommendations viii) made in the form-IA, Conceptual Plan and also that during their presentation to the

Expert Appraisal Committee.

No further expansion or modifications in the plan shall be carried out without prior ix) approval of the Ministry of Environment, Forests and Climate Change The project proponent shall seek fresh (MoEF&CC)/SEIAA, Haryana. environmental clearance under EIA notification 2006 if at any stage there is change of area of this project.

Any change in planning of the approved plan will leads to Environment Clearance x)

void-ab-initio and PP will have to seek fresh Environment Clearance

The PP should give unambiguous affidavit giving land promoters in accordance xi) with your ownership and possession of land legal the case referred for Environment Clearance to SEIAA.

Concealing factual data or submission of false/fabricated data may result in revocation of this environmental clearance and attract action under the provisions

of Environment (Protection) Act, 1986.

The Ministry/SEIAA may revoke or suspend the clearance, if implementation of

any of the above conditions is not satisfactory.

The Ministry/SEIAA reserves the right to stipulate additional conditions if found necessary. The Company in a time bound manner shall implement these conditions.

The Regional Office of this Ministry shall monitor compliance of the stipulated xv) conditions. The project authorities should extend full cooperation to the officer (s) of the Regional Office by furnishing the requisite data / information/monitoring

The above conditions shall be enforced, inter-alia under the provisions of the Water (Prevention & Control of Pollution) Act, 1974, the Air (Prevention & Control of Pollution) Act, 1981, the Environment (Protection) Act, 1986, Hazardous and Other Wastes (Management and Transboundary Movement) Rules, 2016 and the Public Liability Insurance Act, 1991 along with their amendments and Rules and any other orders passed by the Hon'ble Supreme Court of India/High Courts and any other Court of Law relating to the subject matter.

The Project Proponent shall ensure the commitments made in Form-1A, Form-1A, (iivx EFA/EMP and other documents submitted to the SEIAA for the protection of environment and proposed environmental safeguards are complied with in letter and spirit. In case of contradiction between two or more documents on any point, the most environmentally friendly commitment on the point shall be taken as

commitment by project proponent.

The Project proponent shall not violate any judicial orders/pronouncements issued xviii)

by any Court/Tribunal.

Under the provisions of Environment (Protection) Act, 1986, legal action shall be xix) initiated against the Project Proponent if it was found that construction of the project has been started before obtaining prior Environmental Clearance.

Any appeal against the this Environmental Clearance shall lie with the National XX) Green Tribunal, if preferred, within a period of 30 days as prescribed under

Section 16 of the National Green Tribunal Act, 2010:

The project proponent shall put in place Corporate Environment Policy as mentioned in MoEF, GoI OM No. J-11013/41/2006-IA II (I) dated 26.4.2012 xxi) within 3 months period. Latest Corporate Environment Policy should be submitted to SEIAA within 3 months of issuance of this letter.

The project proponent shall ensure the compliance of Forest Department, Haryana xxii)

Notification no. S.O.121/PA2/1900/S.4/97 dated 28.11.1997.

The project proponent is responsible for compliance of all conditions in Environmental Clearance letter and project proponent can not absolve himself xxiii) /herself of the responsibility by shifting it to any contractor engaged by project

proponent. Besides the developer/applicant, the responsibility to ensure the compliance of Environmental Safeguards/conditions imposed in the Environmental Clearance letter shall also lie on the licensee/licensees in whose name/names the license/CLU has been granted by the Town & Country Planning Department,

The project proponent shall seek fresh Environmental clearance if at any stage xxiv)

there is change in the planning of the proposed project.

In view of the severe constrains in water supply augmentation in the region and sustainability of water resources, the developer will submit the NOC from CGWA xxv) specifying water extraction quantities and assurance from HUDA/, utility provider indicating source of water supply and quantity of water with details of intended use of water - potable and non-potable. Assurance is required for both construction and operation stages separately. It shall be submitted to the SEIAA and RO, MOEF, Chandigarh before the start of construction.

Overexploited groundwater and impending severe shortage of water supply in the region requires the developer to redraw the water and energy conservation plan. xxvi) Developer shall reduce the overall footprint of the proposed development. Project proponent shall incorporate water efficiency /savings measures as well as water reuse/recycling within 3 months and before start of construction to the SEIAA,

Haryana and RO, MOEF, GOI, Chandigarh.

xxvii) Vertical fenestration shall not exceed 60% of total wall area.

xxviii) The Project Proponent shall keep the plinth level of the building blocks sufficiently above the level of the approach road to the Project. Levels of the other areas in the Projects shall also be kept suitably so as to avoid flooding.

The project proponent shall construct a sedimentation basin in the lower level of the project site to trap pollutant and other wastes during rains. xxix)

The project proponent shall provide proper rasta of proper width and proper strength for the project before the start of construction. The project proponent shall provide fire control room and fire officer for building xxx)

above 30 meter as per National Building Code. xxxi)

The project proponent shall discharge excess of treated waste water/storm water in the public drainage system and shall seek permission of HUDA before the start of xxxii)

The project proponent shall maintain the distance between STP and water supply xxxiii)

The project proponent shall ensure that the stack height is 6 meter more than the (vixxx For disinfection of the treated wastewater ultra-violet radiation or ozonization

xxxv)

The project proponent shall strive to minimize water in irrigation of landscape by minimizing grass area, using native variety, xeriscaping and mulching, utilizing (ivxxx efficient irrigation, system, scheduling irrigation only after checking evapo-

xxxvii) The Project Proponent shall use zero ozone depleting potential material in insulation, refrigeration, air-conditioning and adhesive. Project Proponent shall also

provide Halon free fire suppression system. xxxviii) Standards for discharge of environmental pollutants as enshrined in various schedules of rule 3 of Environment Protection Rule 1986 shall be strictly complied

The project proponent shall ensure that the of DG sets is more than the highest tower and also ensure that the emission standards of noise and air are within the -xxxix) CPCB latest prescribed limits. Noise and Emission level of DG sets greater than 800 KVA shall be as per CPCB latest standards for high capacity DG sets.

All electric supply exceeding 100 amp, 3 phase shall maintain the power factor

between 0.98 lag to 1 at the point of connection.

The project proponent shall not use fresh water for HVAC and DG cooling. Air based HVAC system should be adopted and only treated water shall be used by project proponent for cooling, if it is at all needed. The Project Proponent shall also use evaporative cooling technology and double stage cooling system for HVAC in order to reduce water consumption. Further temperature, relative humidity during summer and winter seasons should be kept at optimal level. Variable speed drive, best Co-efficient of Performance (Cop), as well as optimal Integrated Point Load

xI) xli)

Value and minimum outside fresh air supply may be resorted for conservation of power and water. Coil type cooling DG Sets shall be used for saving cooling water consumption for water cooled DG Sets.

xlii) The project proponent shall ensure that the transformer is constructed with high quality grain oriented, low loss silicon steel and virgin electrolyte grade copper. The project proponent shall obtain manufacturer's certificate also for that.

xliii) The project proponent shall ensure that exit velocity from the stack should be sufficiently high. Stack shall be designed in such a way that there is no stack

down-wash under any meteorological conditions.

The validity of this environment clearance letter is valid up to 7 years from the date of issuance of EC letter. The environment clearance conditions applicable till life space project in case of Residential project will continue to apply. The resident welfare association/Housing co-operative societies shall responsible to comply conditions laid down in EC. In case of violation the action would be taken as per the laid down law of land. Compliance report should be sent to this office till life of the project.

xlv) If project is not completed within the validity period then the project proponent shall submit the application for extension of validity within one month before the

lapse of validity period of Environment Clearance i/e. 7 years.

xlvi) The project proponent should intimate to the Authority well before shifting their address of communication.

0/

State Level Environment Impact Assessment Authority, Haryana, Panchkula.

Endst. No. SEIAA(124)/HR/2020/385-387

Dated: <u>03</u>/09/2020

A copy of the above is forwarded to the following:

The Additional Director (IA Division), MoEF&CC, Gol, Indra Paryavaran Bhavan, Zor bagh Road-New Delhi.

The Regional office, Ministry of Environment, Forests & Climate Change, Govt.

of India, Bay's no. 24-25, Sector 31-A, Dakshin Marg Chandigarh.

The Chairman, Haryana State Pollution Control Board, C-11, Sector-6, Panchkula.

de

State Level Environment Impacts
Assessment Authority, Haryana, Panchkula.