


**ZONING PLAN OF COMMERCIAL COLONY AREA MEASURING 2.625 ACRES (LICENCE NO. 79 OF 2018 DATED 17/11/2018) IN SECTOR-34, SOHNA BEING DEVELOPED BY SMT. MONIKA RAIZADA W/o SH. NAVEEN RAIZADA IN COLLABORATION WITH NAVI ESTATES LLP.**



- For purpose of Code 1.2 (xcvi) & 6.1 (1) of the Haryana Building Code, 2017, amended from time to time.
- SHAPE & SIZE OF SITE.  
The shape and size of site is in accordance with the demarcation plan shown as A to J as confirmed by DTP, Gurugram vide Endst No. 12040 dated 28.12.2017.
- LAND USE.  
The type of commercial buildings permissible in this site shall conform to the provisions of the commercial zone as provided in Appendix 'B' to the Final Development Plan of Sohna, as amended from time to time, as applicable. Not less than 50% of the permissible FAR should be used for neighborhoods shopping needs.
- TYPE OF BUILDING PERMITTED AND LAND USE ZONES.  
The type of building permitted in this site i.e. Shopping Mall, Multiplex, Departmental Store, Integrated Commercial, Service Apartment, Starred Hotel/Unstarred Hotel, Offices & other allied uses etc.
- SITE COVERAGE AND FLOOR AREA RATIO (FAR)  
(a) The building or buildings shall be constructed only within the portion of the site marked as Building zone as explained above, and nowhere else.  
(b) The maximum coverage on ground floor shall be 60 % on the area of 2.5155 acres.  
(c) Maximum Permissible FAR shall be 175 on the area of 2.5155 acres.
- HEIGHT OF BUILDING.  
The height of the building block, subject of course to the provisions of the site coverage and FAR, shall be governed by the following:-  
(a) The maximum height of the buildings shall be as Chapter 6.3 (3) (ii) and Chapter 6.3 (3) (vii).  
(b) The plinth height of building shall be as per Chapter 7.3.  
(c) All building block(s) shall be constructed so as to maintain an inter-se distance not less than the set back required for each building according to the table below:
- That the coloniser/owner shall obtain the clearance/NOC as per the provisions of the Notification No. S.O. 1533 (F) Dated 14.9.2006 issued by Ministry of Environment and Forest, Government of India before starting the construction, if applicable.
- That the rain water harvesting system shall be provided as per Central Ground Water Authority norms/Haryana Government notification as applicable.
- That the coloniser/owner shall use only Light-Emitting Diode lamps (LED) fitting for internal lighting as well as Campus lighting.
- That the coloniser/owner shall strictly comply with the directions issued vide Notification No. 19/6/2016 dated 31.03.2016 issued by Haryana Government Renewable Energy Department.
- That coloniser/owner shall ensure the installation of Solar Power Plant as per provisions of Haryana Solar Power Policy, 2016 issued by Haryana Government Renewable Energy Department vide Notification No. 19/4/2016 s Power dated 14.03.2016.
- That the coloniser/owner shall ensure the installation of Solar Photovoltaic Power Plant as per the provisions of order No. 22/52/2005-Power dated 22.03.2016 issued by Haryana Government Renewable Energy Department.
- That you shall submit the permission from competent authority for taking the direct access from the Sohna Gurugram Road before approval of building plans.
- GENERAL  
(a) Among other plans and papers detailed elevations of buildings along all sides exposed to public view shall be drawn according to scale as mentioned in the Haryana Building Code-2017.  
(b) The water storage tanks and other plumbing works etc. shall not be exposed to view each face of building but shall be suitably encased.  
(c) No applied decoration like inscription, crosses, names of persons or buildings are permitted on any external face of the building.  
(d) Garbage collection center of appropriate size shall be provided within the site.  
(e) Color trade emblem and other symbols shall be subject to the approval of the Competent Authority.

DRG No. DTCP- 6701 Dated 29-11-2018

(RAM AVATAR BASSI)  
AD (HQ)

(BALWANT SINGH)  
SD (HQ)

(SANJAY NARAG)  
ATP (HQ)

(RAJESH KAUSHIK)  
DTP (HQ)

(DEVENDRA NIMBOKAR)  
STP(M)HQ

(JITENDER SIHAG)  
CTP (HR)

(K.MAKRAND PANDURANG, IAS)  
DTCP (HR)