








(HITESH SHARMA)
STP(M)HQ

(P.P.SINGH)
CTP(HR)

(K.MAKRAND PANDURANG, IAS)
DTCP(HR)

(SANJAY NARANG)
ATP(HQ)

(DINESH KUMAR)
SD(HQ)

AREA CHART

PROPOSED GROUND FLOOR FAR = (A)
= 71.371 Sq.Mt.

PROPOSED FIRST FLOOR FAR
= A-(B+C)
= 71.371-(2.650 X 4.150 + 1.550X1.550)
= 71.371-(10.99+2.402)
= 57.979 Sq.Mt.

PROPOSED SECOND FLOOR FAR
= SAME AS FIRST FLOOR AREA
= 57.979 Sq.Mt.

PROPOSED THIRD FLOOR FAR
= SAME AS SECOND FLOOR AREA
= 57.979 Sq.Mt.

PROPOSED FOURTH FLOOR FAR
= SAME AS THIRD FLOOR AREA
= 57.979 Sq.Mt.

TOTAL FAR =
(GROUND+FIRST+SECOND+THIRD+FOURTH)
= 71.371 + 57.979 + 57.979 + 57.979 + 57.979
= 303.287 Sq.Mt.

TOTAL NON FAR

STAIRCASE WELL & MACHINE ROOM
= (TYP. FL. STAIRCASE X 3 + MUMTY +
MACHINE ROOM)
= (BX3) + (D+E)
= (2.650X4.150X4) + (2.95X4.55 + 1.81X2.010)
= 43.99 + 13.42 + 3.63
= 61.04

PROPOSED NON FAR BASEMENT
= 71.371 Sq.Mt.

TOTAL NON FAR = 61.04 + 71.371 = 132.411 Sq.Mt.

DOOR WINDOW SCHEDULE				
S.NO.	TYPE	SIZE	LEVEL	LEVEL
1	D1	1200 x 2400	---	2400
2	D2	1200 x 2400	---	2400
3	D3	1200 x 2400	---	2400
4	D4	750 x 2100	---	2100
5	SD-01	3190 x 2950	---	2950
6	W1	3645 x 3700	---	3700
7	W2	3645 x 2950	---	2950
8	W2a	3645 x 2650	---	2650
9	W3	1200 x 1350	1050	2400
10	W4	600 x 1200	1200	2400
11	W5	3190 x 2950	---	2950
12	W5a	3190 x 2650	---	2650

M/s GILLSON CHITS PVT. LTD. IN COLLABORATION WITH
M/s BRISK INFRASTRUCTURE & DEVELOPERS PVT. LTD.

STANDARD DESIGN COMMERCIAL PLOTTED COLONY OVER AN AREA
MEASURING 3.6423 ACRES IN THE REVENUE ESTATE OF VILLAGE-
CHAUMA IN SECTOR -109 , GURUGRAM- MANESAR URBAN COMPLEX

OWNERS SIGNATURE

PLANS & ELEVATIONS

SHEET

SCO NO. -42

scale-1:100

Kanwar Gaurav
KANWAR GAURAV
ARCHITECT
CA/2016/76162

SWAIT ARCH
"SWAIT KAMAL"
ARCHITECTS, ENGINEERS
& INTERIOR DESIGNERS
E-10B1, SARASWATI VIHAR, DELHI
WWW.SWAITARCH.COM

DRG. NO.
13