



DAKSHIN HARYANA BIJLI VITRAN NIGAM

(A Government of Haryana Undertaking)
Office of the gmol

Superintending Engineer 'OP' Circle
Mehrauli Road, Gurgaon.



0124-2322427

Fax
No.

0124-2306590

e-mail se.gurgaon@gmail.com

To:

✓ M/s Experion Developers Pvt. Ltd.
32nd (Milestones, Sector-15, Part-II,
Gurgaon.

Memo No. Ch-05

/PC-GC- 339 /City

Dated: 21/10/2016

Sub:

Approval of sanction of 3524KW or 3916KVA ultimate load to M/s
Experion Developers Pvt. Ltd. 32nd (Milestones, Sector-15, Part-II,
Gurgaon on 11KV supply pressure under HT NDS category.

As per the decision taken in the technical feasibility committee meeting
held on dated 14.09.2016 and M.O.M. circulated vide Chief Engineer/Commercial
DHBVN, Hisar endst. No.Ch-95/SE/C/320/14/Vol-II dated 13.10.2016 through email on
dated 14.10.2016, the extract in the subject cited case is under: -

CE/Op, Delhi intimated that the ultimate load has been calculated as 3524 KW or 3916
KVA which will be fed through 11KV independent underground feeder (with double run 3CX300mm²
11KV XLPE cable) from 25/ 31.5 MVA 66/11KV Power T/F T-I at 66 KV S/Stn. Sec-15 Part-II, Gurgaon.
The Committee considered the above proposal and approved the same.

This is for your information ,please.


Superintending Engineer
'OP' Circle DHBVN, Gurgaon

C.C.to: -

- 1- The XEN City 'OP' Divn. DHBVN, Gurgaon.
- 2- The SDO CCC IDC S/Divn.DHBVN, Gurgaon

From

Chief Electrical Inspector
to Govt., Haryana,
SCO 85-86, Sector-17-D,
Chandigarh.

To

M/s Experion Developers Pvt. Ltd.
At Milestone Experion Towers
32nd Mile Stone, N.H-08, Gurugram.

Memo No: H.T.I / 11898

Dated: 16/9/2017

Subject: Inspection of HT installation comprising of 3x2000 KVA 11/0.433Kv T/Fs & HT line (Approx 2200 Mtr. with UG/XLPE Cable) emanating from 66Kv S/Stn. Sector-15 to M/s Milestone Experion Towers, Gurugram.


The subject cited installation was inspected by this department on 16.09.2017 and the same was found generally complying with the relevant provisions of CEA (Measures Relating to Safety and Electric Supply) Regulations, 2010.

The following observations be attended under intimation to this office:

1. Insulating mats confirming to IS:15632:2006 of appropriate voltage level be provided in front of the all panel.
2. Sufficient fire equipments be provided at various places.
3. Permanent Route Marker be provided on throughout the Underground Cable.

Approval for energisation of the subject cited installations is hereby accorded subject to consistent compliance of the relevant provisions of CEA Regulations, 2010 in the installation at your end. Please note that it shall be the responsibility of the owner of electrical installations to maintain and operate the installations in a condition free from danger and as recommended by the manufacturer or by the relevant code of practice of the Bureau of Indian Standards.

Your next inspection shall fall due in the month of September every year. You are therefore requested to deposit inspection fee as per schedule under the Head of A/c "0043- Taxes and Duties on Electricity Fees payable under I.E Rules, 1956" and send the original receipted treasury challan to this office one month before the due date.


Chief Electrical Inspector,
to Govt., Haryana, Chandigarh.
(Camp at Gurugram)

CC: The Executive Engineer, Electrical Inspectorate, Haryana, Gurugram for information.

CC: The SDO/AGM CCC IDC S/Divn., DHBVN, Gurugram for information and necessary action.

From

Chief Electrical Inspector
to Govt., Haryana,
SCO 85-86, Sector-17-D,
Chandigarh.

To

M/s Experion Developers Pvt. Ltd.
At Milestone Experion Towers
32nd Mile Stone, N.H-08, Gurugram

Memo No:

13741

Dated:


02/11/2017

5

Inspection of installation comprising of 4x1010 KVA & 1x625 KVA D.
installed in Milestone Experion Towers, Gurugram.

The subject cited installation was inspected by the undersigned on 02.11.2017 to ascertain the compliance of the relevant provisions of Central Electricity Authority (Maintenance and Relating to Safety and Electric Supply) Regulations, 2010 and found generally complying with the relevant provisions of the Regulations. Approval for energisation of the same is accorded.

Consistent compliance of the relevant provisions of CEA Regulations, 2010 is ensured in the installation at your end. Please note that it shall be the responsibility of the owner of electrical installations to maintain and operate the installations in a condition free from danger and as recommended by the manufacturer or by the relevant code of practice of the Bureau of Indian Standards.


Chief Electrical Inspector,
to Govt., Haryana, Chandigarh
(Camp at Gurugram)

CC: The Executive Engineer, Electrical Inspectorate, Haryana, Gurugram for information