

STATE ENVIRONMENT IMPACT ASSESSMENT AUTHORITY HARYANA
Bay No. 55-58, Prayatan Bhawan, Sector-2, PANCHKULA.

No. SEIAA/HR/2014/ 339

Dated: 21.02.2014

To

M/S Siyona Construction Pvt. Ltd.
1st Floor, The Great Eastern Centre, Nehru Place,
New Delhi- 110049

Subject: Environmental Clearance for proposed Expansion of Group Housing project at Sector-78, Gurgaon, Haryana.

Dear Sir,

This letter is in reference to your application no. Nil dated 07.03.2011 addressed to Director, IA (III) MOEF GOI received on 07.03.2011; transferred to M.S. SEIAA, Haryana on 18.05.2012 and subsequent letters dated 10.03.2011, 01.11.2012, 25.01.2013, 25.03.2013, 11.11.2013 seeking prior Environmental Clearance for the above project under the EIA Notification, 2006. The proposal has been appraised as per prescribed procedure in the light of provisions under the EIA Notification, 2006 on the basis of the mandatory documents enclosed with the application viz., Form-1, Form1-A & Conceptual Plan, EIA/EMP on the basis of approved TOR and additional clarifications furnished in response to the observations of the State Expert Appraisal Committee (SEAC) constituted by MOEF, GOI vide their Notification 23.3.2012, in its meetings held on 26.07.2012, 20.11.2012, 25.03.2013 and 17.06.2013 awarded "Gold" grading to the project.

[2] It is inter-alia, noted that the project involves the Construction of Expansion of Group Housing project at Sector-78, Gurgaon, Haryana with the following proposal for expansion of project:-

Particulars	Existing as per EC	Expansion proposed	Total
Total Plot Area	50642.25 sqmt (12.514 acres)	29711.973 sqmt (7.342 acres)	80354.254 sqmt (19.856 acres)
Built up Area	88258.16 sqmt	70938.209 sqmt	159196.369 sqmt
Green Belt	20257 sqmt	9001.83 sqmt	29258383 sqmt (36.4%)
Dwelling Units			
• Main	611	406	1017
• EWS	108	72	180
• Service area	62	44	106
No. of Blocks	10 Blocks	4 Blocks	14 Blocks
Height	44.25 m	13.95 m	58.2 m
Total Power requirement	5510 KVA	1887 KVA	7397 KVA
Total water requirement	596 KLD	400 KLD	996 KLD
Fresh water	350 KLD	241 KLD	591 KLD
Waste water	389 KLD	296 KLD	685 KLD

For UMANG REALTECH (P) LTD.
Daksh
Authorised Signatory

STP capacity	470 KLD	350 KLD	470 & 350 STPs
Solid waste generation	1684 kg/day	1343 kg/day	3027kg/day
Proposed Parking	850 ECS	608 ECS	1458
RWH Pits	13 nos.	7 nos.	20 nos.

[3] The State Expert Appraisal Committee, Haryana after due consideration of the relevant documents submitted by the project proponent and additional clarification furnished in response to its observations, have recommended the grant of environmental clearance for the project mentioned above, subject to compliance with the stipulated conditions. Accordingly, the State Environment Impact Assessment Authority in its meeting held on 24.01.2014 decided to agree with the recommendations of SEAC to accord necessary environmental clearance for the project under Category 8(b) of EIA Notification 2006 subject to the strict compliance with the specific and general conditions mentioned below:-

PART A-

SPECIFIC CONDITIONS:-

Construction Phase:-

- [1] "Consent for Establish" shall be obtained from Haryana State Pollution Control Board under Air and Water Act and a copy shall be submitted to the SEIAA, Haryana before the start of any construction work at site.
- [2] A first aid room as proposed in the project report shall be provided both during construction and operational phase of the project.
- [3] Adequate drinking water and sanitary facilities shall be provided for construction workers at the site. Provision should be made for mobile toilets. Open defecation by the labourers is strictly prohibited. The safe disposal of waste water and solid wastes generated during the construction phase should be ensured.
- [4] All the topsoil excavated during construction activities shall be stored for use in horticulture/landscape development within the project site.
- [5] The project proponent shall ensure that the building material required during construction phase is properly stored within the project area and disposal of construction waste should not create any adverse effect on the neighboring communities and should be disposed of after taking necessary precautions for general safety and health aspects of people, only in approved sites with the approval of competent authority.
- [6] Construction spoils, including bituminous material and other hazardous materials, must not be allowed to contaminate watercourses and the dump sites for such material must be secured so that they should not leach into the ground water and any hazardous material generated during construction phase, should be disposed off as per applicable rules and norms with necessary approval of the Haryana State Pollution Control Board

For HUMAN GEO REALTECH (P) LTD.
 Authorised Signatory

- [7] The diesel generator sets to be used during construction phase shall be of ultra low sulphur diesel type and should conform to Environment (Protection) Rules prescribed for air and noise emission standards.
- [8] The diesel required for operating DG sets shall be stored in underground tanks and if required, clearance from Chief Controller of Explosives shall be taken.
- [9] Ambient noise levels shall conform to the residential standards both during day and night. Incremental pollution loads on the ambient air and noise quality should be closely monitored during construction phase. Adequate measures should be taken to reduce ambient air pollution and noise level during construction phase, so as to conform to the stipulated residential standards of CPCB/MoEF.
- [10] Fly ash shall be used as building material in the construction as per the provisions of Fly Ash Notification of September 1999 and as amended on 27th August 2003.
- [11] Storm water control and its re-use as per CGWB and BIS standards for various applications should be ensured.
- [12] Water demand during construction shall be reduced by use of pre-mixed concrete, curing agents and other best practices.
- [13] In view of the severe constraints in water supply augmentation in the region and sustainability of water resources, the developer will submit the NOC from CGWA specifying water extraction quantities and assurance from HUDA/ utility provider indicating source of water supply and quantity of water with details of intended use of water – potable and non-potable. Assurance is required for both construction and operation stages separately. It shall be submitted to the SEIAA and RO, MOEF, Chandigarh before the start of construction.
- [14] Roof must meet prescriptive requirement as per Energy Conservation Building Code by using appropriate thermal insulation material.
- [15] Opaque wall must meet prescriptive requirement as per Energy Conservation Building Code which is proposed to be mandatory for all air conditioned spaces while it is desirable for non-air-conditioned spaces by use of appropriate thermal insulation material to fulfill requirement.
- [16] The approval of the competent authority shall be obtained for structural safety of the building on account of earthquake, adequacy of fire fighting equipments, etc. as per National Building Code including protection measures from lightening etc. If any forest land is involved in the proposed site, clearance under Forest Conservation Act shall be obtained from the competent Authority.
- [17] Overexploited groundwater and impending severe shortage of water supply in the region requires the developer to redraw the water and energy conservation plan. Developer shall reduce the overall footprint of the proposed development. Project proponent shall incorporate water efficiency /savings measures as well as water conservation measures.

For UMANG REALTECH (P) LTD.

Authorized Signatory

reuse/recycling within 3 months and before start of construction to the SEIAA, Haryana and RO, MOEF, GOI, Chandigarh.

- [18] The Project Proponent as stated in the proposal shall construct 20 nos. rain water harvesting pits for recharging the ground water within the project premises. Rain water harvesting pits shall be designed to make provisions for silting chamber and removal of floating matter before entering harvesting pit. Maintenance budget and persons responsible for maintenance must be provided. Care shall also be taken that contaminated water do not enter any RWH pit.
- [19] The project proponent shall provide for adequate fire safety measures and equipments as required by Haryana Fire Service Act, 2009 and instructions issued by the local Authority/Directorate of fire from time to time. Further the project proponent shall take necessary permission regarding fire safety scheme/NOC from competent Authority as required.
- [20] The Project Proponent shall obtain assurance from the DHBVN for supply of 7397 KVA of power supply before the start of construction. In no case project will be operational solely on generators without any power supply from any external power utility.
- [21] Detail calculation of power load and ultimate power load of the project shall be submitted to DHBVN under intimation to SEIAA Haryana before the start of construction. Provisions shall be made for electrical infrastructure in the project area.
- [22] The Project Proponent shall not raise any construction in the natural land depression / Nallah/water course and shall ensure that the natural flow from the Nallah/water course is not obstructed.
- [23] The Project Proponent shall keep the plinth level of the building blocks sufficiently above the level of the approach road to the Project. Levels of the other areas in the Projects shall also be kept suitably so as to avoid flooding.
- [24] Construction shall be carried out so that density of population does not exceed norms approved by Director General Town and Country Department Haryana.
- [25] The Project Proponent shall submit an affidavit with the declaration that ground water will not be used for construction and only treated water should be used for construction.
- [26] The project proponent shall not cut any existing tree and project landscaping plan should be modified to include those trees in green area.
- [27] The project proponent shall provide 3 meter high barricade around the project area, dust screen for every floor above the ground, proper sprinkling and covering of stored material to restrict dust and air pollution during construction.

For UMANG REALTECH (P) LTD

Authorised Signatory

- [28] The project proponent shall construct a sedimentation basin in the lower level of the project site to trap pollutant and other wastes during rains.
- [29] The project proponent shall provide proper rasta of proper width and proper strength for the project before the start of construction.
- [30] The project proponent shall ensure that the U-value of the glass is less than 3.177 and maximum solar heat gain co-efficient is 0.25 for vertical fenestration.
- [31] The project proponent shall adequately control construction dusts like silica dust, non-silica dust, wood dust. Such dusts shall not spread outside project premises. Project Proponent shall provide respiratory protective equipment to all construction workers.
- [32] The project proponent shall develop complete civic infrastructure of the Group Housing colony including internal roads, green belt development, sewerage line, Rain Water recharge arrangements, Storm water drainage system, Solid waste management site and provision for treatment of bio-degradable waste, STP, water supply line, dual plumbing line, electric supply lines etc. and shall offer possession of the units/flats thereafter.
- [33] The project proponent shall provide one refuse area till 24 meter as per National Building Code. The project proponent shall not convert any refuse area in the habitable space and it should not be sold out/commercialized.
- [34] The project proponent shall provide fire control room and fire officer for building above 30 meter as per National Building Code.
- [35] The project proponent shall obtain permission of Mines and Geology Department for excavation of soil before the start of construction.
- [36] The project proponent shall seek specific prior approval from concerned local Authority/HUDA regarding provision of storm drainage and sewerage system including their integration with external services of HUDA/ Local authorities beside other required services before taking up any construction activity.
- [37] The site for solid waste management plant be earmarked on the layout plan and the detailed project for setting up the solid waste management plant shall be submitted to the Authority within one month.
- [38] The project proponent shall submit the copy of fire safety plan duly approved by Fire Department before the start of construction.
- [39] The project proponent shall discharge excess of treated waste water/storm water in the public drainage system and shall seek permission of HUDA before the start of construction.
- [40] The project proponent shall maintain the distance between ~~SEWAGE~~ and water supply line.

For **UMANO REALTECH (P) LTD.**
 Authorised Signatory

Pooja Sh

- [41] The project proponent shall ensure that the stack height is 6 meter more than the highest tower.
- [42] The project proponent shall ensure that no construction activity is undertaken either on surface or below or above surface of revenue rasta passing through the project area.
- [43] The project proponent shall indicate the width and length of revenue rasta passing through the project area on sign board and shall display the same at both the ends of revenue rasta stretch, for awareness of public. Sign board shall also display the message that this is public rasta/road and any citizen can use it. There shall not be any gate with or without guards on revenue rasta.
- [44] The project proponent shall provide helipad facility as required under NBC norms and shall seek permission of helipad from AAI accordingly.
- [45] The project proponent shall seek separate environmental clearance for G2 Block after seeking permission of competent Authority for use of revenue rasta.

Operational Phase:

- [a] "Consent to Operate" shall be obtained from Haryana State Pollution Control Board under Air and Water Act and a copy shall be submitted to the SEIAA, Haryana.
- [b] The Sewage Treatment Plant (STP) shall be installed for the treatment of the sewage to the prescribed standards including odour and treated effluent will be recycled to achieve zero exit discharge. The installation of STP shall be certified by an independent expert and a report in this regard shall be submitted to the SEIAA, Haryana before the project is commissioned for operation. Tertiary treatment of waste water is mandatory. The project proponent shall remove not only Ortho-Phosphorus but total Phosphorus to the extent of less than 2mg/liter. Similarly total Nitrogen level shall be less than 2mg/liter in tertiary treated waste water. Discharge of treated sewage shall conform to the norms and standards of CPCB/ HSPCB, whichever is environmentally better. Project Proponent shall implement such STP technology which does not require filter backwash.
- [c] Separation of the grey and black water should be done by the use of dual plumbing line. Treatment of 100% grey water by decentralized treatment should be done ensuring that the re-circulated water should have BOD level less than 5 mg/litre and the recycled water will be used for flushing, gardening and DG set cooling etc. to achieve zero exit discharge.
- [d] For disinfection of the treated wastewater ultra-violet radiation or ozonization process should be used.

For UMANG REALTECH (P) LTD. Diesel power generating sets proposed as source of back-up power for lifts, common area illumination and for domestic use should be of enclosed type and

Daxesh
Authorized Signatory

conform to rules made under the Environment (Protection) Act, 1986. The location of the DG sets shall be in the basement as promised by the project proponent with appropriate stack height above the highest roof level of the project, as per the CPCB norms. The diesel used for DG sets shall be ultra low sulphur diesel (35ppm sulphur), instead of low sulphur diesel.

- [f] Ambient Noise level should be controlled to ensure that it does not exceed the prescribed standards both within and at the boundary of the Proposed Group Housing project.
- [g] The project proponent as stated in the proposal should maintain at least 36.4% as green cover area for tree plantation especially all around the periphery of the project and on the road sides preferably with local species which can provide protection against noise and suspended particulate matter. The open spaces inside the project shall be preferably landscaped and covered with vegetation/grass, herbs & shrubs. Only locally available plant species shall be used.
- [h] The project proponent shall strive to minimize water in irrigation of landscape by minimizing grass area, using native variety, xeriscaping and mulching, utilizing efficient irrigation system, scheduling irrigation only after checking evapo-transpiration data.
- [i] Rain water harvesting for roof run-off and surface run-off, as per plan submitted should be implemented. Before recharging the surface run off, pre- treatment through sedimentation tanks must be done to remove suspended matter, oil and grease. The bore well for rainwater recharging shall be kept at least 5 mts. above the highest ground water table. Care shall be taken that contaminated water do not enter any RWH pit. The project proponent shall avoid Rain Water Harvesting of first 10 minutes of rain fall. Roof top of the building shall be without any toxic material or paint which can contaminate rain water. Wire mesh and filters should be used wherever required.
- [j] The ground water level and its quality should be monitored regularly in consultation with Central Ground Water Authority.
- [k] A report on the energy conservation measures conforming to energy conservation norms finalized by Bureau of Energy Efficiency should be prepared incorporating details about building materials & technology, R & U Factors etc and submitted to the SEIAA, Haryana in three months time.
- [l] Energy conservation measures like installation of LED only for lighting the areas outside the building and inside the building should be integral part of the project design and should be in place before project commissioning. Use of solar panels must be adapted to the maximum energy conservation.

For UMANG REALTECH (P) LTD.
 Pakech
 Authorised Signatory

- [m] The Project Proponent shall use zero ozone depleting potential material in insulation, refrigeration, air-conditioning and adhesive. Project Proponent shall also provide Halon free fire suppression system.
- [n] The solid waste generated should be properly collected and segregated as per the requirement of the MSW Rules, 2000 and as amended from time to time. The bio-degradable waste should be treated by appropriate technology at the site ear-marked within the project area and dry/inert solid waste should be disposed off to the approved sites for land filling after recovering recyclable material.
- [o] The provision of the solar water heating system shall be as per norms specified by HAREDA and shall be made operational in each building block.
- [p] The traffic plan and the parking plan proposed by the Project Proponent should be adhered to meticulously with further scope of additional parking for future requirement. There should be no traffic congestion near the entry and exit points from the roads adjoining the proposed project site. Parking should be fully internalized and no public space should be used.
- [q] The Project shall be operationalized only when HUDA/local authority will provide domestic water supply system in the area.
- [r] Operation and maintenance of STP, solid waste management and electrical Infrastructure, pollution control measures shall be ensured even after the completion of project.
- [s] Different type of wastes should be disposed off as per provisions of municipal solid waste, biomedical waste, hazardous waste, e-waste, batteries & plastic rules made under Environment Protection Act, 1986. Particularly E-waste and Battery waste shall be disposed of as per existing E-waste Management Rules 2011 and Batteries Management Rules 2001. The project proponent should maintain a collection center for E-waste and it shall be disposed of to only registered and authorized dismantler / recycler.
- [t] Standards for discharge of environmental pollutants as enshrined in various schedules of rule 3 of Environment Protection Rule 1986 shall be strictly complied with.
- [u] Water supply shall be metered among different users and different utilities.
- [v] The project proponent shall ensure that the stack height of DG sets is more than the highest tower and also ensure that the emission standards of noise and air are within the CPCB latest prescribed limits. Noise and Emission level of DG sets greater than 800 KVA shall be as per CPCB latest standards for high capacity DG sets.
- [w] All electric supply exceeding 100 amp, 3 phase shall maintain the power factor between 0.98 lag to 1 at the point of connection.

For UMANG REALTECH (P) LTD.
 10/10/2018

Raven
 Authorized Signatory

- [x] The project proponent shall use only treated water instead of fresh water for HVAC and DG cooling. The Project Proponent shall also use evaporative cooling technology and double stage cooling system for HVAC in order to reduce water consumption. Further temperature, relative humidity during summer and winter seasons should be kept at optimal level. Variable speed drive, best Co-efficient of Performance (CoP), as well as optimal Integrated Point Load Value and minimum outside fresh air supply may be resorted for conservation of power and water. Coil type cooling DG Sets shall be used for saving cooling water consumption for water cooled DG Sets.
- [y] The project proponent shall ensure that the transformer is constructed with high quality grain oriented, low loss silicon steel and virgin electrolyte grade copper. The project proponent shall obtain manufacturer's certificate also for that.
- [z] The project proponent shall ensure that exit velocity from the stack should be sufficiently high. Stack shall be designed in such a way that there is no stack down-wash under any meteorological conditions.
- [aa] The project proponent shall provide water sprinkling system in the project area to suppress the dust in addition to the already suggested mitigation measures in the Air Environment Chapter of EMP.
- [ab] The project proponent shall ensure proper Air Ventilation and light system in the basements area for comfortable living of human being and shall ensure that number of Air Changes per hour/(ACH) in basement never falls below 15. In case of emergency capacity for increasing ACH to the extent of 30 must be provided by the project proponent.

PART-B. GENERAL CONDITIONS:

- [i] The Project Proponent shall ensure the commitments made in Form-1, Form-1A, EIA/EMP and other documents submitted to the SEIAA for the protection of environment and proposed environmental safeguards are complied with in letter and spirit. In case of contradiction between two or more documents on any point, the most environmentally friendly commitment on the point shall be taken as commitment by project proponent.
- [ii] The project proponent shall also submit six monthly reports on the status of compliance of the stipulated EC conditions including results of monitored data (both in hard copies as well as by e-mail) to the northern Regional Office of MoEF, the respective Zonal Office of CPCB, HSPCB and SEIAA Haryana.
- [iii] STP outlet after stabilization and stack emission shall be monitored monthly. Other environmental parameters and green belt shall be monitored on quarterly basis. After every 3 (three) months, the project proponent shall conduct environmental audit and shall take corrective measure, if required, without delay.


For UMANG REALTECH (P) LTD.
Daksh
 Authorised Signatory

- [iv] The SEIAA, Haryana reserves the right to add additional safeguard measures subsequently, if found necessary. Environmental Clearance granted will be revoked if it is found that false information has been given for getting approval of this project. SEIAA reserves the right to revoke the clearance if conditions stipulated are not implemented to the satisfaction of SEIAA/MoEF.
- [v] The Project proponent shall not violate any judicial orders/pronouncements issued by any Court/Tribunal.
- [vi] All other statutory clearances such as the approvals for storage of diesel from Chief Controller of Explosives, Fire Department, Civil Aviation Department, Forest Conservation Act, 1980 and Wildlife (Protection) Act, 1972, Forest Act, 1927, PLPA 1900, etc. shall be obtained, as applicable by project proponents from the respective authorities prior to construction of the project.
- [vii] The Project proponent should inform the public that the project has been accorded Environment Clearance by the SEIAA and copies of the clearance letter are available with the Haryana State Pollution Control Board & SEIAA. This should be advertised within 7 days from the date of issue of the clearance letter at least in two local newspapers that are widely circulated in the region and the copy of the same should be forwarded to SEIAA Haryana. A copy of Environment Clearance conditions shall also be put on project proponent's web site for public awareness.
- [viii] Under the provisions of Environment (Protection) Act, 1986, legal action shall be initiated against the Project Proponent if it was found that construction of the project has been started before obtaining prior Environmental Clearance.
- [ix] Any appeal against the this Environmental Clearance shall lie with the National Green Tribunal, if preferred, within a period of 30 days as prescribed under Section 16 of the National Green Tribunal Act, 2010.
- [x] The project proponent shall put in place Corporate Environment Policy as mentioned in MoEF, GoI OM No. J-11013/41/2006-IA II (I) dated 26.4.2012 within 3 months period. Latest Corporate Environment Policy should be submitted to SEIAA within 3 months of issuance of this letter.
- [xi] The fund ear-marked for environment protection measures should be kept in separate account and should not be diverted for other purposes and year wise expenditure shall be reported to the SEIAA/RO MOEF GOI under rules prescribed for Environment Audit.
- [xii] The project proponent shall ensure the compliance of Forest Department, Haryana Notification no. S.O. 121/PA2/1900/S.4/97 dated 28.11.1997.
- [xiii] The Project Proponent shall ensure that no vehicle during construction/operation phase enter the project premises without valid 'Pollution Under Control' certificate from competent Authority.

For UMANG REALTECH (P) LTD.

Authorised Signatory

- [xiv] The project proponent is responsible for compliance of all conditions in Environmental Clearance letter and project proponent can not absolve himself/herself of the responsibility by shifting it to any contractor engaged by project proponent.
- [xv] The project proponent shall seek fresh Environmental clearance if at any stage there is change in the planning of the proposed project.
- [xvi] Besides the developer/applicant, the responsibility to ensure the compliance of Environmental Safeguards/ conditions imposed in the Environmental Clearance letter shall also lie on the licensee/licensees in whose name/names the license/CLU has been granted by the Town & Country Planning Department, Haryana.
- [xvii] The proponent shall upload the status of compliance of the stipulated EC conditions, including results of monitored data on their website and shall update the same periodically. It shall simultaneously be sent to the Regional Office of MoEF, the respective Zonal Office of CPCB and the SPCB. The criteria pollutant levels namely; $PM_{2.5}$, PM_{10} , SO_x , NO_x , Ozone, Lead, CO, Benzene, Ammonia, Benzopyrine, arsenic and Nickel. (Ambient levels as well as stack emissions) or critical sectoral parameters, indicated for the project shall be monitored and displayed at a convenient location near the main gate of the company in the public domain.
- [xviii] The environmental statement for each financial year ending 31st March in Form-V as is mandated to be submitted by the project proponent to the HSPCB Panchkula as prescribed under the Environment (Protection) Rules, 1986, as amended subsequently, shall also be put on the website of the company along with the status of compliance of the EC conditions and shall also be sent to the respective Regional Offices of MoEF by e-mail.
- [xviii] The project proponent shall conduct environment audit at every three months interval and thereafter corrected measures shall be taken without any delay. Details of environmental audit and corrective measures shall be submitted in the monitoring report.


Member Secretary,
State Level Environment Impact
Assessment Authority, Haryana, Panchkula.


Endst. No. SEIAA/HR/2014

Dated:.....

A copy of the above is forwarded to the following:

1. The Additional Director (IA Division), MOEF, GOI, CGO Complex, Lodhi Road, New Delhi.
2. The Regional office, Ministry of Environment & Forests, Govt. of India, Sector 31, Chandigarh.
3. The Chairman, Haryana State Pollution Control Board, Pk1.

1
Member Secretary,
State Level Environment Impact
Assessment Authority, Haryana, Panchkula.

PANCHKULA REALTECH (P) LTD.

Authorised Signatory

GOVERNMENT OF HARYANA
STATE ENVIRONMENT IMPACT ASSESSMENT AUTHORITY HARYANA
Bay No. 55-58, Prayatan Bhawan, Sector-2, PANCHKULA.

No. SEIAA HR 2010 (146)

Dated: 21-1-10

To

MS Uppal Housing Ltd.
5th Floor, South Tower, NBCC Place,
Bhishma Pitamah Marg, Pragati Vihar,
Lodhi Road, New Delhi - 110003.

Subject: Environmental Clearance for construction of Group Housing Project "Uppal's Canary Residency" at village - Naurangpur, Sector-78, Gurgaon, Haryana.

Dear Sir,

This has reference to your application No. UG/Letter/2008/258 dated 22.04.08 addressed to Director, I.A. Division MOEF, GOI, transferred in the office of MS SEIAA on 30.06.08 and subsequent letters dated 02.12.08, 13.02.09, 05.05.09, 14.07.09, 25.08.09, 09.09.09 and 24.09.09 seeking prior environmental clearance for the above project under the EIA Notification, 2006. The proposal has been appraised as per prescribed procedure in the light of provisions under the EIA Notification, 2006 on the basis of the mandatory documents enclosed with the application viz., Form-I, Form-I-A & Conceptual Plan and the additional clarifications furnished in response to the observations of the State Expert Appraisal Committee (SEAC) constituted by MOEF, GOI vide their Notification 21.4.2008, in its meeting held on 27.08.08, 27.01.09, 15.07.09 and 24.09.09 awarded "Gold" grading to the project.

[2] It is interalia noted that the project involves construction of Proposed construction of Group Housing Project "Uppal's Canary Residency" at village - Naurangpur, Sector-78, Gurgaon, Haryana on a plot area of 50643.46 Sq. m out of total leased area of 117547 sqm. The Proposed builtup area will

For UMANG REALTECH (P) LTD.

Pardeep

Authorised Secretary

of towers. The maximum height of the building will be 44.25 meters and NOC from Airport Authority is awaited. The total fresh water requirement will be 350 KLD. The water requirement will be met from HUDA Bore-well. The quantity of waste water generated from the project activity will be about 389 KLD which will be treated in the STP by primary, secondary and tertiary treatment. The capacity of STP will be 470 KLD. The 246 KLD of treated water will be recycled back and utilized for horticulture, cooling of DG, flushing etc and 143 KLD of treated water will be discharged in the public sewer. Total solid waste generation will be 1684 Kg per day which will be disposed off as per Solid Waste Management & Handling Rules. The project proponent has proposed to carry out composting of bio-degradable waste within the project area. The power requirement is 4683.5 KW which will be supplied by DIHBVN. The total parking spaces proposed are for 850 ECS in basements and stilt. Total cost of the project is Rs.122.28 crores.

[3] The State Expert Appraisal Committee, Haryana after due consideration of the relevant documents submitted by the project proponent and additional clarification furnished in response to its observations have recommended the grant of environmental clearance for the project mentioned above subject to compliance with the stipulated conditions. Accordingly, the State Environment Impact Assessment Authority hereby accords necessary environmental clearance for the project under Category 8(a) of EIA Notification 2006 subject to the strict compliance with the specific and general conditions mentioned below:-

PART A-

SPECIFIC CONDITIONS:-

Construction Phase:-

For UMANG REALTECH (P) LTD.

Rajesh

Authorised Signatory

[i] A first aid room as proposed in the project report will be provided in

- [ii] Adequate drinking water and sanitary facilities should be provided for construction workers at the site. Provision should be made for mobile toilets. Open defecation by the labourers is strictly prohibited. The safe disposal of waste water and solid wastes generated during the construction phase should be ensured.
- [iii] All the topsoil excavated during construction activities should be stored for use in horticulture landscape development within the project site.
- [iv] Disposal of muck during construction phase should not create any adverse effect on the neighboring communities and be disposed taking the necessary precautions for general safety and health aspects of people, only in approved sites with the approval of competent authority.
- [v] Construction spoils, including bituminous material and other hazardous materials, must not be allowed to contaminate watercourses and the dump sites for such material must be secured so that they should not leach into the ground water and any hazardous waste generated during construction phase, should be disposed off as per applicable rules and norms with necessary approval of the Haryana State Pollution Control Board.
- [vi] The diesel generator sets to be used during construction phase should be of low sulphur diesel type and should conform to Environment (Protection) Rules prescribed for air and noise emission standards.
- [vii] The diesel required for operating DG sets shall be stored in underground tanks and if required, clearance from Chief Controller of Explosives shall be taken.
- [viii] Ambient noise levels should conform to the residential standards both during day and night. Incremental pollution loads on the ambient air and noise quality should be closely monitored during construction phase. Adequate measures should be made to reduce ambient air and noise level during construction phase, so as to conform to the stipulated standards.
- [ix] Fly ash should be used as building material in the construction as per the provisions of Fly Ash Notification of September 1999 and amended as on 27th August 2003.
- [x] Ready mixed concrete must be used in building construction.
- [xi] Storm water control and its re-use as per COWB and BIS standards for various applications.

Authorised Signatory

RECEIVED
22/07/2023

- [xii] Water demand during construction should be reduced by use of pre-mixed concrete, curing agents and other best practices referred.
- [xiii] Permission from Competent Authority for supply of water shall be obtained prior to operation of the project.
- [xiv] Roof should meet prescriptive requirement as per Energy Conservation Building Code by using appropriate thermal insulation material to fulfill requirement
- [xv] Opaque wall should meet prescriptive requirement as per Energy Conservation Building Code which is proposed to be mandatory for all air conditioned spaces while it is aspirational for non-air-conditioned spaces by use of appropriate thermal insulation material to fulfill requirement.
- [xvi] The approval of the competent authority shall be obtained for structural safety of the building due to earthquake, adequacy of fire fighting equipments, etc. as per National Building Code including protection measures from lightening etc. If any forest land is involved in the proposed site, clearance under Forest Conservation Act shall be taken from the competent Authority.
- [xvii] The Project Proponent shall abstract ground water only after obtaining prior permission of CGWA. However the project proponent will use the water for construction phase through tankers.
- [xviii] The project proponent will construct rain water harvesting pits @ 1 pit per acre for recharging the ground water within the project premises.

Operation Phase:

- [i] The STP shall be installed for the treatment of the sewage generated to the prescribed standards including odour and treated effluent will be recycled to achieve zero discharge. The STP should be installed at the farthest place in the project area.
- [ii] Separation of the grey and black water should be done by the use of dual plumbing line. Treatment of 100% grey water by decentralized treatment should be done ensuring that the re-circulated water should have BOD maximum 10 ppm and the recycled water will be used for flushing, gardening and DG set cooling.
- [iii] For disinfections of the treated wastewater ultra violet radiation or

- [iv] The solid waste generated should be properly collected and segregated. Bio-degradable waste will be decomposed at site and dry inert solid waste should be disposed off to the approved sites for land filling after recovering recyclable material.
- [v] Diesel power generating sets proposed as source of back up power for lifts, common area illumination and for domestic use should be of enclosed type and conform to rules made under the Environment (Protection) Act, 1986. The location of the DG sets should be in the basement as promised by the project proponent with appropriate stack height i.e. above the roof level as per the CPCB norms. The diesel used for DG sets should be of low sulphur contents (maximum 0.25%).
- [vi] Ambient Noise level should be controlled to ensure that it does not exceed the prescribed standards both within and at the boundary of the Proposed Residential Complex.
- [vii] The project proponent should maintain at least 20% as green cover area for tree plantation especially all around the periphery of the project and on the road sides preferably with local species so as to provide protection against particulates and noise. The open spaces inside the plot should be preferably landscaped and covered with vegetation/grass. The Project Proponent shall provide green cover to the paved area.
- [viii] Weep holes in the compound front walls shall be provided to ensure natural drainage of rain water in the catchments area during the monsoon period.
- [ix] The project proponent shall setup rain water harvesting pits @ 1 pit/ acre having 400 mm bore and 200 mm slotted pipe for roof run-off and surface run-off, as plan submitted should be implemented. Before recharging the surface run off, pre-treatment must be done to remove suspended matter, oil and grease. The bore well for rainwater recharging should be kept at least 5 mts. above the highest ground water table.
- [x] The ground water level and its quality should be monitored regularly in consultation with Central Ground Water Authority.
- [xi] There should be no traffic congestion near the entry and exit points from the roads adjoining the proposed project site. Parking should be fully internalized and no public space should be utilized.
- [xii] A report on the energy conservation measures conforming to energy conservation norms.

prepared incorporating details about building materials & technology, R & U Factors etc and submit to the SI IAA, Haryana in three months time

- [xiii] Energy conservation measures like installation of CFLs TFLs for lighting the areas outside the building should be integral part of the project design and should be in place before project commissioning. Used CFLs and TFLs should be properly collected and disposed off/sent for recycling as per the prevailing guidelines/rules of the regulatory authority to avoid mercury contamination. Use of solar panels may be done to the extent possible.
- [xiv] The solid waste generated should be properly collected and segregated as per the requirement of the MSW Rules, 2000 and as amended from time to time. The bio-degradable waste should be composted by vermi-composting at the site ear marked within the project area and dry/inert solid waste should be disposed off to the approved sites for land filling after recovering recyclable material.
- [xv] The provision of the solar water heating system shall be as per the norms specified by HAREDA and shall be made operational in each building block.
- [xvi] The project proponent will use the water from the already existing tube wells for domestic purposes only after getting permission from CGWA or will use water supply from HUDA whichever is earlier during operation phase.
- [xvii] The traffic plan and the parking plan proposed by the PP should be adhered to meticulously with further scope of additional parking for future requirement. There should be no traffic congestion near the entry and exit points from the roads adjoining the proposed project site. Parking should be fully internalized and no public space should be utilized.
- [xviii] The Project Proponent shall comply with the EC BC norms.

For UMANG REALTECH (P) LTD.

PART-B. GENERAL CONDITIONS:

Pace P3

Authorised Signatory

- [i] The environmental safeguards contained in the EIA-EMP Report should be implemented in letter and spirit.
- [ii] Six monthly compliance reports should be submitted to the HSPCB and Regional Office, MOEF, GOI, Northern Region, Chandigarh and a copy to

- [iii] The SEIAA, Haryana reserves the right to add additional safeguard measures subsequently, if found necessary. Environmental Clearance granted will be revoked if it is found that false information has been given for getting approval of this project.
- [iv] All other statutory clearances such as the approvals for storage of diesel from Chief Controller of Explosives, Fire Department, Civil Aviation Department and Wildlife (Protection) Act, 1972, PLPA, 1900, Forest Act, 1927 etc. shall be obtained, as applicable by project proponents from the respective authorities prior to construction of the project.
- [v] The Project proponent will not violate any judicial orders pronouncements issued by the Hon'ble Supreme Court High Courts.
- [vi] Environmental Clearance is subject to their obtaining prior clearance from forestry angle.
- [vii] The grant of this environmental clearance does not necessarily imply that forestry clearance shall be granted to the project and that their proposal for forestry clearance will be considered by respective Authorities on their merits and decisions taken. It is also made clear that if any, investment is made, based on environmental clearance so granted, in anticipation of clearance from Forestry angle shall be entirely at the cost and risk of the Project Proponent



Member Secretary,
State Level Environment Impact
Assessment Authority, Haryana, Panchkula.




Endst. No. SEIAA HR 2010

Dated:

A copy of the above is forwarded to the following:

1. The Additional Director (IA Division), MOEF, GOI, CGO Complex, Lodi Road, New Delhi
2. The Regional office, Ministry of Environment & Forests, Govt. of India, Sector 31, Chandigarh.
3. The Chairman, Haryana State Pollution Control Board, PKI.

For UMANG REALTECH (P) LTD.


Authorised Signatory

Member Secretary,
State Level Environment Impact
Assessment Authority, Haryana, Panchkula.