

ENVIRONMENTAL
CLEARANCE

PARIVESH

(Pro-Active and Responsive Facilitation by Interactive, and Virtuous Environmental Single-Window Hub)



Government of India
Ministry of Environment, Forest and Climate Change
(Issued by the State Environment Impact Assessment
Authority(SEIAA), Haryana)

To,

The Authorized Signatory
RAMPRASTHA PROMOTERS & DEVELOPERS PVT LTD
Plot No. 114, Sector-44, Gurugram, Haryana -122002

Subject: Grant of Environmental Clearance (EC) to the proposed Project Activity under the provision of EIA Notification 2006-regarding

Sir/Madam,

This is in reference to your application for Environmental Clearance (EC) in respect of project submitted to the SEIAA vide proposal number SIA/HR/MIS/66492/2021 dated 10-Dec-2021. The particulars of the environmental clearance granted to the project are as below.

1. EC Identification No.	EC22B039HR176822
2. File No.	SEIAA/HR/2021/491
3. Project Type	Expansion
4. Category	B1
5. Project/Activity including Schedule No.	8(b) Townships and Area Development projects.
6. Name of Project	Expansion cum modification of Group Housing Colony " Primera & Ark'at Village - Garauli Kalan, Sector- 37-D, Gurugram, Haryana M/s Ramprastha Promoters & Developers Pvt Ltd
7. Name of Company/Organization	RAMPRASTHA PROMOTERS & DEVELOPERS PVT LTD
8. Location of Project	Haryana
9. TOR Date	16 Aug 2021

The project details along with terms and conditions are appended herewith from page no 2 onwards.

Date: 25/09/2022

(e-signed)
Pardeep Kumar, IAS
Member Secretary
SEIAA - (Haryana)

Note: A valid environmental clearance shall be one that has EC identification number & E-Sign generated from PARIVESH. Please quote identification number in all future correspondence.

This is a computer generated cover page.

State Environment Impact Assessment Authority, Haryana,
Bays No.55-58, Prayatan Bhawan, Sector-2 Panchkula.

Tel: 0172-2565232, 4043956
E-mail Id: seiaa-21.env@hry.gov.in

Subject: EC for Expansion cum Modification of Group Housing Colony at Village Garauli Kalan, Sector 37-D, Gurugram, Haryana of land measuring 13.156 acres by M/s Ramprastha Promoters & Developers Pvt Ltd.

This has reference to your Proposal No. SIA/HR/MIS/68492/2021 on 02.11.2021 and subsequent letter dated 12.03.2022, 21.06.2022 for seeking prior Environmental Clearance (EC) for the above project under the EIA Notification, 2006 along with submission of required Scrutiny Fee amounting of Rs. 2,00,000/- vide DD. No.069544 dated 09.12.2021 in compliance of Haryana Government, Environment & Climate Change Notification No. DE&CCH/3060 dated 14th October, 2021. The proposal has been appraised as per prescribed procedure in the light of provisions under the EIA Notification, 2006 on the basis of the mandatory documents enclosed with the application viz., Form-1, Form1-A, Conceptual Plan, EIA/EMP Report and additional clarifications furnished in response to the observations of the State Expert Appraisal Committee (SEAC) constituted by MoEF & CC, GoI vide their Notification dated 21.02.2022, in its meeting held on 09.03.2022 and 25.07.2022 awarded “Gold” rating / grading to the Project.

2. It is inter-alia, noted that the project involves in Expansion cum Modification of Group Housing Colony at Village Garauli Kalan, Sector 37-D, Gurugram, Haryana.

3. The details of project are as under:

Table 1: Construction status

Sr. No	Description	Tower A, R.C.D and EWS	Tower E	Community Building (1&2) Convenient Shopping	Blocks (1-20) and Nursery School (1-2)
1	Excavation Work	100%	100%	100%	NIL
2	Foundation	100%	100%	100%	NIL
3	Roofs/Slabs	100%	NIL	100%	NIL
4	Drainage System	95%	NIL	NIL	NIL
5	Sewerage Treatment Plant	85%		NIL	NIL
6	Roads	60%	NIL	30%	NIL

Table 2:Basic Details

Sr.No.	Particulars	Existing	Expansion	Total Area
1)	Online Project Proposal Number	SIA/HR/MIS/68492/2021, Dated 20.09.2021		
2)	Latitude	28°27'5.82"N		
3)	Longitude	76°58'23.29"E		
4)	Plot Area	53,240.36m ² (13.156 acres)		
5)	Proposed Ground Coverage	11,529.00 m ² (21.56%)		
6)	Proposed FAR	92,220.48m ²	-	92,220.48m ²

7)	Non FAR Area	38,019.25m ²	24,209.52m ²	62,228.77m ²
8)	Total Built Up area	1,30,239.73m2	24,209.52m2	1,54,449.25m2
9)	Total Green Area with Percentage	18,729.958m ² (35.18% plot	Nil	18,729.958m ² (35.18% plot
10)	Rain Water Harvesting Pits	14 Nos.	Nil	14 Nos.
11)	STP Capacity	2 STP of 370 & 490 KLD	--	2 STP of 490 KLD & 370 KLD
12)	Total Parking	1,441 ECS	Nil	1,441 ECS
13)	Organic Waste Converter	-	-	2,100 Kg/day (1x1250 Kg/day+ 1x500 + 1 x 100 Kg/day+ 1 x 250 Kg/day))
14)	Maximum Height of the Building (till terrace)	92.20 m	-10.25 m	81.25 m
15)	Power Requirement	7851 KVA	-2151 KVA	5700 KVA
16)	Power Backup	-	-	7 Nos of DG sets having Capacity of 4820 KVA (6*750 KVA+1*320 KVA)
17)	Total Water Requirement	748KLD	---	748 KLD
18)	Domestic Water Requirement	455 KLD	---	455 KLD
19)	Fresh Water Requirement	455 KLD	---	455 KLD
20)	Treated Water	--	--	339 KLD
21)	Waste Water Generated	617 KLD	--	617 KLD
22)	Solid Waste Generated	2261kg/day	+620 kg/day	2881 kg/day
23)	Biodegradable Waste	-	-	1,729 kg/day
24)	Number of Towers	25 nos	-20nos	5nos
25)	Number of Blocks	--	--	20 nos
26)	No. of Floors for Towers	--	--	G+25
27)	No. of Floors for Blocks	--	--	G+4
28)	Dwelling Units	672	--	672
29)	EWS Unit	119	--	119
30)	Servant Room	160	--	160
31)	Basement	-	-	5 nos
32)	Community Center	-	-	1,800 sqm
33)	Nursery School (1-2)	-	-	1,618.80sqm
34)	Convenient Shopping	-	-	266.05sqm
35)	Stories	-	-	G+25 Floors
36)	R+U Value of Material used (Glass)	--	-	U Value: 5.5 w/sqm k SHGC: 0.9
37)	Total Cost of the project:	i) Land Cost ii) Construction Cost	--	223 Cr.

38)	EMP Cost/Budget	--	--	Total Project Cost 223 Cr EMP (5% of Project Cost) :1115 Lakh
39)	Incremental Load in respect of: i) PM 2.5	--	--	0.00641 µg/m ³
40)	PM 10	--	--	0.01435µg/m ³
41)	SO ₂	--	--	0.42069 µg/m ³
42)	NO ₂	--	--	0.01531 µg/m ³
43)	CO	--	--	0.00000743mg/m ³
44)	Construction Phase: Power Back-up	--	--	Temporary Connection
45)	Water Requirement & Source	--	--	GMDA+ Treated water
46)	STP (Modular)	--	--	5 KLD
47)	Anti-Smoke Gun	--	--	1

Table 3:EMP BUDGET

Existing Phase	
Description	Expense done (in Rs) 2014 to till now)
Waste Water Management (STP)	1,75,00,000
Rain Water Harvesting System	20,00,000
Storm Water Drainage System	1,90,00,000
Landscaping/ maintenance of Green Area	15,00,000
Monitoring for Air, Water, Stack, emission & Noise	4,00,000
Barricading	12,00,000
PPE for workers & Health Care	1,50,000
Medical cum First Aid facility (Providing medical room & Doctor)	5,00,000
DG set Stack	38,00,000
Solar panel (40KW)	18,29,000
Total	4,78,79,000

Expansion Phase or proposed/balance construction to be done					
Description	During Construction Phase		Description	During Operation Phase	
	Capital Cost	Recurring Cost		Capital Cost	Recurring Cost
	(Lakhs)	(Lakhs for 5 Year)		(Lakhs)	(Lakhs for 10 Year)
Sanitation and Waste Water Management (Modular STP)	5.00	4.00	Waste Water Management (Sewage Treatment Plant)	80.00	200.00
Green Belt Development	25.00	5.00	Green Belt Development	10.00	50.00
Air, Noise, Soil, Water Monitoring	0.00	5.00	Monitoring for Air, Water, Noise & Soil	00.00	10.00
Rainwater harvesting system	8.00	4.00	Rainwater harvesting system	00.00	25.00
PPE for workers & Health Care	5.00	5.00	Solid Waste Management (Dust bins & OWC)	40.00	60.00
Medical cum First Aid facility (Providing medical room &	10.00	20.00	DG set Stack	30.00	15.21

Doctor)					
			Up gradation of toilets, providing furniture, water tanks & dustbins in the nearby existing school of Basavivillage	20.00	0.00
Total	53 Lakhs	43 Lakhs		180 Lakhs	360.21 Lakhs

4. The State Expert Appraisal Committee, Haryana after due consideration of the relevant documents submitted by the project proponent and additional clarification furnished in response to its observations, have recommended this project for grant of environmental clearance. Accordingly, the State Environment Impact Assessment Authority in its **145th meeting held on 8th – 9th September 2022** decided to agree with the recommendations of SEAC to accord necessary Environmental Clearance for the project under **Category 8(b)** of EIA Notification 2006 subject to the **strict compliance with the following stipulations depicted below:-**

A. Specific conditions:-

1. The Project Proponent shall obtain requisite sewer connection/permission from the Competent Authority.
2. The Project Proponent will ensure that Green area will remain same as mentioned in the earlier Environmental Clearance and will not reduced in any manner.
3. Sewage shall be treated in the modular STP based on latest Technology to achieve standards ordered by NGT. The Treated effluent from STP shall be recycled /reused for flushing. DG cooling and Gardening
4. The PP shall spent Rs.5 Lakhs on various wildlife conservation activities like artificial nests on the trees, digging of ponds and construction of feeding platforms through Environment Management Plan
5. The Project Proponent would devise a monitoring plan to the satisfaction of the State Pollution Control Board so as to continuously monitor the treated waste water being used for flushing in terms of faecal coli forms and other pathogenic bacteria.
6. The PP shall ensure that total 2% of the cost of project shall be spent on EMP Budget. However, the amount and component shown in EMP table above shall also be included for the purpose of 2% amount. The EMP cost on Socio Economic activities shall be used before the commencement of the project & EMP recurring inside the project shall be implemented throughout the operation of the project. The PP shall establish Environment monitoring cell as per documents submitted.
7. The PP shall not carry out any construct above and below revenue rasta if passing through the project and ensure that permission of the competent authority shall be obtained before carry out any construction above or below the revnue rasta. The PP shall put notice board on the revenue rasta for the passer byes.
8. The project proponent shall upload the status of compliance of the basic details (given in above tables), stipulated environment clearance conditions, including results of monitored data on their website and update the same on half-yearly basis.
9. The Project Proponents would commission a third party study on the implementation of conditions related to quality and quantity of recycle and reuse of treated water, efficiency of treatment systems, quality of treated water being supplied for flushing (specially the bacterial counts), comparative bacteriological studies from toilet seats using recycled treated waters and fresh waters for flushing, and quality of water being supplied through spray faucets attached to toilet seats.
10. Separate wet and dry bins must be provided in each unit and at ground level for facilitating segregation of waste. Solid Waste shall be segregated into wet garbage and inert materials. Wet Garbage shall be composted in Organic waste convertor. Adequate area shall be provided for solid waste management within the premises which will include area for segregation, composting. The Inert waste from the project will be sent to solid waste dumping site through authorized vender.

11. Traffic management plan as submitted shall be implemented in letter and spirit. Apart, a detailed traffic management and traffic decongestion plan shall be drawn up to ensure that the current level of service of the roads within a 05 kms radius of the project is maintained and improved upon after the implementation of the project. This plan should be based on cumulative impact of all development and increased habilitation being carried out or purpose to be carried out by the project or other agencies in this 05kms radius of the site in different scenarios of space and time
 12. No tree cutting has been proposed in the instant project. A minimum of 1 tree for every 80sqm of land should be planted and maintained. The Existing trees will be counted for this purpose. The landscape planning should include plantation of native species. The species with heavy foliage, broad leaves and wide canopy cover are desirable. Water intensive and/or invasive species should not be used for landscaping. As proposed 18,729.958m²(35.18% plot area) shall be provided for Green Area development for whole project, excluding plot areas.
 13. The Project Proponent shall obtain all necessary clearance/permission from all relevant agencies including town planning authority before commencement of work. All the construction shall be done in accordance with the local building byelaws.
 14. Consent to establish/operate for the project shall be obtained from the State Pollution Control Board as required under the Air (Prevention and Control of pollution) Act, 1981 and the Water (Prevention and control of pollution) Act, 1974.
 15. The Approval of the Competent Authority shall be obtained for structural safety of building code due to earthquakes, adequacy of fire fighting equipments etc. as per National Building Code including protection measures from lightening etc.
 16. The PP shall obtain the Fire NOC from the Competent Authority before taking the occupation of the building.
 17. The PP shall install the Eco Friendly Green Transformer based on ester oil to reduce the carbon footprint. The PP shall shift to gas based generator set when the gas is available. The PP shall install APCM for the DG set. The PP shall reduce the So₂ load by 30% if HSD is used. The DG sets will be operated for maximum 04 hours during power failure through Executing Agency
 18. The PP shall not give occupation or possession before the water supply and sewage connection permitted by the competent authority.
 19. The PP shall not give occupation or possession before the electricity connection permitted by the competent Authority.
 20. The PP shall obtain the permission regarding withdrawal of ground water, if any from HWRA/CGWA before the start of the project and also obtained the CTO from HSPCB after the approval from HWRA/CGWA.
 21. The PP shall carry out the quarterly awareness programs for the stakeholders of the project.
 22. 14 Rain water harvesting recharge pits shall be provided for ground water recharging as per the CGWB norms
 23. The PP shall install Digital water level recorder for monitoring the water recharge and carry out quarterly maintenance and cleaning of 14RWH pits
 24. The PP shall provide the Anti smog gun mounted on vehicle in the project for suppression of dust during construction & operational phase and shall use the treated water, if feasible.
 25. The PP shall take all preventive measures including water sprinkles to control dust during construction and operational phase.
 26. Any change in stipulations of EC will lead to Environment Clearance void-ab-initio and PP will have to seek fresh Environment Clearance.
- B. Statutory Compliance:**
- [1] The project proponent shall obtain all necessary clearance/ permission from all relevant agencies including town planning authority for ground coverage, FAR and should be in accordance with zoning plan approved by Competent Authority before commencement of work. All the construction shall be done in accordance with the local building byelaws.
 - [2] The approval of the Competent Authority shall be obtained for structural safety of buildings due to earthquakes, adequacy of firefighting equipment etc as per National Building Code including protection measures from lightening etc.
 - [3] The project proponent shall obtain forest clearance under the provisions of Forest (Conservation) Act, 1986, in case of the diversion of forest land for non-forest purpose involved in the project.
 - [4] The project proponent shall obtain clearance from the National Board for Wildlife, if applicable.

- [5] The project proponent shall obtain Consent to Establish/Operate under the provisions of Air (Prevention & Control of Pollution) Act, 1981 and the Water (Prevention & Control of Pollution) Act, 1974 from the Haryana State Pollution Control Board.
- [6] The project proponent shall obtain the necessary permission for drawl of ground water /surface water required for the project from the competent authority.
- [7] A certificate of adequacy of available power from the agency supplying power to the project along with the load allowed for the project should be obtained.
- [8] All other statutory clearances such as the approvals for storage of diesel from Chief Controller of Explosives, Fire Department, Civil Aviation Department shall be obtained, as applicable, by project proponents from the respective competent authorities.
- [9] The provisions of the Solid Waste (Management) Rules, 2016, e-Waste (Management) Rules, 2016, the Plastics Waste (Management) Rules, 2016 and Batteries waste (Management Handling Rules 2001 as amended in 2020) shall be followed.
- [10] The project proponent shall follow the ECBC Act/ECBC-Rules prescribed by Bureau of Energy Efficiency, Ministry of Power strictly in addition of bylaws of the State Government.

I Air Quality Monitoring and Preservation

- 1) Notification GSR 94(E) dated 25.01.2018 of MoEF&CC regarding Mandatory Implementation of Dust Mitigation Measures for Construction and Demolition Activities for projects requiring Environmental Clearance shall be complied with.
- 2) A management plan shall be drawn up and implemented to contain the current exceedance in ambient air quality at the site.
- 3) The project proponent shall install system to carryout Ambient Air Quality monitoring for common/criterion parameters relevant to the main pollutants released (e.g. PM10 and PM2.5) covering upwind and downwind directions during the construction period.
- 4) Diesel power generating sets proposed as source of backup power should be of enclosed type and conform to rules made under the Environment (Protection) Act, 1986. The height of stack of DG sets should be equal to the height needed for the combined capacity of all proposed DG sets. Use of ultra lowsulphur diesel. The location of the DG sets may be decided with in consultation with State Pollution Control Board
- 5) Construction site shall be adequately barricaded before the construction begins. Dust, smoke & other air pollution prevention measures shall be provided for the building as well as the site. These measures shall include screens for the building under construction, continuous dust/ wind breaking walls all around the site (at least 3 meter height), Plastic/tarpaulin sheet covers shall be provided for vehicles bringing in sand, cement, murrum and other construction materials prone to causing dust pollution at the site as well as taking out debris from the site.
- 6) Sand, murrum, loose soil, cement, stored on site shall be covered adequately so as to prevent dust pollution.
- 7) Wet jet shall be provided for grinding and stone cutting.
- 8) Unpaved surfaces and loose soil shall be adequately sprinkled with water to suppress dust.
- 9) All construction and demolition debris shall be stored at the site (and not dumped on the roads or open spaces outside) before they are properly disposed. All demolition and construction waste shall be managed as per the provisions of the Construction and Demolition Waste Rules 2016.
- 10) The diesel generator sets to be used during construction phase shall be ultra lowsulphur diesel type and shall conform to Environmental (Protection) prescribed for air and noise emission standards.
- 11) The gaseous emissions from DG set shall be dispersed through adequate stack height as per CPCB standards. Acoustic enclosure shall be provided to the DG sets to mitigate the noise pollution. Ultra low sulphur diesel shall be used. The location of the DG set and exhaust pipe height shall be as per the provisions of the Central Pollution Control Board (CPCB) norms.
- 12) For indoor air quality the ventilation provisions as per National Building Code of India.

II Water Quality Monitoring and Preservation

1. The natural drain system should be maintained for ensuring unrestricted flow of water. No construction shall be allowed to obstruct the natural drainage through the site, on wetland and water bodies. Check dams, bio-swales, landscape, and other sustainable urban drainage systems (SUDS) are allowed for maintaining the drainage pattern and to harvest rain water.
2. Buildings shall be designed to follow the natural topography as much as possible. Minimum cutting and filling should be done.

3. Total fresh water use shall not exceed the proposed requirement as provided in the project details. The per capita supply should adhere to NBC 2016 and CGWA Notification dated 12.12.2018.
4. The quantity of fresh water usage, water recycling and rainwater harvesting shall be measured and recorded to monitor the water balance as projected by the project proponent. The record shall be submitted to the Regional Office, MoEF&CC along with six monthly Monitoring reports.
5. A certificate shall be obtained from the local body supplying water, specifying the total annual water availability with the local authority, the quantity of water already committed the quantity of water allotted to the project under consideration and the balance water available. This should be specified separately for ground water and surface water sources, ensuring that there is no impact on other users.
6. At least 20% of the open spaces as required by the local building bye-laws shall be pervious. Use of Grass pavers, paver blocks with at least 50% opening, landscape etc. would be considered as pervious surface.
7. Installation of dual pipe plumbing for supplying fresh water for drinking, cooking and bathing etc and other for supply of recycled water for flushing, landscape irrigation, car washing, thermal cooling, conditioning etc, shall be done.
8. Use of water saving devices/ fixtures (viz. low flow flushing systems; use of low flow faucets tap aerators etc) for water conservation shall be incorporated in the building plan.
9. Separation of grey and black water should be done by the use of dual plumbing system. In case of single stack system separate recirculation lines for flushing by giving dual plumbing system be done.
10. Water demand during construction should be reduced by use of pre-mixed concrete, curing agents and other best practices referred.
11. The local bye-law provisions on rain water harvesting should be followed. If local byelaw provision is not available, adequate provision for storage and recharge should be followed as per the Ministry of Urban Development Model Building Byelaws, 2016. Rain Water Harvesting pits shall be provided for ground water recharging as per the CGWB norms.
12. A rain water harvesting plan needs to be designed where the recharge bores of minimum one recharge bore per 5,000 square meters of built up area and storage capacity of minimum one day of total fresh water requirement shall be provided. In areas where ground water recharge is not feasible, the rain water should be harvested and stored for reuse. The ground water shall not be withdrawn without approval from the Competent Authority.
13. All recharge should be limited to shallow aquifer.
14. No ground water shall be used during construction phase of the project.
15. Any ground water dewatering should be properly managed and shall conform to the approvals and the guidelines of the CGWA in the matter. Formal approval shall be taken from the CGWA for any ground water abstraction or dewatering.
16. The quantity of fresh water usage, water recycling and rainwater harvesting shall be measured and recorded to monitor the water balance as projected by the project proponent. The record shall be submitted to the Regional Office, MoEF&CC along with six monthly Monitoring reports.
17. Sewage shall be treated in the STP with tertiary treatment. The treated effluent from STP shall be recycled/re-used for flushing, AC make up water and gardening. As proposed, no treated water shall be disposed in to municipal drain.
18. No sewage or untreated effluent water would be discharged through storm water drains.
19. Onsite sewage treatment of capacity of treating 100% waste water to be installed. The installation of the Sewage Treatment Plant (STP) shall be certified by an independent expert and a report in this regard shall be submitted to the Ministry before the project is commissioned for operation. Treated waste water shall be reused on site for landscape, flushing, cooling tower, and other end-uses. Excess treated water shall be discharged as per statutory norms notified by Ministry of Environment, Forest and Climate Change. Natural treatment systems shall be promoted.
20. Periodical monitoring of water quality of treated sewage shall be conducted. Necessary measures should be made to mitigate the odour problem from STP.
21. Sludge from the onsite sewage treatment, including septic tanks, shall be collected, conveyed and disposed as per the Ministry of Urban Development, Central Public Health and Environmental Engineering Organization (CPHEEO) Manual on Sewerage and Sewage Treatment Systems, 2013.

III Noise Monitoring and Prevention

1. Ambient noise levels shall conform to residential area/commercial area both during day and night as per Noise Pollution (Control and Regulation) Rules, 2000. Incremental pollution loads on the ambient air and noise quality shall be closely monitored during construction phase. Adequate measures shall be made to reduce ambient air and noise level during construction phase, so as to conform to the stipulated standards by CPCB / SPCB.
2. Noise level survey shall be carried as per the prescribed guidelines and report in this regard shall be submitted to Regional Officer of the Ministry as a part of six-monthly compliance report.
3. Acoustic enclosures for DG sets, noise barriers for ground-run bays, ear plugs for operating personnel shall be implemented as mitigation measures for noise impact due to ground sources.

IV Energy Conservation Measures

1. Compliance with the Energy Conservation Building Code (ECBC) of Bureau of Energy Efficiency as per ECBC Act, 2017 read with ECBC Rules, 2018 shall be ensured. Buildings in the States which have notified their own ECBC, shall comply with the State ECBC also which is in no case should be less than 25% as prescribed.
2. Outdoor and common area lighting shall be LED.
3. Concept of passive solar design that minimize energy consumption in buildings by using design elements, such as building orientation, landscaping, efficient building envelope, appropriate fenestration, increased day lighting design and thermal mass etc. shall be incorporated in the building design. Wall, window, and roof R & U-values shall be as per ECBC specifications.
4. Energy conservation measures like installation of CFLs/ LED for the lighting the area outside the building should be integral part of the project design and should be in place before project commissioning.
5. Solar, wind or other Renewable Energy shall be installed to meet electricity generation equivalent to 1% of the demand load or as per the state level/ local building bye-laws requirement, whichever is higher.
6. Solar power shall be used for lighting in the apartment to reduce the power load on grid. Separate electric meter shall be installed for solar power. Solar water heating shall be provided to meet 20% of the hot water demand of the commercial and institutional building or as per the requirement of the local building bye-laws, whichever is higher. Residential buildings are also recommended to meet its hot water demand from solar water heaters, as far as possible.
7. The PP will submit report indicating compliance of each parameter of ECBC requirement and submit quantification saving report for each component.

V Waste Management

- 1) A certificate from the competent authority handling municipal solid wastes, indicating the existing civic capacities of handling and their adequacy to cater to the M.S.W. generated from project shall be obtained.
- 2) Disposal of muck during construction phase shall not create any adverse effect on the neighbouring communities and be disposed taking the necessary precautions for general safety and health aspects of people, only in approved sites with the approval of competent authority.
- 3) Separate wet and dry bins must be provided in each unit and at the ground level for facilitating segregation of waste. Solid waste shall be segregated into wet garbage and inert materials.
- 4) Organic Waste Converter within the premises with a minimum capacity of 0.5 kg /person/day must be installed. Leaves to be put in earmarked pits for converting them into compost to be used as manure.
- 5) All non-biodegradable waste shall be handed over to authorized recyclers for which a written tie up must be done with the authorized recyclers.
- 6) Any hazardous waste generated during construction phase, shall be disposed of as per applicable rules and norms with necessary approvals of the State Pollution Control Board.
- 7) Use of environment friendly materials in bricks, blocks and other construction materials, shall be required for at least 20% of the construction material quantity. These include Fly Ash bricks, hollow bricks, AACs, Fly Ash Lime Gypsum blocks, Compressed earth blocks, and other environment friendly materials.
- 8) Fly ash should be used as building material in the construction as per the provision of Fly Ash Notification of September, 1999 and amended as on 27th August, 2003 and 25th January, 2016. Ready mixed concrete must be used in building construction.

- 9) Any wastes from construction and demolition activities related thereto shall be managed so as to strictly conform to the Construction and Demolition Rules, 2016.
- 10) Used CFLs and TFLs should be properly collected and disposed off/sent for recycling as per the prevailing guidelines/ rules of the regulatory authority to avoid mercury contamination.

VI Green Cover

- 1) No tree can be felled/transplant unless exigencies demand. Where absolutely necessary, tree felling shall be with prior permission from the concerned regulatory authority. Old trees should be retained based on girth and age regulations as may be prescribed by the Forest Department. Plantations to be ensured species (cut) to species (planted).
- 2) A minimum of 1 tree (5' tall) for every 80 sqm of land should be planted and maintained. The existing trees will be counted for this purpose. The landscape planning should include plantation of native species. The species with heavy foliage, broad leaves and wide canopy cover are desirable. Water intensive and/or invasive species should not be used for landscaping.
- 3) Where the trees need to be cut with prior permission from the concerned local Authority, compensatory plantation in the ratio of 1:10 (i.e. planting of 10 trees for every 1 tree that is cut) shall be done and maintained. Plantations to be ensured species (cut) to species (planted). Area for green belt development shall be provided as per the details provided in the project document.
- 4) Topsoil should be stripped to a depth of 20 cm from the areas proposed for buildings, roads, paved areas, and external services. It should be stockpiled appropriately in designated areas and reapplied during plantation of the proposed vegetation on site.

VII Transport

1. A comprehensive mobility plan, as per MoUD best practices guidelines (URDPFI), shall be prepared to include motorized, non-motorized, public, and private networks. Road should be designed with due consideration for environment, and safety of users. The road system can be designed with these basic criteria.
 - a) Hierarchy of roads with proper segregation of vehicular and pedestrian traffic.
 - b) Traffic calming measures.
 - c) Proper design of entry and exit points.
 - d) Parking norms as per local regulation.
2. Vehicles hired for bringing construction material to the site should be in good condition and should have a pollution check certificate and should conform to applicable air and noise emission standards be operated only during non-peak hours.
3. A detailed traffic management and traffic decongestion plan shall be drawn up to ensure that the current level of service of the roads within a 05 kms radius of the project is maintained and improved upon after the implementation of the project. This plan should be based on cumulative impact of all development and increased habitation being carried out or proposed to be carried out by the project or other agencies in this 05 Kms radius of the site in different scenarios of space and time and the traffic management plan shall be duly validated and certified by the State Urban Development department and the P.W.D./ competent authority for road augmentation and shall also have their consent to the implementation of components of the plan which involve the participation of these departments.

VIII Human Health Issues

1. All workers working at the construction site and involved in loading, unloading, carriage of construction material and construction debris or working in any area with dust pollution shall be provided with dust mask.
2. For indoor air quality the ventilation provisions as per National Building Code of India.
3. Emergency preparedness plan based on the Hazard identification and Risk Assessment (HIRA) and Disaster Management Plan shall be implemented.
4. Provision shall be made for the housing of construction labour within the site with all necessary infrastructure and facilities such as fuel for cooking, mobile toilets, mobile STP, safe drinking water, medical health care, crèche etc. The housing may be in the form of temporary structures to be removed after the completion of the project.
5. Occupational health surveillance of the workers shall be done on a regular basis.
6. A First Aid Room shall be provided in the project both during construction and operations of the project.

IX Corporate Environment Responsibility

1. The project proponent shall comply with the provisions of CER, as applicable.
2. The company shall have a well laid down environmental policy duly approved by the Board of Directors. The environmental policy should prescribe for standard operating procedures to have proper checks and balances and to bring into focus any infringements/ deviation/ violation of the environmental/ forest/ wildlife norms/ conditions. The company shall have defined system of reporting infringements/ deviation/ violation of the environmental/ forest/ wildlife norms/ conditions and/ or shareholders/ stake holders. The copy of the board resolution in this regard shall be submitted to the MoEF&CC as a part of six-monthly report.
3. A separate Environmental Cell both at the project and company head quarter level, with qualified personnel shall be set up under the control of senior Executive, who will directly to the head of the organization.
4. Action plan for implementing EMP and environmental conditions along with responsibility matrix of the company shall be prepared and shall be duly approved by competent authority. The year wise funds earmarked for environmental protection measures shall be kept in separate account and not to be diverted for any other purpose. Year wise progress of implementation of action plan shall be reported to the Ministry/Regional Office along with the Six Monthly Compliance Report.

X Miscellaneous

- 1) The project proponent shall prominently advertise it at least in two local newspapers of the District or State, of which one shall be in the vernacular language within seven days indicating that the project has been accorded environment clearance and the details of MoEFCC/SEIAA website where it is displayed.
- 2) The copies of the environmental clearance shall be submitted by the project proponents to the Heads of local bodies, Panchayats and Municipal Bodies in addition to the relevant offices of the Government who in turn has to display the same for 30 days from the date of receipt.
- 3) The project proponent shall upload the status of compliance of the stipulated environment clearance conditions, including results of monitored data on their website and update the same on half-yearly basis.
- 4) The project proponent shall submit six-monthly reports on the status of the compliance of the stipulated environmental conditions on the website of the ministry of Environment, Forest and Climate Change at environment clearance portal.
- 5) The project proponent shall submit the environmental statement for each financial year in Form-V to the concerned State Pollution Control Board as prescribed under the Environment (Protection) Rules, 1986, as amended subsequently and put on the website of the company.
- 6) The project proponent shall inform the Regional Office as well as the Ministry, the date of financial closure and final approval of the project by the concerned authorities, commencing the land development work and start of production operation by the project.
- 7) The project authorities must strictly adhere to the stipulations made by the State Pollution Control Board and the State Government.
- 8) The project proponent shall abide by all the commitments and recommendations made in the form-IA, Conceptual Plan and also that during their presentation to the Expert Appraisal Committee.
- 9) No further expansion or modifications in the plan shall be carried out without prior approval of the Ministry of Environment, Forests and Climate Change (MoEF&CC)/SEIAA, Haryana. The project proponent shall seek fresh environmental clearance under EIA notification 2006 if at any stage there is change of area of this project.
- 10) Any change in planning of the approved plan will leads to Environment Clearance voidab-initio and PP will have to seek fresh Environment Clearance
- 11) The PP should give unambiguous affidavit giving land promoters in accordance with your ownership and possession of land legal the case referred for Environment Clearance to SEIAA.
- 12) Concealing factual data or submission of false/fabricated data may result in revocation of this environmental clearance and attract action under the provisions of Environment (Protection) Act, 1986.
- 13) The Ministry/SEIAA may revoke or suspend the clearance, if implementation of any of the above conditions is not satisfactory.
- 14) The Ministry/SEIAA reserves the right to stipulate additional conditions if found necessary. The Company in a time bound manner shall implement these conditions.
- 15) The Regional Office of this Ministry shall monitor compliance of the stipulated conditions. The project authorities should extend full cooperation to the officer (s) of the Regional

- Office by furnishing the requisite data / information/monitoring reports.
- 16) The above conditions shall be enforced, inter-alia under the provisions of the Water (Prevention & Control of Pollution) Act, 1974, the Air (Prevention & Control of Pollution) Act, 1981, the Environment (Protection) Act, 1986, Hazardous and Other Wastes (Management and Transboundary Movement) Rules, 2016 and the Public Liability Insurance Act, 1991 along with their amendments and Rules and any other orders passed by the Hon'ble Supreme Court of India / High Courts and any other Court of Law relating to the subject matter.
- 17) The validity of this environment clearance letter is valid up to 10 years from the date of issuance of EC letter (As per MoEF & CC, GoI Notification dated 12.04.2022). The environment clearance conditions applicable till life space project will continue to apply. In case of violation the action would be taken as per the laid down law of land. Compliance report should be sent to this office till life of the project.
- 18) If project is not completed within the validity period then the project proponent shall submit the application for extension of validity within one month before the lapse of validity period of Environment Clearance i.e. 10 years.
- 19) The Project Proponent should intimate to the Authority as well as to the quarter concerned in case of any change in the present communication address.

(Pardeep Kumar, IAS)
Member Secretary,
State Level Environment Impact
Assessment Authority, Haryana, Panchkula

A copy of the above is forwarded to the following:

1. Director (IA Division), MoEF & CC, GoI, Indira Paryavaran Bhavan, Zor bagh Road-New Delhi-110003.
2. Chairman, State Environment Impact Assessment Authority, Bay No. 55-58, Prayatan Bhawan, Sector-2, Panchkula, Haryana
3. Chairman, Haryana State Pollution Control Board, C-11, Sector-6, Panchkula with a request to ensure the conditions meticulously before issuing the consents.
4. Director, Environment & Climate Change Department, Haryana, Bay No. 55-58, Prayatan Bhawan, Sector-2, Panchkula, Haryana
5. Director General, Town & Country Planning Haryana, Plot No. 3, Sector - 18A, Madhya Marg, Chandigarh- 160018 with a request to ensure the conditions meticulously before issuing Occupation Certificate.
6. Regional Office, Ministry of Environment, Forests & Climate Change, Govt. of India, Bay's No. 24-25, Sector 31-A, Dakshin Marg, Chandigarh-160018.
7. Concerned File/ Office Copy

(Pardeep Kumar, IAS)
Member Secretary,
State Level Environment Impact
Assessment Authority, Haryana, Panchkula

Signature Not Verified
Digitally signed by Sh. Pardeep
Kumar, IAS
Member Secretary
Date: 9/25/2022 12:44:18 PM