

This is a PROVISIONAL APPROVED BUILDING PLAN
only for purpose of inviting
objection from the general public

(T.L.SATYAPRAKASH, IAS)
DG, TCP (HR.)


(H.SINGH)
CP (HR.)

(HITESH SHARMA)
STP(M) HQ


(S.K.SEHWAT)
DTP(HQ)

(RAJAT CHAUHAN)
ATP (HQ)


(RAJESH DUTT)
JD (HQ)



SECTION - XX



ELEVATION REAR



AREA CHART

PROPOSED GROUND FLOOR FAR -
= (A)
= 441.090 Sq.Mt

PROPOSED FIRST FLOOR FAR
= (A) - (1+2)
= 441.090 - (11.520 + 3.240)
= 441.090 - 14.760
= 426.330 Sq.Mt

PROPOSED SECOND FLOOR FAR
= SAME AS FIRST FLOOR AREA
= 426.330 Sq.Mt

PROPOSED THIRD FLOOR FAR
= SAME AS FIRST FLOOR AREA
= 426.330 Sq.Mt

TOTAL FAR
= (GROUND+FIRST+SECOND+THIRD)
= 441.090 + 426.330 + 426.330 + 426.330 Sq.Mt
= 1720.080 Sq.Mt.

TOTAL NON FAR


STAIRCASE WELL, LIFT & MUMTY
= (TYP. FL. STAIRCASE + LIFT X 4) + MUMTY
= ((1+2) X 4) + Z
= ((11.520 + 3.240) X 4) + 20.849
= (59.040 + 20.849) = 79.889 Sq. Mt.

PROPOSED NON FAR BASEMENT
= (A) = 441.090 Sq. Mt.


TOTAL NON FAR = 79.889 + 441.090 = 520.979 Sq.Mt.

	X (MTRS)	Y (MTRS)	AREA (SQ. MTRS)
A	24.505	18.000	441.090
1	2.400	4.800	11.520
2	1.800	1.800	3.240
Z	2.880	7.290	20.849

AREA DIAGRAM



ELEVATION FRONT



SECTION - YY

S.NO	TYPE	SIZE	CILL LEVEL	LINTEL LEVEL
1	D-01	1000 x 2400	---	2400
2	D-02	750 x 2400	---	2400
3	D/W	5310 x 2800	---	2800
4	VV-01	5310 x 2800	---	2800
5	VV-02	1800 x 2800	---	2800
6	VV-03	600 x 1200	1200	2400
7				
8				

M/s GILLSON CHITS PVT. LTD. IN COLLABORATION WITH
M/s BRISK INFRASTRUCTURE & DEVELOPERS PVT. LTD.

REVISED STANDARD DESIGN COMMERCIAL PLOTTED COLONY OVER
AN AREA MEASURING 3.6423 ACRES IN THE REVENUE ESTATE OF
VILLAGE- CHAUMA IN SECTOR -109, GURUGRAM- MANESAR URBAN
COMPLEX

OWNERS SIGNATURE

Arch. M. Plan(Housing)
Reg. No: CA/2016/79479
Mob: 9569556600
ar.abhishekgoyal2016@gmail.com

ARCHITECT'S SIGNATURE

SECTIONS & ELEVATIONS

SHEET SCO NO. - 02

scale-N.T.S.

ARCHDECK ASSOCIATES
#567, SECTOR-27, GURUGRAM-122001
Email id: info@archdeckassociates.com
Contact - +91-9569556600

05
SHEET NO.

DRG NO:- D4TCP 985.5 (V) DT 28-08-23