










S.NO.	TYPE	SIZE	CILL LEVEL	LINTEL LEVEL
1	D-01	1200 x 2400	---	2400
2	D-02	750 x 2400	---	2400
3	W-01	4923 x 2800	---	2800
4	W-02	5055 x 2800	---	2800
5	W-03	600 x 1200	1200	2400
6	W-04	2400 x 2800	---	2800
7	DW	4923 x 2800	---	2800

X (MTRS)	Y (MTRS)	AREA (SQ. MTRS)
A	13.445	15.000
B	11.888	15.000/2
1	2.400	3.600
2	1.800	1.800
Z	4.140	4.890

This is a PROVISIONAL APPROVED BUILDING PLAN only for purpose of inviting objection from the general public.



AREA CHART

PROPOSED GROUND FLOOR FAR -
 = (A+B) - (1+2) - SHAFT
 = (201.825 + 87.660) - (8.640 + 3.240) - (2.881 X 3.446)
 = 289.485 Sq. Mt.

PROPOSED FIRST FLOOR FAR
 = (A+B) - (1+2) - SHAFT
 = (201.825 + 87.660) - (8.640 + 3.240) - (2.881 X 3.446)
 = 272.985 Sq. Mt.

PROPOSED SECOND FLOOR FAR
 = SAME AS FIRST FLOOR AREA
 = 272.985 Sq. Mt.

PROPOSED THIRD FLOOR FAR
 = SAME AS SECOND FLOOR AREA
 = 272.985 Sq. Mt.

PROPOSED FOURTH FLOOR FAR
 = SAME AS THIRD FLOOR AREA
 = 272.985 Sq. Mt.

TOTAL FAR
 = (GROUND+FIRST+SECOND+THIRD+FOURTH)
 = 289.485 + 272.985 + 272.985 + 272.985 + 272.985
 = 1381.425 Sq. Mt.

TOTAL NON FAR
 = (TYP. FL. STAIRCASE + SHAFT + LIFT X 4) + MUMTY
 = ((1+2+SHAFT) X 4) + (2)
 = ((8.640 + 3.240 + 4.620) X 4) + (2.244)
 = (16.500 + 20.244) = 36.744 Sq. Mt.

PROPOSED NON FAR BASEMENT
 = (A+B) = 277.805 Sq. Mt.

TOTAL NON FAR = 86.244 + 277.805 = 363.849 Sq. Mt.

M/s GILLSON CHITS PVT. LTD. IN COLLABORATION WITH
 M/s BRISK INFRASTRUCTURE & DEVELOPERS PVT. LTD.

REVISED STANDARD DESIGN COMMERCIAL PLOTTED COLONY
 OVER AN AREA MEASURING 3.6423 ACRES IN THE REVENUE ESTATE
 OF VILLAGE- CHAUMA IN SECTOR -109, GURUGRAM- MANESAR
 URBAN COMPLEX

OWNER'S SIGNATURE

PLANS & ELEVATIONS

SHEET SCO NO. - 11

scale-N.T.S.

ARCHITECT'S SIGNATURE

ARCHDECK ASSOCIATES

#587, SECTOR-27, GURUGRAM-122001

Email id- info@archdeckassociates.com

Contact - +91-9569556600

(T.L.SATYAPRAKASH, IAS)
 DG, TCP (HR.)

(P.P.SINGH)
 C.E. (HR.)

(HITESH SHARMA)
 STP(M) HQ

(S.K.SEHRAWAT)
 DTP(HQ)

(RAJAT CHAUHAN)
 ATP (HQ)

(RAJESH DUTT)
 JD (HQ)

DRG. NO. - DGT-9525 (XIV) DT 28-8-23