LAYOUT CUM DEMARCATION PLAN OF AFFORDABLE RESIDENTIAL PLOTTED COLONY UNDER DEEN DAYAL JAN AWAS YOJANA OVER AN AREA MEASURING 13.9125 ACRES(LICENCE NO.39 OF 2018 DATED 09.06.2018) IN THE REVENUE ESTATE OF VILLAGE RAWALAN, SECTOR -42, AMBALA CANTT., DISTRICT AMBALA (HARYANA), BEING DEVELOPED BY M/S HERMAN PROPERTIES PVT. LTD. & OTHERS.

AREA CHART

S.NO.	PARTICULARS	PROPOSAL (IN ACRES)	PROPOSAL %	PERMISSIBLE (IN ACRES)	PERMISSIBLE %
1.	AREA OF THE SCHEME	13.9125	-	5 TO 15	-
2.	AREA UNDER PLOTS	7.7924	56.01	8.4995	61.0
3.	AREA UNDER COMMERCIAL	0.3237	2.33	0.5565	4.0
4.	TOTAL SALEABLE AREA(2+3)	8.1161	58.34	9.0451	65.0
5.	OPEN SPACE / PARKS	1.0507	7.55	1.0434	7.50
6.	AREA UNDER COMMUNITY FACILITIES	1.3918	10.0	1.3912	10.0

DEATIL OF PLOTS

S.NO.	CATEGORY	PLOT NO.	SIZE (IN MTRS)	AREA (IN SQ.MTRS)	PLOT NOS.	TOTAL AREA (IN SQ.MTRS)
1.	A	1-6	7.60 X 19.00	134.53	6	805.68
		7	9.00 THE FIGURE	146.445	1	146.445
2.	B	8	9.00 THE FIGURE	99.44	1	99.44
		9	9.00 THE FIGURE	107.09	1	107.09
		10	9.00 THE FIGURE	107.26	1	107.26
		11	9.00 THE FIGURE	149.279	1	149.279
		12	9.00 THE FIGURE	148.28	1	148.28
		13	9.00 THE FIGURE	140.305	1	140.305
		14-19	6.69 X 16.08	110.11	6	660.66
		20	5.47 X 16.08	106.13	1	106.13
		21	5.86 X 16.08	105.55	1	105.55
3.	C	22	9.00 THE FIGURE	149.10	1	149.10
		23-39	7.31 X 18.00	138.78	17	1006.26
		40	9.00 THE FIGURE	138.33	1	138.33
4.	D	41-61, 84-84	7.54 X 16.00	120.64	42	5066.88
		62	9.00 THE FIGURE	149.04	1	149.04
		63	9.00 THE FIGURE	130.64	1	130.64
5.	E	64-83	9.00 THE FIGURE	120.64	20	2412.80
6.	I	135-62	6.79 X 16.00	90.64	49	4440.72
		136-139	6.77 X 20.00	148.64	3	445.92
		170-189, 172-205	5.72 X 22.00	126.84	69	8507.12
		171	9.00 THE FIGURE	149.49	1	149.49
7.	J	206	9.00 THE FIGURE	134.75	1	134.75
		207	7.78 X 17.92	139.42	1	139.42
		207-235, 236-266	6.71 X 17.92	120.24	58	6973.92
		236	120.24 SQ.MTR	120.65	1	120.65
		237	120.24 SQ.MTR	109.74	1	109.74
8.	TOTAL				205	31554.805 SQMT 7.7924 ACRES(56.01%)

AREA CHART - COMMERCIAL:



AREA CHART - UNDERGROUND SEWAGE TREATMENT PLANT(U.G.S.T.P.):

AREA CHART - MISCELLANEOUS PLOTS: 7, 8, 10, 11, 12 & 13:





AREA CHART - COMMUNITY FACILITIES

AREA CHART - MISCELLANEOUS PLOTS: 27, 40, 61, 63, 170 & 171



AREA CHART - OPEN SPACES/ PARKS:



To be read with Licence No. 39 of 2018 Dated 09-06-2018

That this **Layout-cum-demarcation plan for an area measuring 13.9125 acres (Drawing No. DTCP-6700 dated 24.01.2019) comprised of licence which is issued in respect of Affordable Residential Plotted Colony (Under Deen Dayal Jan Awas Yojna) being developed by Herman Properties Pvt. Ltd. & others in revenue estate of Village Rawalan, Sector- 42, District Ambala** is hereby approved subject to the following conditions:

1. That this **Layout-cum-demarcation Plan** shall be read in conjunction with the clauses appearing on the Agreement executed under Rule 11 and the bilateral agreement.
2. That the plotted area of the colony shall not exceed 65% of the net planned area of the colony. The entire area reserved for commercial purposes shall be taken as plotted for calculation of the area under plots.
3. That the demarcation plans as per site of all the Residential Plots and Commercial site shall be got approved from this Department and construction on these sites shall be governed by the Haryana Building Code, 2017 and the Zoning Plan approved by the Director, Town & Country Planning, Haryana.
4. That for proper planning and integration of services in the area adjacent to the colony, the colonizer shall abide by the directions of the DTCP for the modification of layout plans of the colony.
5. That the revenue rasta falling in the colony shall be kept free for circulation/movement as shown in the layout plan.
6. That the colonizer shall abide by the directions of the DTCP, Haryana and accordingly shall make necessary changes in the layout plan for making any adjustment in the alignment of the peripheral roads, internal road circulation or for proper integration of the planning proposals of the adjoining areas.
7. That no property/plot shall derive access directly from the carriage way of 30 metres or wider sector road if applicable.
8. All green belts provided in the layout plan within the licenced areas of the colony shall be developed by the colonizer. All other green belts outside the licenced area shall be developed by the Haryana Urban Development Authority/colonizer on the directions of the Director, Town and Country planning, Haryana or in accordance with terms and conditions of the Agreements of the licence.
9. At the time of demarcation plan, if received percentage of organized open space is reduced, the same will be provided by the colonizer in the licenced area.
10. No plot will derive an access from less than 9 metres wide road would mean a minimum clear width of 9 metres between the plots.
11. Any excess area over and above the permissible 4% under commercial use shall be deemed to be open space.
12. The portion of the sector/development plan roads /green belts as provided in the Development Plan if applicable, which form part of the licenced area shall be transferred free of cost to the government on the lines of Section 3(3)(d)(ii) of the Act No.8 of 1975.
13. That the sale/lease plan is not being approved subject to the conditions that these plots should not have a frontage of less than 75% of the standard frontage when demarcated.
14. That you will have no objection to the regularization of the boundaries of this licence through give and take with this land that HUDA is finally able to acquire in the interest of planned development and integration of services. The decision of the competent authority shall be binding in this regard.
15. That the rain water harvesting system shall be provided as per Central Ground Water Authority norms/Haryana Govt. notification as applicable.
16. That the colonizer/owner shall use only Light-Emitting Diode lamps (LED) fitting for internal lighting as well as Street Lighting.
17. That the colonizer/owner shall ensure the installation of Solar Photovoltaic Power Plant as per the provisions of order No.23/32/2005-5Power dated 21.03.2016 issued by Haryana Government Renewable Energy Department.
18. That the colonizer/owner shall strictly comply with the directions issued vide Notification No. 19/5/2015-1P dated 11.03.2016 issued by Haryana Government Renewable Energy Department for enforcement of the Energy Conservation Building Code.

(DIVESH NAIR) IS (HQ)

(S.K. SAINI) ATP (HQ)

(VIJENDER KUMAR) ATP (HQ)

(R.K. GOYAL) ATP (HQ)

(DIVESH GUPTA) ATP (HQ)

(K. PRAKASH) ATP (HQ)

(K. PRAKASH PANTURANG) ATP (HQ)

N

W E

S

LAYOUT CUM DEMARCATION PLAN
(SCALE-N.T.S.)

For Herman Properties (P) Ltd.
Authorised Signatory

SIGNATURE OF APPLICANT

Ar. MONU SHARMA
CA/2016/76557
NEELKANTH ASSOCIATES
First Floor, Gohana Chowk,
G.T. Road, PANIPAT
(M)-98139-90375

SIGNATURE OF ARCHITECT

DETAIL OF 65% RESIDENTIAL PLOTTED AREA AS REQUIRED TO BE FREEZED AS PER POLICY (7.5062 ACRES)
DETAIL OF RESIDENTIAL PLOTS OFFERED BY THE LICENSEE TO BE FREEZED

S.NO.	CATEGORY	PLOT NO.	SIZE (IN MTRS)	AREA (IN SQ.MTRS)	PLOT NOS.	TOTAL AREA (IN SQ.MTRS)
1.	A	1-6	7.60 X 19.00	134.53	6	805.68
		7	9.00 THE FIGURE	146.445	1	146.445
2.	B	8	9.00 THE FIGURE	99.44	1	99.44
		9	9.00 THE FIGURE	107.09	1	107.09
		10	9.00 THE FIGURE	107.26	1	107.26
		11	9.00 THE FIGURE	149.279	1	149.279
		12	9.00 THE FIGURE	148.28	1	148.28
		13	9.00 THE FIGURE	140.305	1	140.305
		14-19	6.69 X 16.08	110.11	6	660.66
		20	5.47 X 16.08	106.13	1	106.13
		21	5.86 X 16.08	105.55	1	105.55
3.	C	22	9.00 THE FIGURE	149.10	1	149.10
		23-39	7.31 X 18.00	138.78	17	1006.26
		40	9.00 THE FIGURE	138.33	1	138.33
4.	D	41-61, 84-84	7.54 X 16.00	120.64	42	5066.88
		62	9.00 THE FIGURE	149.04	1	149.04
		63	9.00 THE FIGURE	130.64	1	130.64
5.	E	64-83	9.00 THE FIGURE	120.64	20	2412.80
6.	I	135-62	6.79 X 16.00	90.64	49	4440.72
		136-139	6.77 X 20.00	148.64	3	445.92
		170-189, 172-205	5.72 X 22.00	126.84	69	8507.12
		171	9.00 THE FIGURE	149.49	1	149.49
7.	J	206	9.00 THE FIGURE	134.75	1	134.75
		207	7.78 X 17.92	139.42	1	139.42
		207-235, 236-266	6.71 X 17.92	120.24	58	6973.92
		236	120.24 SQ.MTR	120.65	1	120.65
		237	120.24 SQ.MTR	109.74	1	109.74
8.	TOTAL				205	31554.805 SQMT 7.7924 ACRES(56.01%)

DETAIL OF 35% RESIDENTIAL PLOTS AS REQUIRED TO BE MORTGAGE AS PER POLICY (1.10806 ACRES)
DETAIL OF RESIDENTIAL PLOTS OFFERED BY THE LICENSEE TO BE MORTGAGE

S.NO.	CATEGORY	PLOT NO.	SIZE (IN MTRS)	AREA (IN SQ.MTRS)	PLOT NOS.	TOTAL AREA (IN SQ.MTRS)
1.	I	145-134, 179-205	6.72 X 20.00	120.64	37	4464.08
2.	TOTAL				37	4464.08 SQMT (1.1035 ACRES(14.79%))

LEGEND:
E.T. – ELECTRIC TRANSFORMER AREA – 2.0 X 2.0 = 4.00 SQMT
U/G – UNDERGROUND WATER TANK
T.W. – TUBE WELL
U/G S.T.P. – UNDERGROUND SEWAGE TREATMENT PLANT
PARKS / OPEN SPACES
COMMERCIAL AREA
COMMUNITY FACILITIES
MURLA LINE
KILLA LINE
SCHEME BOUNDARY

ABBREVIATIONS:
I.G. – INCIDENTAL GREEN
E.T. – ELECTRIC TRANSFORMER
S.T.P. – SEWAGE TREATMENT PLANT