




PLOT AREA DETAIL								
PLOT NO	TYPE	LENGHT	WIDTH	AREA SQMTRS	GAZ	NO. OF PLOT	TOTAL AREA IN SQMT	TOTAL AREA IN GAZ
1-9	A	18.004	7.020	126.388	151.16	9	1137.493	1360.441
10-12	B	16.351	8.337	136.318	163.04	3	408.955	489.110
13	B1	16.351	8.336	136.302	163.02	1	136.302	163.017
14-16	C	16.351	8.250	134.896	161.34	3	404.687	484.006
17	C1	16.351	8.248	134.863	161.30	1	134.863	161.296
18	D1	15.000	7.079	106.185	127.00	1	106.185	126.997
19-26	D	15.000	7.078	106.170	126.98	8	849.360	1015.835
27	C1	16.351	8.248	134.863	161.30	1	134.863	161.296
28-30	C	16.351	8.250	134.896	161.34	3	404.687	484.006
31	B-1	16.351	8.336	136.302	163.02	1	136.302	163.017
32-37	B	16.351	8.337	136.318	163.04	6	817.910	978.220
38	B-1	16.351	8.336	136.302	163.02	1	136.302	163.017
39-41	C	16.351	8.250	134.896	161.34	3	404.687	484.006
42	C1	16.351	8.248	134.863	161.30	1	134.863	161.296
43-44	E	16.102	7.000	112.714	134.81	2	225.428	269.612
45-56	F	15.234	7.353	112.016	133.97	12	1344.187	1607.648
57	F1	15.234	7.362	112.153	134.13	1	112.153	134.135
58	G1	15.234	7.058	107.522	128.60	1	107.522	128.596
59-67	G	15.234	7.060	107.552	128.63	9	967.968	1157.690
68	H1	15.235	7.052	107.437	128.49	1	107.437	128.495
69-72	H	15.235	7.049	107.392	128.44	4	429.566	513.761
73-92	I	18.893	7.070	133.574	159.75	20	2671.470	3195.078
93-97	I1	18.894	7.070	133.581	159.76	5	667.903	798.812
98-114	J	16.000	6.428	102.848	123.01	17	1748.416	2091.106
115	J1	16.000	6.424	102.784	122.93	1	102.784	122.930
TOTAL NO. OF PLOTS						115	13832.293	16543.423



AREA STATEMENT			
S.NO	PERCENTAGE	AREA IN SQ.MT	AREA IN ACERS
TOTAL AREA OF SITE		25823.962	6.38125
PERMISSIBLE AREA UNDER RESIDENTIAL PLOT	61%	15752.617	3.893
PERMISSIBLE AREA UNDER COMMERCIAL PLOT	4%	1032.958	0.255
GREEN AREA	7.50%	1936.797	0.479
AREA UNDER COMMUNITY AREA	10%	2582.396	0.638
PROPOSED AREA			
PROPOSED RESIDENTIAL AREA	53.56%	13832.293	3.418
COMMERCIAL AREA	3.10%	800.318	0.198
GREEN AREA	7.52%	1942.537	0.480
COMMUNITY AREA	10%	2582.413	0.638
TOTAL SALABLE AREA (PLOT AREA + COMMERCIAL AREA)	56.66%	14632.611	3.616
MIN.MAX. PERMISSIBLE DENCITY	240-400		PPA
DENSITY CALCULATION			
	115	X	13.5
			+
			6.38125
		243	PPA



DEMARCATIION - CUM - ZONING PLAN OF AFFORDABLE RESIDENTIAL PLOTTED COLONY UNDER DEEN DAYAL JAN AWAS YOJANA-2016 OVER AN AREA MEASURING 6.38125 ACRES BEARING LICENSE NO. 61 OF 2024 DATED 13.06.2024 IN THE REVENUE ESTATE OF VILLAGE RATHDHANA, SECTOR 35 , TEH. & DISTT. SONIPAT, HARYANA. BEING DEVELOPED BY M/s SKYLARK FLYING REAL ESTATE PRIVATE LIMITED.

FOR PURPOSE OF CODE 1.2 (xcvi) & 6.1 (1) OF THE HARYANA BUILDING CODE, 2017, AS AMENDED FROM TIME TO TIME.

- USE ZONE**
The land shown in this zoning plan shall be utilized in accordance with the marking explained in the table below and no other manner whatsoever:

Notation	Permissible use of land on the portion of the plot marked in column 1	Type of building permissible on land marked in column 1.
	Road	Road furniture at approved places.
	Public open space	To be used only for landscape features.
	Residential buildable zone	Residential building.
	Commercial	As per supplementary zoning plan to be approved separately for each site.
	Community	To be used for community facilities buildings.
- MAXIMUM PERMISSIBLE GROUND COVERAGE BASEMENT, FAR AND MAXIMUM PERMISSIBLE HEIGHT / INCLUDING STILT PARKING**
 - The building or buildings shall be constructed only with in the portion of the site marked as buildable zone as explained above, and nowhere else.
 - The Planning parameter to be adopted is as below:-

Plot Area	Maximum Permissible Ground Coverage	Permissible Basement	Maximum Permissible Floor Area Ratio (FAR)	Maximum permissible Height (in.metres)
Upto 150 square metres	75%	Single Level	200%	16.5 M
 - The stilts are permitted for parking purpose in residential plots of all sizes.
- PERMISSIBLE NUMBER OF DWELLING UNIT ON EACH PLOT**
No. of dwelling unit permitted on each plot : 3 (Three)
- BAR ON SUB-DIVISION OF PLOT**
Sub-division & clubbing of the plots shall not be permitted any circumstances.
- BUILDING SETBACK**
Building other than boundary wall and gates shall be constructed only within the portion of the site marked as residential buildable zone in clause number 1 above. The cantilever projections as allowed in Haryana Building Code, 2017 shall not project beyond the portion marked as residential buildable zone in the rear side.
- STILT PARKING**
Stilt parking is allowed in all sizes plots. The clear height of the stilt shall be 2.40 metres from the plinth level and below the bottom of the beam. The Stilt will not be permissible for any purpose other than parking.
- PARKING**
 - Parking shall be provided as per the provisions of Haryana Building Code - 2017, as amended from time to time.
 - In no circumstance, the vehicle(s) belonging to the plot shall be parked outside the plot area.
- PLINTH LEVEL**
The plinth height of building shall be as per Code No. 7.3 of the Haryana Building Code, 2017.
- BASEMENT**
Single level basements within the building zone of the site shall be provided as per Code 6.3(3)(i)(a) and shall be constructed, used and maintained as per Code 7.16 of the Haryana Building Code, 2017.
- RESTRICTION OF ACCESS FROM 45 MTS. WIDE OR MORE SECTOR ROADS AND PUBLIC OPEN SPACES**
In the case of plots which abut on the 45 meters or more wide sector roads and plots which abut on public open spaces, no direct access whatsoever secondary or main shall be allowed into the plots from such roads and open spaces.
- BOUNDARY WALL**
 - The boundary wall shall be constructed as per Code 7.5
 - The boundary walls in front courtyard which abut on a road or an open space shall be constructed according to standard design as approved by the DTCP. The boundary wall in the rear courtyard shall not be more than 1.80 meters in height.
 - In case of corner plots, boundary walls shall be rounded off at such corner by a radius as given below:-
 - 0.5 meters Radius for plots opening on to open space.
 - 1.0 meters Radius for plots upto 125 sq. meters.
 - 1.50 meters Radius for plots above 125 sq. meters to 150 sq. meters.
 - The owner/applicant if desires, is permitted to not construct boundary wall in front of plot, so that the said area can be utilized for parking.
- GATE AND GATE POST**
 - Gate and gate post shall be constructed as per approved standard design, at the position indicated on the zoning plan.
 - An additional wicket gate of standard design not exceeding 1.15 meter width may be allowed in the front and side boundary wall provided further that no gate shall be allowed in the rear boundary wall or towards the sector road and public open space.
- DISPLAY OF POSTAL NUMBER OF THE PLOT**
The premises number and postal address shall be written at the space shown for this purpose on the standard design of the gate as per approved design.
- GARBAGE COLLECTION POINT**
Every plot holder shall make adequate provision for garbage collection in his own plot and make suitable arrangement for disposal at the towable collection point to be provided by the colonizer.
- ACCESS**
No plot or public building will derive an access from less than 9.00 meters wide road.
- GENERAL**
 - That the coloniser/owner shall use only Light-Emitting Diode lamps (LED) fitting for internal lighting as well as Campus lighting.
 - That the coloniser/owner shall strictly comply with the directions issued vide Notification No. 19/6/2016-5P dated 31.03.2016 issued by Haryana Government Renewable Energy Department, if applicable.
 - That the coloniser/owner shall ensure the installation of Solar Photovoltaic Power Plant as per the provisions of order No. 22/52/2005-5Power dated 21.03.2016 issued by Haryana Government Renewable Energy Department, if applicable.
 - Rain water harvesting shall be provided as per HBC-2017, if applicable.
 - Fire safety protection measures shall be regulated by Haryana fire service Act, 2009, as amended from time to time.

DRG. NO. DTCP 10428 DATED 12-08-24

(GURPREET KHEPAR) AD (HQ) (NEHA YADAV) ATP(HQ) (S. K. SEHWAT) DTP (HQ) (HITESH SHARMA) STP (HQ) (JITENDER SHAG) CTP (HR) (AMIT KHATRI, IAS) DTCP (HR)