

REVISIONED LAYOUT PLAN FOR ADDITIONAL AREA

Checked subject to Comments
In forwarding letter No 127756
Dated 06.06.2023 and notes
attached with the estimate.

LEGEND:-	
MANHOLE	○ M.H.
WATER LINE EXTERNAL	200 mm D.S.W PIPE
GROUND LEVEL	G.L.
INVEST LEVEL	I.L.
CONNECTION LEVEL	C.L.

IMPORTANT NOTES

This drawing shall be coordinated with Architectural and Landscape Drawings.
The feasibility of making connection of sewerage and storm drain line at outfall shall be ascertained before starting the work.

PIPE SCHEDULE

PIPE NO.	SIZE	MATERIAL	SLOPE
A	200 DIA	STONEWARE PIPE	1:100
B	250 DIA	STONEWARE PIPE	1:200
C	300 DIA	STONEWARE PIPE	1:333
D	350 DIA	STONEWARE PIPE	1:400

NOTES:-

- ALL PIPE DIAMETERS ARE IN MM.
- ALL WORKS ARE TO BE CARRIED OUT AS PER SPECIFICATIONS.
- GROUND LEVELS AS PER MENTIONED ARE TENTATIVE. THESE SHALL MATCH WITH FORMATION LEVELS AS GIVEN BY ARCHITECTS.
- FIGURE SHOWN THUS [DISTANCE] ARE DISTANCES BETWEEN MANHOLES WHICH ARE APPROXIMATE AND INDICATIVE AND SHALL BE ADJUSTED AS PER ACTUAL SITE CONDITION.
- MANHOLES SHALL BE CONSTRUCTED AS PER STANDARD DETAILS.

To be read with Licence No. 66 of 2023 Dated 22-03-2023

This layout plan for an additional area measuring 1.673 acres in Residential Affordable Plotted Colony under DDJAY measuring 20.589 acres (Licence No. 08 of 2021 dated 05.03.2021), thereby making total site area 22.262 acres (Drawing No. 9088 Dated 24-3-23) comprised of licence which is issued in respect of Residential Plotted Colony Under DDA Jan Awas Yojana being developed by Sh. Manoj Mehlawat in collaboration with Signature Global Developers Pvt. Ltd., Sector-37-D, Gurugram is hereby approved subject to the following conditions:-

- That this Layout Plan shall be read in conjunction with the clauses appearing on the agreement executed under Rule 11 and the bilateral agreement.
- That the plotted area of the colony shall not exceed 65% of the net planned area of the colony. The entire area reserved for commercial purposes shall be taken as per calculation of the area under plots.
- That the demarcation plan at par site of all the Residential Plots and Commercial site shall be got approved from this Department and construction on these sites shall be governed by the Haryana Building Code, 2017 and the Zoning Plan approved by the Director, Town & Country Planning, Haryana.
- That for proper planning and integration of services in the area adjacent to the colony, the colonizer shall abide by the directions of the DTCP for the modification of layout and keep free for circulation/movement as shown in the layout plan.
- That the revenue rates falling in the colony shall be kept free for circulation/movement.
- That the colonizer shall abide by the directions of the DTCP, Haryana and accordingly shall make necessary changes in the layout plan for making any adjustment in the alignment of the peripheral roads, internal road circulation or for proper integration of the planning proposals of the adjoining areas.
- That no property/plot shall derive access directly from the carriage way of 30 metres or wider sector road if applicable.
- All green belts provided in the layout plan within the licensed area of the colony shall be developed by the colonizer. All other green belts outside the licensed area shall be developed by the Haryana Urban Development Authority/colonizer on the directions of the Director, Town & Country planning, Haryana or in accordance with terms and conditions of the agreements of the licence.
- At the time of demarcation plan, if required percentage of organized open space is reduced, the same will be provided by the colonizer in the licensed area.
- No plot will derive an access from less than 9 metres wide road would mean a minimum clear width of 9 metres between the plots.
- Any excess area over and above the permissible 4% under commercial use shall be deemed to be open space.
- The portion of the sector/development plan roads /green belts as provided in the Development Plan if applicable, which form part of the licensed area shall be transferred free of cost to the government on the lines of Section 3(3)(a)(ii) of the Act No. 8 of 1973.
- That the odd use plots are being approved subject to the conditions that these plots should not have a frontage of less than 75% of the standard frontage when demarcated.
- That you will have no objection to the regularization of the boundaries of the licence through give and take with the land that HSVP is finally able to acquire in the interest of planned development and integration of services. The decision of the competent authority shall be binding in this regard.
- That the rain water harvesting system shall be provided as per Central Ground Water Authority norms/Haryana Govt. notification as applicable.
- That the colonizer/owner shall use only Light-Emitting Diode lamps (LED) fitting for internal lighting as well as Campus lighting.
- That the colonizer/owner shall ensure the installation of Solar Photovoltaic Power Plant as per the provisions of order No.22/52/2005-Spower dated 21.03.2016 issued by Haryana Government Renewable Energy Department.
- That the colonizer shall strictly comply with the directions issued vide Notification No. 19/6/2016-SI dated 31.03.2016 issued by Haryana Government Renewable Energy Department for enforcement of the Energy Conservation Building Codes.

(NARENDER KUMAR)
(Hitesh Sharma)
(Tender Sihag)
(F.L. Satyaprakash, IAS)
(D.G. TCP(HR))

(PANKAJ BENIWAL)
(Dinesh Kumar)
(PA(HQ))

VEGETABLE/MILK BOOTH	MTS.	MTS.	SQ.MTS.
	6.02	4.36	26.25
TOTAL			26.25

GREEN AREA CALCULATION	
SQ.M.	ACRES
G1	1128.780
G2	1474.330
G3	1107.010
G4	312.210
G5	376.810
G6	325.770
G7	299.180
G8	613.250
G9	225.850
G10	1112.180
TOTAL	6975.370
	1.724

SITE-37D+EXTENSION (22.262 ACRE)	PERMISSIBLE		PROPOSED			
	AREA	AREA	PERCENTAGE	AREA	AREA	
ACRES	SQ.MTS.	%	ACRES	SQ.MTS.	%	
TOTAL Licence Area	22.26200	90090.975				
Open Area under GREEN/PARK	1.670	6756.823	7.50	1.724	6975.370	7.74
Community Facilities	2.226	9009.097	10.00	2.227	9013.610	10.01
Commercial Area (calculated on total licenced area)	0.890	3603.539	4.00	0.890	3603.510	4.00
Area Under Plots (calculated on total licenced area)	13.580	54955.495	61.00	10.997	44503.970	49.40
Total permissible Residential + Commercial area	14.470	58559.134	65.00	11.888	48107.480	53.40
Permissible Density	240-400 ppa		Minimum Required Plots	296.83		
Achieved Density @ 18 persons per plot	287.04	ppa	Achieved Plots	355.000	(@18 Persons/Plot)	

CLASSIFICATION OF PLOTS				
TYPE	SIZE OF PLOT		AREA OF PLOT	NO. OF PLOTS
	MTS.	MTS.	SQ.MTS.	SQ.MTS.
A	7.50	19.99	149.93	60
B	6.70	20.00	134.00	175
C	6.70	15.00	100.50	104
M	IRREGULAR SIZE		16	1606.47
	TOTAL		355	44503.97

LEGEND
ALREADY LICENSED BOUNDARY (20.589 acres) (LIC. NO. - 08 OF 2021 DATED 05.03.2021)
Additional Land applied for license(1.673 acres)
COMMERCIAL
COMMUNITY FACILITY
SERVICES
TDR 40 (In principle approval through memo no. :- TDRA-40A/CTP/2108/2023 dated 23.01.2023)
GREEN
REVENUE RASTA

PROJECT NAME AND ADDRESS:
REVISED LAYOUT PLAN OF PROPOSED RESIDENTIAL PLOTTED COLONY UNDER DDJAY, IN SECTOR-37D, GURGAON, OVER AN AREA OF 22.262 ACRES BEING DEVELOPED BY SIGNATURE GLOBAL DEVELOPERS PVT. LTD.

OWNER'S NAME:
M/S SIGNATURE GLOBAL DEVELOPERS PVT. LTD.

OWNER'S NAME:
SITE LAYOUT PLAN -SEWERAGE LAYOUT

For Service Plan Estimate Only

Executive Engineer HSV/Div. No. 41,
Gurugram

R.D. Thakral
Superintendent Engineer
HSV/Circle, Gurugram
AR. AMAN THAKRAL
CA/2016/79767
AMBIN DESIGNS
(M) +91-934327061






Checked subject to Comments
In forwarding letter No. 127754
Dated 06.02.2023 and notes
attached with the estimate

LEGEND	
FRESH WATER SUPPLY LINE	
D.3 PIPE	D.2 PIPE
D.2 PIPE	D.2 PIPE
TUBEWELL	TW

Superintending Engineer (HQ)
for Chief Engineer-4
HSVP, Gurgaon
[Signature]

[Signature]</i



Checked subject to Comments
in forwarding letter No. 127156
Dt 05-06-2023 and notes
attached with the estimate

Superintendent Engineer (HO)
for Chief Engineer-I
C.P. Panigrahi
Sob. no-2

Director
Town & Country Planning
Gurgaon, Chandigarh

To be read with Licence No. 60 of 2023 Dated 22-03-2023
That this Layout plan for an additional area measuring 1.673 acres in Residential Affordable Plotted Colony under DDJAY measuring 20.5890 acres (Licence No. 08 of 2021 dated 05.03.2021), thereby making total site area 22.262 acres (Drawing No. 9096 Dated 24-3-2023) comprised of licence which is issued in respect of Affordable Residential Plotted Colony (Under Deen Dayal Jan Awas Yojna) being developed by Sh. Nandu Mehta in collaboration with Signature Global Developers Pvt. Ltd., Sector-37-D, Gurugram is hereby approved subject to the following conditions:-

1. That this Layout Plan shall be read in conjunction with the clauses appearing on the agreement executed under Rule 11 and the bilateral agreement.
2. That the plotted area of the colony shall not exceed 65% of the net planned area of the colony. The entire area reserved for commercial purposes shall be taken as plotted for calculation of the area under plots.
3. That the demarcation plans as per site of all the Residential Plots and Commercial site shall be got approved from this Department and construction on these sites shall be governed by the Haryana Building Code, 2017 and the Zoning Plan approved by the Director, Town & Country Planning, Haryana.
4. That for proper planning and integration of services in the area adjacent to the colony, the colonizer shall abide by the directions of the DTCP for the modification of layout plans of the colony.
5. That the revenue rates failing in the colony shall be kept free for circulation/movement as shown in the layout plan.
6. That the colonizer shall abide by the directions of the DTCP, Haryana and accordingly shall make necessary changes in the layout plan for making any adjustment in the alignment of the peripheral roads, internal road circulation or for proper integration of the planning proposals of the adjoining areas.
7. That no property/plot shall derive access directly from the carriage way of 30 metres or wider sector road if applicable.
8. All green belts provided in the layout plan within the licenced areas of the colony shall be developed by the colonizer. All other green belts outside the licenced area shall be developed by the Haryana Urban Development Authority/colonizer on the directions of the Director, Town & Country planning, Haryana or in accordance with terms and conditions of the agreements of the licence.
9. At the time of demarcation, if required percentage of organized open space is reduced, the same will be provided by the colonizer in the licenced area.
10. No plot will derive an access from less than 9 metres wide road would mean a minimum clear width of 9 metres between the plots.
11. Any excess area over and above the permissible 4% under commercial use shall be deemed to be open space.
12. The portion of the sector/development plan road/green belts as provided in the Development Plan if applicable, which form part of the licensed area shall be transferred free of cost to the government on the lines of Section 3(3)(a)(iii) of the Act No. 5 of 1975.
13. That the odd size plots are being approved subject to the conditions that these plots should not have a frontage of less than 75% of the standard frontage when demarcated.
14. That you will have no objection to the regularization of the boundaries of the licence through give and take with the concerned authority shall be binding in this regard.
15. That the rain water harvesting system shall be provided as per Central Ground Water Authority norms/Haryana Govt. notification as applicable.
16. That the colonizer/owner shall use only Light-Emitting Diode lamps (LED) fitting for internal lighting as well as Campus lighting.
17. That the colonizer/owner shall ensure the installation of Solar Photovoltaic Power Plant as per the provisions of order Ilo 22/52 (2005)Power dated 21.03.2016 issued by Haryana Government Renewable Energy Department.
18. That the colonizer/owner shall strictly comply with the directions issued vide Notification No. 19/6/2016-SP dated 31.03.2016 issued by Haryana Government Renewable Energy Department for enforcement of the Energy Conservation Building Codes.

(Signature)
(NARENDER KUMAR)
DTP(HQ)
(Signature)
(Hitesh Sharma)
(TENDER SHAG) T.L. SATYAPRAKASH, IAS
STP(MHQ)
CXP (IT&M)
DG, JFCP(I&R)
(Signature)
(PANAJI BENIWAL)
ATP(HQ)
(Signature)
(DINESH KUMAR)
PA(HQ)

LEGEND

	ALREADY LICENSED BOUNDARY (20.589acres) (LIC. NO. - 08 OF 2021 DATED 05.03.2021)
	Additional Land applied for license(1.673 acres)
	COMMERCIAL
	COMMUNITY FACILITY
	SERVICES
	TDR 40 (In principle approval through memo no. :- TDRA-40A/CTP/2108/2023 dated 23.01.2023)
	GREEN
	REVENUE RASTA

SITE-37D+EXTENSION (22.262 ACRE)	PERMISSIBLE		PROPOSED		
	AREA ACRES	AREA SQ.MTS.	PERCENTAGE %	AREA ACRES	AREA SQ.MTS.
				%	%
TOTAL Liscence Area	22.26200	90090.975			
Open Area under GREEN/PARK	1.670	6756.823	7.50	1.724	6975.370
Community Facilities	2.226	9009.097	10.00	2.227	9013.610
Commercial Area (calculated on total licenced area)	0.890	3603.639	4.00	0.890	3603.510
Area Under Plots (calculated on total licenced area)	13.580	54955.495	61.00	10.997	44503.970
Total permissible Residential + Commercial area	14.470	58559.134	65.00	11.888	48107.480
Permissible Density	240-400 ppa		Minimum Required Plots	296.83	
Achieved Density @ 18 persons per plot	287.04	ppa	Achieved Plots	355.000	(@18 Persons/Plot)

TYPE	SIZE OF PLOT		AREA OF PLOT MTS.	NO. OF PLOTS	TOTAL AREA OF PLOTS SQ.MTS.
	MTS.	MTS.			
A	7.50	19.99	149.93	60	8995.50
B	6.70	20.00	134.00	175	23450.00
C	6.70	15.00	100.50	104	10452.00
M	IRREGULAR SIZE			16	1606.47
	TOTAL			355	44503.97

PROJECT NAME AND ADDRESS:	REVISED LAYOUT PLAN OF PROPOSED RESIDENTIAL PLOTTED COLONY UNDER DDJAY, IN SECTOR-37D, GURGAON, OVER AN AREA OF 22.262 ACRES BEING DEVELOPED BY SIGNATURE GLOBAL DEVELOPERS PVT. LTD	
OWNER'S NAME:	M/S SIGNATURE GLOBAL DEVELOPERS PVT. LTD	
OWNER'S NAME:	SITE LAYOUT PLAN - ROAD LEVEL LAYOUT For Service Plan Estimate Only.	
OWNER'S SIGNATURE:	<i>(Signature)</i>	
Executive Engineer HSVP Divn. No. M, Gurugram 31		
* SIGNATURE GLOBAL DEVELOPERS PVT. LTD		
Supervising Engineer HSVP Circle, Gurugram		
NORTH		
W. S. E. N.		
AR. AMAN THAKUR CA/2016/7976/ AMBIN DESIGNS (M) +91-9034327061		

