

DOOR WINDOW SCHEDULE (Basement Doors)					
S.NO	Door Tag	Rough Opening (WxH)	Sill	Lintel	Fire Rating
1	BFD1	1800	0	2400	2hrs
2	BFD2	1700	0	2400	2hrs
3	BFD3	1500	0	2400	2hrs
4	BFD4	1000	0	2400	2hrs
5	BFD5	1250	0	2400	2hrs
6	BFD6	2000	0	2400	2hrs
7	BFD7	1250	0	2400	2hrs
8	BFD8	2500	0	2400	2hrs
9	BFD9	1000	0	2400	4hrs
10	BFD10	2000	0	2400	2hrs
11	BFD11	1000	0	2400	2hrs
12	BFD12	3000	0	3000	2hrs
13	BFD13	1500	0	3000	4hrs
14	BFD14	4200	0	3000	4hrs



GROSS-A					
NO.	A	B	C	D	E
1	88.230	151.320	123.375	171.4025	1714479.450
2	151.320	123.375	65.920	171.4025	1476880.242
3	34.640	16.335	47.535	171.4025	40760.304
4	34.640	33.580	8.650	171.4025	20662.229
TOTAL					8332.835 SQM

GROSS-B					
NO.	A	B	C	D	E
1	3.14	15.810	15.810	62	15.810
TOTAL					24.624 SQM

GROSS-C					
NO.	A	B	C	D	E
1	3.14	15.810	15.810	62	15.810
TOTAL					24.624 SQM

GROSS-D					
NO.	A	B	C	D	E
1	8.088	24.305	24.695	171.4025	97.670
2	24.305	24.695	5.440	171.4025	66.105
3	24.695	5.440	18.335	171.4025	197.843
4	27.220	1.295	1.560	171.4025	0.587
5	32.720	32.180	33.770	171.4025	35.977
6	33.770	35.977	18.575	171.4025	312.943
7	2.240	19.865	19.250	171.4025	20.778
8	19.250	38.610	30.070	171.4025	279.623
9	19.750	27.490	30.070	171.4025	284.721
10	4.055	17.785	17.300	171.4025	35.076
TOTAL					1011.727 SQM

GROSS-E					
NO.	A	B	C	D	E
1	1.000	1.000	1.000	1.000	1.000
2	1.000	1.000	1.000	1.000	1.000
3	1.000	1.000	1.000	1.000	1.000
4	1.000	1.000	1.000	1.000	1.000
5	1.000	1.000	1.000	1.000	1.000
6	1.000	1.000	1.000	1.000	1.000
7	1.000	1.000	1.000	1.000	1.000
8	1.000	1.000	1.000	1.000	1.000
9	1.000	1.000	1.000	1.000	1.000
10	1.000	1.000	1.000	1.000	1.000
TOTAL					10.000 SQM

NOTES:-
 1. AIR CONDITIONING SYSTEM IS BEING PROVIDED.
 2. DG POWER BACKUP IS BEING PROVIDED.
 3. TOILETS ARE MECHANICALLY VENTILATED.
 4. ALL LIFTS SHALL HAVE POWER BACK-UP.
 5. ALL ELECTRICAL INSTALLATION SHALL BE AS PER PROVISION OF RELEVANT CODE.
 6. FIRE/FIGHTING/SAFETY PROVISIONS SHALL BE AS PER RELEVANT CODE PROVISIONS.
 7. BASEMENT AREA SHALL HAVE MECHANICALLY VENTILATED AS PER RELEVANT CODE.
 8. ALL TOILETS ARE VENTILATED AS PER HARYANA BUILDING CODE 2017.
 9. BUILDINGS HAS AUTOMATIC SPRINKLER SYSTEM WHEREVER REQUIRED BY RELEVANT CODE.
 10. BUILDING WILL BE DESIGNED/STRUCTURES AS PER RELEVANT U.S.CODES FOR EARTHQUAKE RESISTANCE.
 11. SOLAR PANELS OF REQUIRED CAPACITY SHALL BE PROVIDED AS PER HARYANA DAYZONING NORMS.
 12. ALL HANDICAP RAMPS WITH RAILING.
 13. ALL FIRE FIGHTING INSTALLATIONS SHALL BE AS PER PROVISION OF RELEVANT CODE.
 14. THE RAINWATER HARVESTING SYSTEM SHALL BE PROVIDED AS PER CENTRAL GROUND WATER AUTHORITY NORMS.

BUILDING PLAN OF G.H. SITE NO.1
 IN SECTOR-42 GURUGRAM
 OWNER
 M/s. Experion Developers Pvt. Ltd.
 (Formerly M/s. Gold Developers Pvt. Ltd.)
 8th Floor, Milestone Experion Centre, Sector 15(Part-2),
 Gurgaon, Haryana-122001

ARCHITECTS
 Arco Associates Pvt. Ltd.
 Plot 36B, Sector-32, Gurgaon 122001
 Ph. 2624-2050, 2624-2169

ASSOCIATE ARCHITECTS-Submission Drawings
 CosMAN, 11th Floor, Tower-2, DLF Corporate Greens
 Sector-74A, Gurgaon 122004

OWNER'S SEAL
 & SIGNATURE
 DTP (H) Member Secretary
 BPAAC
 Suraj J.D.
 Chairman
 BPAAC

ARCHITECT'S SEAL
 & SIGNATURE
 SANCTIONED
 Vide Memo No.3.1113, Dated 14/07/24
 Ar. Ravinder Kumar
 CA/2012/55971

AUGUST-2024 Scale: 1:200
 Drawing No:- BS-01
 Drawing Title:- Public Health (Sanitary) Service only subject to comments in the form of letter No. 2465710/124/24
 Superseding Engineer (H) DDX (T) MEMBER BPAAC
 HSPV, Panthukula