

STATE ENVIRONMENT IMPACT ASSESSMENT AUTHORITY HARYANA
Bay No. 55-58, Prayatan Bhawan, Sector-2, PANCHKULA.

No. SEIAA/HR/2013/1543

Dated: ...24-12-2013..

To

M/s Emaar MGF Land Ltd.
 Emaar MGF Business Park, MG Road,
 Sikanderpur Chowk, Sector-28,
 Gurgaon, Haryana-122002

**Subject: Environmental Clearance for proposed Group Housing Colony
 "Ekaantam" measuring 10.744 Acres, Village Bajghera, Sector-112,
 Gurgaon, Haryana.**

Dear Sir,

This letter is in reference to your application no. Emaar MGF/SEC/EC/739 dated 22-03-2013 addressed to M.S. SEIAA, Haryana received on 22-03-2013 and subsequent letters dated 16-04-2013 and 21-06-2013 seeking prior Environmental Clearance for the above project under the EIA Notification, 2006. The proposal has been appraised as per prescribed procedure in the light of provisions under the EIA Notification, 2006 on the basis of the mandatory documents enclosed with the application viz., Form-1, Form1-A, Conceptual Plan and additional clarifications furnished in response to the observations of the State Expert Appraisal Committee (SEAC) constituted by MOEF, GOI vide their Notification 23.3.2012, in its meetings held on 06-06-2013 and 23-07-2013 awarded "Gold" grading to the project.

[2] It is inter-alia, noted that the project involves the construction of Group Housing project at Village Bajghera, Sector-112, Gurgaon, Haryana on a total plot area of 10.744 Acres. The total built up area shall be 104134.02 sqmt. The Group Housing Colony shall have 11 no. of towers having 2 basements + GF + stilt + maximum 22 floors. The maximum height of the building shall be 75.15 meters. The group housing project will have EWS tower G+5, 2 no. of community building, shopping and MLCP, G+3. The total water requirement shall be 316.21 KLD. The fresh water requirement shall be 162.27 KLD. The waste water generation will be 171.05 KLD, which will be treated in the STP of 205 KLD capacity. The total power requirement shall be 3058.86 KW which will be supplied by DHBVN. The Project Proponent has proposed to develop green belt on 40% of project area (21% tree plantation + 19% landscaping). The Project Proponent proposed to construct 10 rain water harvesting pits. The solid waste generation will be 1300 kg/day. The bio-degradable waste will be treated in the project area by adopting appropriate technology. The total parking spaces proposed are 800 ECS.

[3] The State Expert Appraisal Committee, Haryana after due consideration of the relevant documents submitted by the project proponent and additional clarification

furnished in response to its observations, have recommended the grant of environmental clearance for the project mentioned above, subject to compliance with the stipulated conditions. Accordingly, the State Environment Impact Assessment Authority in its meeting held on 19-12-2013 decided to agree with the recommendations of SEAC to accord necessary environmental clearance for the project under Category 8(a) of EIA Notification 2006 subject to the strict compliance with the specific and general conditions mentioned below:-

PART A-

SPECIFIC CONDITIONS:-

Construction Phase:-

- [1] "Consent for Establish" shall be obtained from Haryana State Pollution Control Board under Air and Water Act and a copy shall be submitted to the SEIAA, Haryana before the start of any construction work at site.
- [2] A first aid room as proposed in the project report shall be provided both during construction and operational phase of the project.
- [3] Adequate drinking water and sanitary facilities shall be provided for construction workers at the site. Provision should be made for mobile toilets. Open defecation by the labourers is strictly prohibited. The safe disposal of waste water and solid wastes generated during the construction phase should be ensured.
- [4] All the topsoil excavated during construction activities shall be stored for use in horticulture/landscape development within the project site.
- [5] The project proponent shall ensure that the building material required during construction phase is properly stored within the project area and disposal of construction waste should not create any adverse effect on the neighboring communities and should be disposed of after taking necessary precautions for general safety and health aspects of people, only in approved sites with the approval of competent authority.
- [6] Construction spoils, including bituminous material and other hazardous materials, must not be allowed to contaminate watercourses and the dump sites for such material must be secured so that they should not leach into the ground water and any hazardous waste generated during construction phase, should be disposed off as per applicable rules and norms with necessary approval of the Haryana State Pollution Control Board.
- [7] The diesel generator sets to be used during construction phase shall be of ultra low sulphur diesel type and should conform to Environment (Protection) Rules prescribed for air and noise emission standards.
- [8] The diesel required for operating DG sets shall be stored in underground tanks and if required, clearance from Chief Controller of Explosives shall be taken.

- [9] Ambient noise levels shall conform to the residential standards both during day and night. Incremental pollution loads on the ambient air and noise quality should be closely monitored during construction phase. Adequate measures should be taken to reduce ambient air and noise level during construction phase, so as to conform to the stipulated residential standards of CPCB/MoEF.
- [10] Fly ash shall be used as building material in the construction as per the provisions of Fly Ash Notification of September 1999 and as amended on 27th August 2003.
- [11] Storm water control and its re-use as per CGWB and BIS standards for various applications should be ensured.
- [12] Water demand during construction shall be reduced by use of pre-mixed concrete, curing agents and other best practices.
- [13] In view of the severe constraints in water supply augmentation in the region and sustainability of water resources, the developer will submit the NOC from CGWA specifying water extraction quantities and assurance from HUDA/ utility provider indicating source of water supply and quantity of water with details of intended use of water – potable and non-potable. Assurance is required for both construction and operation stages separately. It shall be submitted to the SEIAA and RO, MOEF, Chandigarh before the start of construction.
- [14] Roof must meet prescriptive requirement as per Energy Conservation Building Code by using appropriate thermal insulation material.
- [15] Opaque wall must meet prescriptive requirement as per Energy Conservation Building Code which is proposed to be mandatory for all air conditioned spaces while it is desirable for non-air-conditioned spaces by use of appropriate thermal insulation material to fulfill requirement.
- [16] The approval of the competent authority shall be obtained for structural safety of the building on account of earthquake, adequacy of fire fighting equipments, etc. as per National Building Code including protection measures from lightening etc. If any forest land is involved in the proposed site, clearance under Forest Conservation Act shall be obtained from the competent Authority.
- [17] Overexploited groundwater and impending severe shortage of water supply in the region requires the developer to redraw the water and energy conservation plan. Developer shall reduce the overall footprint of the proposed development. Project proponent shall incorporate water efficiency /savings measures as well as water reuse/recycling within 3 months and before start of construction to the SEIAA, Haryana and RO, MOEF, GOI, Chandigarh.
- [18] The Project Proponent as stated in the proposal shall construct 10 rain water harvesting pits for recharging the ground water within the project premises. Rain water harvesting pits shall be designed to make provisions for silting chamber and

removal of floating matter before entering harvesting pit. Maintenance budget and persons responsible for maintenance must be provided. Care shall also be taken that contaminated water do not enter any RWH pit.

- [19] The project proponent shall provide for adequate fire safety measures and equipments as required by Haryana Fire Service Act, 2009 and instructions issued by the local Authority/Directorate of fire from time to time. Further the project proponent shall take necessary permission regarding fire safety scheme/NOC from competent Authority as required.
- [20] The Project Proponent shall obtain assurance from the DHBVN for supply of 3058.86 KW of power supply before the start of construction. In no case project will be operational solely on generators without any power supply from any external power utility.
- [21] Detail calculation of power load and ultimate power load of the project shall be submitted to DHBVN under intimation to SEIAA Haryana before the start of construction. Provisions shall be made for electrical infrastructure in the project area.
- [22] The Project Proponent shall not raise any construction in the natural land depression / Nallah/water course and shall ensure that the natural flow from the Nallah/water course is not obstructed.
- [23] The Project Proponent shall keep the plinth level of the building blocks sufficiently above the level of the approach road to the Project. Levels of the other areas in the Projects shall also be kept suitably so as to avoid flooding.
- [24] Construction shall be carried out so that density of population does not exceed norms approved by Director General Town and Country Department Haryana.
- [25] The Project Proponent shall submit an affidavit with the declaration that ground water will not be used for construction and only treated water should be used for construction.
- [26] The project proponent shall not cut any existing tree and project landscaping plan should be modified to include those trees in green area.
- [27] The project proponent shall provide 3 meter high barricade around the project area, dust screen for every floor above the ground, proper sprinkling and covering of stored material to restrict dust and air pollution during construction.
- [28] The project proponent shall construct a sedimentation basin in the lower level of the project site to trap pollutant and other wastes during rains.
- [29] The project proponent shall provide proper rasta of proper width and proper strength for the project before the start of construction.

- [30] The project proponent shall ensure that the U-value of the glass is less than 3.177 and maximum solar heat gain co-efficient is 0.25 for vertical fenestration.
- [31] The project proponent shall adequately control construction dusts like silica dust, non-silica dust, wood dust. Such dusts shall not spread outside project premises. Project Proponent shall provide respiratory protective equipment to all construction workers.
- [32] The project proponent shall develop complete civic infrastructure of the Group Housing colony including internal roads, green belt development, sewerage line, Rain Water recharge arrangements, Storm water drainage system, Solid waste management site and provision for treatment of bio-degradable waste, STP, water supply line, dual plumbing line, electric supply lines etc. and shall offer possession of the units/flats thereafter.
- [33] The project proponent shall provide one refuse area till 24 meter, one till 39 meter and one each after 15 meter as per National Building Code.
- [34] The project proponent shall provide fire control room and fire officer for building above 30 meter as per National Building Code.
- [35] The project proponent shall obtain permission of Mines and Geology Department for excavation of soil before the start of construction.
- [36] The project proponent shall seek specific prior approval from concerned local Authority/HUDA regarding provision of storm drainage and sewerage system including their integration with external services of HUDA/ Local authorities beside other required services before taking up any construction activity.
- [37] The site for solid waste management plant be earmarked on the layout plan and the detailed project for setting up the solid waste management plant shall be submitted to the Authority within one month.
- [38] The project proponent shall submit the copy of fire safety plan duly approved by Fire Department before the start of construction.
- [39] The project proponent shall discharge excess of treated waste water/storm water in the public drainage system and shall seek permission of HUDA before the start of construction.
- [40] The project proponent shall maintain the distance between STP and water supply line.
- [41] The project proponent shall ensure that no construction activity is undertaken either on surface or below or above surface of revenue rasta passing through the project area.
- [42] The project proponent shall indicate the width and length of revenue rasta passing through the project area on sign board and shall display the same at both the ends of revenue rasta stretch, for awareness of public. Sign board shall also display the

message that this is public rasta/road and any citizen can use it. There shall not be any gate with or without guards on revenue rasta.

- [43] The project proponent shall ensure that natural flow of existing nallah is never obstructed and shall seek NOC from HUDA/Irrigation/Relevant authority regarding this before the start of the construction.
- [44] The project proponent shall ensure that in case of excessive flow of water in, nallah, the structural integrity of buildings along-side the nallah is not breached in any circumstances.
- [45] The project proponent shall ensure that there should not be any water logging on the bed of nallah even in case of excessive rain.
- [46] The project proponent shall ensure that sewerage pipe line should not cross over the nallah and project proponent shall maintain separate STP in the plot area across the nallah.
- [47] The project proponent shall ensure that sewerage line shall be planned by taking into account the natural slope and gravity of original land.
- [48] The project proponent shall ensure that bed of nallah is not encroached in any manner, while constructing the culvert over the nallah.
- [49] The project proponent shall ensure plinth level of the building block is 1.5 meter above 100 years flood level.
- [50] The project proponent shall provide pervious surface instead of impervious and hard surface in order to reduce flow of water in nallah.
- [51] The project proponent shall provide helipad facility as required under NBC norms and shall seek permission of helipad from AAI accordingly /relevant authority.
- [52] The project proponent shall obtain NOC from HUDA as well as Irrigation Department before the start of construction, regarding possible adverse effect of project proposal on the said Najafgarh Jheel.
- [53] All system of water supply, sewerage system, STP etc. shall be provided based on revised requirement of @135lpcd.
- [54] The project proponent shall ensure that the stack height is 6 meter more than the highest tower.

Operational Phase:

- [a] "Consent to Operate" shall be obtained from Haryana State Pollution Control Board under Air and Water Act and a copy shall be submitted to the SEIAA, Haryana.
- [b] The Sewage Treatment Plant (STP) shall be installed for the treatment of the sewage to the prescribed standards including odour and treated effluent shall be recycled. The installation of STP shall be certified by an independent expert and a report in this regard shall be submitted to the SEIAA, Haryana before the

project is commissioned for operation. Tertiary treatment of waste water is mandatory. Discharge of treated sewage shall conform to the norms and standards of HSPCB, Panchkula. Project Proponent shall implement such STP technology which does not require filter backwash.

- [c] Separation of the grey and black water should be done by the use of dual plumbing line. Treatment of 100% grey water by decentralized treatment should be done ensuring that the re-circulated water should have BOD level less than 10 mg/litre and the recycled water will be used for flushing, gardening and DG set cooling etc. to achieve zero exit discharge.
- [d] For disinfection of the treated wastewater ultra-violet radiation or ozonization process should be used.
- [e] Diesel power generating sets proposed as source of back-up power for lifts, common area illumination and for domestic use should be of enclosed type and conform to rules made under the Environment (Protection) Act, 1986. The location of the DG sets shall be in the basement as promised by the project proponent with appropriate stack height i.e. above the roof level as per the CPCB norms. The diesel used for DG sets shall be ultra low sulphur diesel (50ppm sulphur), instead of low sulphur diesel.
- [f] Ambient Noise level should be controlled to ensure that it does not exceed the prescribed standards both within and at the boundary of the Proposed Residential Complex.
- [g] The project proponent as stated in the proposal should maintain at least 40% as green cover area for tree plantation especially all around the periphery of the project and on the road sides preferably with local species which can provide protection against noise and suspended particulate matter. The open spaces inside the project shall be preferably landscaped and covered with vegetation/grass, herbs & shrubs. Only locally available plant species shall be used.
- [h] The project proponent shall strive to minimize water in irrigation of landscape by minimizing grass area, using native variety, xeriscaping and mulching, utilizing efficient irrigation system, scheduling irrigation only after checking evapo-transpiration data.
- [i] Rain water harvesting for roof run-off and surface run-off, as per plan submitted should be implemented. Before recharging the surface run off, pre-treatment through sedimentation tanks must be done to remove suspended matter, oil and grease. The bore well for rainwater recharging shall be kept at least 5 mts. above the highest ground water table. Care shall be taken that contaminated water do not enter any RWH pit. The project proponent shall avoid Rain Water Harvesting of first 10 minutes of rain fall. Roof top of the building shall be without any toxic

material or paint which can contaminate rain water. Wire mesh and filters should be used wherever required.

- [j] The ground water level and its quality should be monitored regularly in consultation with Central Ground Water Authority.
- [k] A report on the energy conservation measures conforming to energy conservation norms finalized by Bureau of Energy Efficiency should be prepared incorporating details about building materials & technology, R & U Factors etc and submitted to the SEIAA, Haryana in three months time.
- [l] Energy conservation measures like installation of LED only for lighting the areas outside the building and inside the building should be integral part of the project design and should be in place before project commissioning. Use of solar panels must be adapted to the maximum energy conservation.
- [m] The Project Proponent shall use zero ozone depleting potential material in insulation, refrigeration, air-conditioning and adhesive. Project Proponent shall also provide Halon free fire suppression system.
- [n] The solid waste generated should be properly collected and segregated as per the requirement of the MSW Rules, 2000 and as amended from time to time. The bio-degradable waste should be treated by appropriate technology at the site earmarked within the project area and dry/inert solid waste should be disposed off to the approved sites for land filling after recovering recyclable material.
- [o] The provision of the solar water heating system shall be as per norms specified by HAREDA and shall be made operational in each building block.
- [p] The traffic plan and the parking plan proposed by the Project Proponent should be adhered to meticulously with further scope of additional parking for future requirement. There should be no traffic congestion near the entry and exit points from the roads adjoining the proposed project site. Parking should be fully internalized and no public space should be used.
- [q] The Project shall be operationalized only when HUDA/local authority will provide domestic water supply system in the area.
- [r] Operation and maintenance of STP, solid waste management and electrical Infrastructure, pollution control measures shall be ensured even after the completion of project.
- [s] Different type of wastes should be disposed off as per provisions of municipal solid waste, biomedical waste, hazardous waste, e-waste, batteries & plastic rules made under Environment Protection Act, 1986. Particularly E-waste and Battery waste shall be disposed of as per existing E-waste Management Rules 2011 and Batteries Management Rules 2001. The project proponent should maintain a collection center

for E-waste and it shall be disposed of to only registered and authorized dismantler / recycler.

- [t] Standards for discharge of environmental pollutants as enshrined in various schedules of rule 3 of Environment Protection Rule 1986 shall be strictly complied with.
- [u] Water supply shall be metered among different users of utilities.
- [v] The project proponent shall ensure that the stack height of DG sets is more than the highest tower and also ensure that the emission standards of noise and air are within the CPCB prescribed limits. Noise and Emission level of DG sets greater than 800 KVA shall be as per CPCB latest standards for high capacity DG sets.
- [w] All electric supply exceeding 100 amp, 3 phase shall maintain the power factor between 0.98 lag to 1 at the point of connection.
- [x] The project proponent shall use only treated water instead of fresh water for DG cooling. The Project Proponent shall also use evaporative cooling technology and double stage cooling system for HVAC in order to reduce water consumption. Further temperature, relative humidity during summer and winter seasons should be kept at optimal level. Variable speed drive, best Co-efficient of Performance, as well as optimal integrated point load value and minimum outside fresh air supply may be resorted for conservation of power and water. Coil type cooling DG Sets shall be used for saving cooling water consumption for water cooled DG Sets.
- [y] The project proponent shall ensure that the transformer is constructed with high quality grain oriented, low loss silicon steel and virgin electrolyte grade copper. The project proponent shall obtain manufacturer's certificate also for that.
- [z] The project proponent shall ensure that exit velocity from the stack should be sufficiently high. Stack shall be designed in such a way that there is no stack down-wash under any meteorological conditions.
- [aa] The project proponent shall provide water sprinkling system in the project area to suppress the dust in addition to the already suggested mitigation measures in the Air Environment Chapter of EMP.
- [ab] The project proponent shall ensure proper Air Ventilation and light system in the basements area, for comfortable living of human being and shall ensure that number of Air Changes per hour/(ACH) in basement never falls below 15. In case of emergency capacity for increasing ACH to the extent of 30 must be provided by the project proponent.
- [ac] The project proponent shall get the inspection of nallah before the onset of monsoon season every year from Irrigation Department.
- [ad] The project proponent shall not discharge untreated water in the nallah and also shall not throw any solid waste in the nallah.

PART-B. GENERAL CONDITIONS:

- [i] The Project Proponent shall ensure the commitments made in Form-1, Form-1A, EIA/EMP and other documents submitted to the SEIAA for the protection of environment and proposed environmental safeguards are complied with in letter and spirit. In case of contradiction between two or more documents on any point, the most environmentally friendly commitment on the point shall be taken as commitment by project proponent.
- [ii] The project proponent shall also submit six monthly reports on the status of compliance of the stipulated EC conditions including results of monitored data (both in hard copies as well as by e-mail) to the northern Regional Office of MoEF, the respective Zonal Office of CPCB, HSPCB and SEIAA Haryana.
- [iii] STP outlet after stabilization and stack emission shall be monitored monthly. Other environmental parameters and green belt shall be monitored on quarterly basis. After every 3 (three) months, the project proponent shall conduct environmental audit and shall take corrective measure, if required, without delay.
- [iv] The SEIAA, Haryana reserves the right to add additional safeguard measures subsequently, if found necessary. Environmental Clearance granted will be revoked if it is found that false information has been given for getting approval of this project. SEIAA reserves the right to revoke the clearance if conditions stipulated are not implemented to the satisfaction of SEIAA/MoEF.
- [v] The Project proponent shall not violate any judicial orders/pronouncements issued by any Court/Tribunal.
- [vi] All other statutory clearances such as the approvals for storage of diesel from Chief Controller of Explosives, Fire Department, Civil Aviation Department, Forest Conservation Act, 1980 and Wildlife (Protection) Act, 1972, Forest Act, 1927, PLPA 1900, etc. shall be obtained, as applicable by project proponents from the respective authorities prior to construction of the project.
- [vii] The Project proponent should inform the public that the project has been accorded Environment Clearance by the SEIAA and copies of the clearance letter are available with the Haryana State Pollution Control Board & SEIAA. This should be advertised within 7 days from the date of issue of the clearance letter at least in two local newspapers that are widely circulated in the region and the copy of the same should be forwarded to SEIAA Haryana. A copy of Environment Clearance conditions shall also be put on project proponent's web site for public awareness.
- [viii] Under the provisions of Environment (Protection) Act, 1986, legal action shall be initiated against the Project Proponent if it was found that construction of the project has been started before obtaining prior Environmental Clearance.
- [ix] Any appeal against the this Environmental Clearance shall lie with the National Green Tribunal, if preferred, within a period of 30 days as prescribed under Section 16 of the National Green Tribunal Act, 2010.
- [x] The project proponent shall put in place Corporate Environment Policy as mentioned in MoEF, GoI OM No. J-11013/41/2006-IA II (I) dated 26.4.2012 within 3 months period. Latest Corporate Environment Policy should be submitted to SEIAA within 3 months of issuance of this letter.
- [xi] The fund ear-marked for environment protection measures should be kept in separate account and should not be diverted for other purposes and year wise expenditure shall be reported to the SEIAA/RO MOEF GOI under rules prescribed for Environment Audit.

- [xii] The project proponent shall ensure the compliance of Forest Department, Haryana Notification no. S.O.121/PA2/1900/S.4/97 dated 28.11.1997.
- [xiii] The Project Proponent shall ensure that no vehicle during construction/operation phase enter the project premises without valid 'Pollution Under Control' certificate from competent Authority.
- [xiv] The project proponent is responsible for compliance of all conditions in Environmental Clearance letter and project proponent can not absolve himself /herself of the responsibility by shifting it to any contractor engaged by project proponent.
- [xv] The project proponent shall seek fresh Environmental clearance if at any stage there is change in the planning of the proposed project.
- [xvi] Besides the developer/applicant, the responsibility to ensure the compliance of Environmental Safeguards/ conditions imposed in the Environmental Clearance letter shall also lie on the licensee/licensees in whose name/names the license/CLU has been granted by the Town & Country Planning Department, Haryana.
- [xvii] The proponent shall upload the status of compliance of the stipulated EC conditions, including results of monitored data on their website and shall update the same periodically. It shall simultaneously be sent to the Regional Office of MoEF, the respective Zonal Office of CPCB and the SPCB. The criteria pollutant levels namely; SPM, RSPM, SO₂, NO_x (ambient levels as well as stack emissions) or critical sectoral parameters, indicated for the project shall be monitored and displayed at a convenient location near the main gate of the company in the public domain.
- [xviii] The environmental statement for each financial year ending 31st March in Form-V as is mandated to be submitted by the project proponent to the HSPCB Panchkula as prescribed under the Environment (Protection) Rules, 1986, as amended subsequently, shall also be put on the website of the company along with the status of compliance of the EC conditions and shall also be sent to the respective Regional Offices of MoEF by e-mail.


Member Secretary,
State Level Environment Impact
Assessment Authority, Haryana, Panchkula.

Endst. No. SEIAA/HR/2013

Dated:.....

A copy of the above is forwarded to the following:

1. The Additional Director (IA Division), MOEF, GOI, CGO Complex, Lodhi Road, New Delhi.
2. The Regional office, Ministry of Environment & Forests, Govt. of India, Sector 31, Chandigarh.
3. The Chairman, Haryana State Pollution Control Board, Pkl.


Member Secretary,
State Level Environment Impact
Assessment Authority, Haryana, Panchkula.

**State Environment Impact Assessment Authority, Haryana,
Bays No.55-58, Prayatan Bhawan, Sector-2 Panchkula.**

Telephone No. 0172-2565232
E-mail ID: seiaa.hry@gmail.com

Memo No: SEIAA/HR/2020/567

Date: 16/11/2020

To

**M/s Emaar MGF Land Ltd,
306-308, 3rd Floor, Square One, C-2,
District Centre, Saket, New Delhi-110017**

**Subject: Extension of validity of Environment Clearance for Group Housing Project
“Ekaantam” at Village Bajghera, Sector 112, Gurgaon, Haryana.**

With reference to your application No. Nil dated 21.09.2020 received in this office on 05.10.2020 for seeking Extension of Validity of Environment Clearance granted for Group Housing Project “Ekaantam” at Village Bajghera, Sector 112, Gurgaon, Haryana on 24.12.2013. The Validity of your Environment Clearance is up to 23.12.2020 as per MoEF & CC, GoI dated 14.09.2006 & its subsequent Amendment dated 29.04.2015 & 14.09.2016.

The case was examined in the light of MoEF & CC, GoI Amended Notification dated 14.09.2016.

Keeping in view of above, the Authority decided to grant Extension for Validity of Environment Clearance for further 3 years i.e. upto 23.12.2023 subject to compliance of the conditions already imposed in the Environmental Clearance letter dated 24.12.2013 granted by SEIAA, Haryana.


Chairman,
SEIAA, Haryana.



भारत का राजपत्र The Gazette of India

सी.जी.-डी.एल.-अ.-18012021-224513
CG-DL-E-18012021-224513

असाधारण
EXTRAORDINARY

भाग II—खण्ड 3—उप-खण्ड (ii)
PART II—Section 3—Sub-section (ii)

प्राधिकार से प्रकाशित
PUBLISHED BY AUTHORITY

सं. 201]	नई दिल्ली, सोमवार, जनवरी 18, 2021/पौष 28, 1942
No. 201]	NEW DELHI, MONDAY, JANUARY 18, 2021/PAUSHA 28, 1942

पर्यावरण, वन और जलवायु परिवर्तन मंत्रालय

अधिसूचना

नई दिल्ली, 18 जनवरी, 2021

का.आ. 221(अ).— केंद्रीय सरकार, तत्कालीन पर्यावरण और वन मंत्रालय में, पर्यावरण (संरक्षण) अधिनियम, 1986 की धारा 3 की उप-धारा (1) और उप-धारा (2) के खंड (v) के अधीन अपनी शक्तियों के प्रयोग करते हुए, पर्यावरण समाघात निवारण अधिसूचना, 2006 (जिसे इसके बाद उक्त अधिसूचना कहा गया है) संख्या का. आ. 1533 (अ), तारीख 14 सितंबर, 2006 द्वारा प्रकाशित किया जा चुका है, उक्त अधिसूचना की अनुसूची में सभी संबंधित सूचीबद्ध नई परियोजनाओं या क्रियाकलापों के लिए उनके विस्तार और आधुनिकीकरण और/या उत्पाद मिश्रण में परिवर्तन किया जा सकता है यथास्थिति, भूमि को अभिप्राप्त करने के सिवाय, परियोजना प्रबंधन द्वारा किसी भी संनिर्माण कार्य या भूमि को तैयार करने से पूर्व संबंधित विनियामक प्राधिकरण से पूर्व पर्यावरणीय अनापत्ति अपेक्षित होगी।

और कोरोना वायरस (कोविड-19) के प्रकोप को देखते हुए और तत्पश्चात इसके नियंत्रण के लिए घोषित लॉकडाउन (कुल या आंशिक) ने, क्षेत्र में परियोजनाओं या क्रियाकलापों के कार्यान्वयन को प्रभावित किया है। पर्यावरण और वन जलवायु परिवर्तन मंत्रालय उक्त अधिसूचना में अनुज्ञात अधिकतम अवधि से परे पूर्व पर्यावरणीय अनापत्तियों की विधिमान्यता के विस्तार के लिए अनुरोधों की संख्या प्राप्ति में है, क्योंकि कोविड 19 महामारी अभी तक समाप्त नहीं हुई है। मामले की उक्त मंत्रालय में समीक्षा की गई है और चिंता इस तथ्य को ध्यान में रखते हुए है कि लॉकडाउन (कुल या आंशिक) के कारण, क्षेत्र में क्रियाकलापों को जारी रखना कठिन हो सकता है।

अतः अब, केंद्रीय सरकार, पर्यावरण (संरक्षण) नियम, 1986 के नियम 5 के (4) खंड के साथ पठित पर्यावरण (संरक्षण) अधिनियम, 1986 (1986 का 29) की धारा 3 की उप-धारा (1) की उप-धारा (2) के खंड (v) द्वारा प्रदत्त शक्तियों का प्रयोग करते हुए, लोक हित में उक्त नियमों के नियम 5 के उप-नियम (3) के खंड (क) के अधीन नोटिस की अपेक्षा अभिमुक्ति के पश्चात भारत के राजपत्र असाधारण, भाग- II, खंड 3, उपखंड (II), में प्रकाशित, भारत सरकार की तत्कालीन पर्यावरण और वन मंत्रालय अधिसूचना का.आ.1533 (अ), तारीख 14 सितंबर, 2006, में निम्नलिखित और संशोधन करती है, अर्थात्: -

उक्त अधिसूचना में,

(i) उप शीर्ष II "चरण (2) विस्तारण", के अधीन पैरा 7 के उप पैरा 7(i) में, खंड (viii) के पश्चात निम्नलिखित खंड अंतःस्थापित किया जाएगा अर्थात्: -

"(ix) उपरोक्त में अंतर्विष्ट किसी बात के होते हुए, 1 अप्रैल 2020 से 31 मार्च 2021 की अवधि में कोरोना वायरस (कोविड-19) के प्रकोप को देखते हुए और तत्पश्चात इसके नियंत्रण के लिए घोषित लॉकडाउन (कुल या आंशिक) की दृष्टि में इस अधिसूचना के उपबंधों के अधीन मंजूर संदर्भ की शर्तों की विधिमान्यता की अवधि की गणना के प्रयोजन के लिए विचार नहीं किया जाएगा, तथापि उक्त संदर्भ की शर्तों के संबंध में इस अवधि के दौरान अपनाए गए सभी क्रियाकलाप विधिमान्य समझे जाएंगे।";

(ii) पैरा 9 क के स्थान पर, निम्नलिखित पैरा रखा जाएगा, अर्थात्: -

"9 क. इस अधिसूचना में अंतर्विष्ट किसी बात के होते हुए, 1 अप्रैल 2020 से 31 मार्च 2021 की अवधि में कोरोना वायरस (कोविड-19) के प्रकोप को देखते हुए और तत्पश्चात इसके नियंत्रण के लिए घोषित लॉकडाउन (कुल या आंशिक) की दृष्टि में इस अधिसूचना के उपबंधों के अधीन मंजूर पूर्व पर्यावरणीय अनापत्ति की विधिमान्यता की अवधि की गणना के प्रयोजन के लिए विचार नहीं किया जाएगा, तथापि उक्त पर्यावरणीय अनापत्ति के संबंध में इस अवधि के दौरान अपनाए गए सभी क्रियाकलाप विधिमान्य समझे जाएंगे।";

[फा. सं. 22-25/2020-आईए. III]

गीता मेनन, संयुक्त सचिव

टिप्पण : मूल अधिसूचना भारत के राजपत्र, असाधारण, भाग II, खंड 3, उप-खंड (ii) संख्या का.आ. 1533 (अ), तारीख 14 सितंबर, 2006 द्वारा प्रकाशित की गई थी और अधिसूचना अधिसूचना संख्या का.आ. 4254 (अ), तारीख 27 नवंबर, 2020 द्वारा अंतिम बार संशोधन किया गया था।

MINISTRY OF ENVIRONMENT, FOREST AND CLIMATE CHANGE NOTIFICATION

New Delhi, the 18th January, 2021

S.O. 221(E).—Whereas, the Central Government in the erstwhile Ministry of Environment and Forests, in exercise of its powers by sub-section (1) and clause (v) of sub-section (2) of section 3 of the Environment (Protection) Act, 1986 has published the Environment Impact Assessment Notification, 2006 (hereinafter referred to as the said notification) vide number S.O.1533(E), dated the 14th September, 2006, making the requirement of prior environmental clearance from the concerned regulatory authority mandatory for all new projects or activities listed in the Schedule to the said notification, their expansion and modernisation and/or change in product mix, as the case may be, before any construction work or preparation of land by the project management except for securing the land;

And whereas, in view of the outbreak of Corona Virus (COVID-19) and subsequent lockdowns (total or partial) declared for its control, implementation of projects or activities in the field has been affected. Ministry of Environment, Forest and Climate Change is in receipt of number of requests for extension of the validity of prior environmental clearances beyond the maximum period allowed in the said notification, as the COVID-19 pandemic has not yet come to an end. The matter has been examined in the said Ministry and the concern is genuine keeping in view the fact that due to lockdowns (total or partial), continuation of activities in the field has been difficult.

Now, therefore, in exercise of the powers conferred by sub-section (1) and clause (v) of sub-section (2) of section 3 of the Environment (Protection) Act, 1986 (29 of 1986), read with sub-rule (4) of rule 5 of the Environment (Protection) Rules, 1986, the Central Government, after having dispensed with the requirement of notice under clause (a) of sub-rule (3) of rule 5 of the said rules in public interest, hereby makes the following further amendments in the notification of Government of India, in the erstwhile Ministry of Environment and Forests, number S.O. 1533 (E), dated the 14th September, 2006, published in the Gazette of India, Extraordinary, Part-II, Section 3, Sub-section (II), namely:-

In the said notification, -

- (i) in paragraph 7, in sub-paragraph 7(i), under sub-heading II. "Stage (2) – Scoping", after clause (viii), the following clause shall be inserted, namely:-

"(ix). Notwithstanding anything contained above, the period from the 1st April, 2020 to the 31st March, 2021 shall not be considered for the purpose of calculation of the period of validity of Terms of Reference granted under the provisions of this notification in view of outbreak of Corona Virus (COVID-19) and subsequent lockdowns (total or partial) declared for its control, however, all activities undertaken during this period in respect of the said Terms of Reference shall be treated as valid.";

- (ii) for paragraph 9A, the following paragraph shall be substituted namely:-

"9A. Notwithstanding anything contained in this notification, the period from the 1st April, 2020 to the 31st March, 2021 shall not be considered for the purpose of calculation of the period of validity of Prior Environmental Clearances granted under the provisions of this notification in view of outbreak of Corona Virus (COVID-19) and subsequent lockdowns (total or partial) declared for its control, however, all activities undertaken during this period in respect of the Environmental Clearance granted shall be treated as valid.".

[F.No.22-25/2020-IA.III]

GEETA MENON, Joint Secy.

Note: The principal notification was published in the Gazette of India, Extraordinary, Part II, Section 3, Sub-section (ii) vide number S.O. 1533 (E), dated the 14th September, 2006 and was last amended vide the notification number S.O. 4254(E), dated the 27th November, 2020.