

**REVISED SERVICE ESTIMATE
OF
AFFORDABLE PLOTTED COLONY
AT
SECTOR-104, GURUGRAM**

Jul-24

CLIENT : M/S SADAN REALTECH PVT. LTD.

ARCHITECT: STUDIO ATK

MEP CONSULTANT: KRIM ENGINEERING SERVICES PVT. LTD.



For Sadan Realtech Pvt. Ltd.


Director/Authorised Signatory

10 Rain Water Harvesting

Since the area has a very high water table (about 0.70M), exemption for Rain Water Harvesting has been granted by the Hydrologist, Ground Water Cell, Gurugram vide Letter No.: 637 Dated 17.08.2023. Thus the storm water will be discharged to the public storm water discharge system whenever available. Copy of letter dated 17.08.2023 is enclosed.

11 Roads

The road are proposed to be provided in the plotted development in such a way that main 9M & 12M wide colony road connects with 24M Sector Road. Internal service of the roads of the colony 9M & 12M wide provide approach for construction of roads to the plots. Detailed caculation of the various item of works have been made on the basis of the design of the roads as approved by Chief Engineer HSVP, Gurugram.

12 Street Lighting

Street lighting system has been designed to provide illumination of 15 to 20 Lux on roads. Street lights are provided on 6M high steel tubular poles are located on one side of 9M & 12M wide road. Luminaries with 60 Watts LED lights are proposed to be provided for achieving the desired illumination.

13 Horticulture

Provision of road side plantation of trees with tree guards has been made for all roads. The parks shall be provided by providing lawns & trees etc.

14 Specifications :

The work will be carried out in accordance with the standard specifications of P.H. Department as laid down by the HSVP & Haryana Government.

15 Rates

Estimates for providing services in this site has been prepared on the recent HSVP rates.

16 Cost

The total ^{revised} cost of development in this Project including various PH & B & R services works out to ~~Rs. 1173.00~~ ^{1175.20} ~~Lakhs~~ which includes 3% contingency and PE charges and 49% departmental charges also.

The cost per gross acre for this works out to ~~Rs. 82.97~~ ^{83.12} ~~Lakhs / Acre~~ which covers the provision of services like water supply, sewerage, storm water drainage, roads, street lighting and plantations including plantations maintenance thereof as well as future expansion whatsoever indicated.

M/S SADAN REALTECH PVT. LTD.
Authorised Signatory



For Sadan Realtech Pvt. Ltd.


Director/Authorised Signatory

6 Distribution System

The distribution system for this development has been designed to supply @ 172.5 liter per head per day @ 2.5 times the average rate of flow on 'Hazen William' formula with C-140. Necessary provision for laying C.I. pipe K-9 conforming to relevant IS standards along with valves and specials has been made in the project. The minimum terminal head at any point will be more than 30.00 Meters. Minimum pipe dia for distribution is kept as 100mm dia for domestic water supply.

7 Rising Mains

Rising mains for HSVP water main or sector road to water works have also been designed and provision for D.I. pipe line (dia as / design) has been made in this estimate.

8 Sewerage

This scheme is designed for sewer connecting to the proposed sewage treatment. The sewerage system has been marked on the respective plans.

The sewer lines have been designed for 3 times average DWR in relation to the water supply demand assuming that 80% of the domestic water supply shall find its way into the proposed sewer. DWC HDPE SN8 pipe sewers have been proposed designed to run half full. The sewers have been designed on 0.75 meter per second velocity ie. Self cleansing velocity. Necessary provisions for laying DWC HDPE SN8 pipes, manholes etc. has been made in this estimate.

Necessary design statement for entire sewerage system has been prepared and attached with estimate.

Size / Shape of Manholes

As per IS 4111:1986 " Circular type of manholes are much stronger than rectangular and arch type manholes thus these type of manholes are preferred over rectangular as well as arch type manholes. However both rectangular and circular type of manholes are proposed to be provided. The brick masonry rectangular manhole is proposed to be provided for depth upto 0.9m.

The brick masonry / concrete circular manholes are proposed to be provided for all depth exceeding 0.9m upwards. Circular manhole are straight down in lower portion and slanting on top portion so as to narrow down to top opening equal to internal dia of manhole cover.

Depending on the depth of manhole brick circular manhole of dia 910, 1120, 1520, 1820mm dia are proposed to be provided.

Necessary design statement for entire sewerage system has been prepared and attached with estimate.

9 Storm Water Drainage

The storm water drain is being designed to carry 6.25 mm rain fall per hour or 0.123 cusecs per acre as discharge. Also suitable provisions are contemplated in our scheme to ensure better recharging of underground water table in the area. RCC NP3 pipe drain with minimum 400 mm dia is proposed in this area with circular manhole.

For Sadan Realtech Pvt. Ltd.


Director/Authorised Signatory



REVISED SERVICE ESTIMATE for OLIVE GREEN (SECTOR - 104) GURGRAM as per TCP Haryana Memo No-Misc-2339(L)(S+4)/2024/19679-83 Dated 02.07.2024

for AFFORDABLE PLOTTED COLONY proposed at Sector 104, Gurgram for development by M/s. SADAN REALTECH PVT. LTD.

PROJECT REPORT / ESTIMATES FOR PROVIDING INTERNAL SERVICES EG. WATER SUPPLY, FIRE, SEWERAGE & STORM WATER DRAINAGE, ETC. IN RESPECT OF AFFORDABLE PLOTTED COLONY AREA MEASURING 14.1375 ACRES (LICENSE NO. 174 OF 2022) UNDER "DEEN DAYAL JAN AWAS YOJNA" IN THE REVENUE ESTATE OF VILLAGE DHANWAPUR, SECTOR 104 , DISTRICT GURUGRAM, HARYANA

Water Supply

1 Source

The source of water supply in this area by Gurugram Metropolitan Development Authority (GMDA), Gurugram, Haryanawe and also made provision made for tanker water supply. Further, we have taken the approval for drinking water supply connection from GMDA vide letter dated 12.02.2024 in respect of our application no. WC-1703603544635 dated 22.01.2024 and the said water supply line also laid upto our project site and functional (Copy of letter date 12.02.2024 is enclosed).

2 Design

The scheme has been designed for approved population of **4914 persons in 14.1375 Acres**. The rate of water supply per head per day has been taken as **172.5 litres (150+15%)** as per NBC 2016 / HSVP Norms. In addition to above necessary provision of water for community area, commercial area, parks etc. have been take into account for calculating the maximum quantity of water requirement.

3 Pumping Equipments

It has been proposed to install pumping set as described with standby of equal capacity. The provision for standby generating set has been provided in case of any electricity failure. Generator will be provided separately or added to the capacity of main generator.

4 Under Ground Storage

Underground storage tank provision has been made for **435 KL** capacity in 2 compartments of **180 KL** each, which caters for the raw & domestic and separate **75 KL** for fire fighting requirement. The water from fire compartment shall overflow to the raw water compartment so that the water in the fire compartment always remain fresh.

5 Boosting Station

A boosting station having monoblock centrifugal pump set is planned near under ground reservoir to pump water from domestic treated under ground water tank to individual plot.

For Sadan Realtech Pvt. Ltd.


Director/Authorised Signatory



**REVISED SERVICE ESTIMATE - DEEN DAYAL JAN AWAS YOJNA AFFORDABLE PLOTTED HOUSING COLONY
AT SECTOR-104, GURUGRAM (HARYANA)**

1 DESIGN CALCULATION			For	Unit
i) Daily Domestic Water Requirement				
a) Residential (D.U)				
	Population person per plot		273	
	Therefore population (DU)		18	
			4914	persons
	Total Population		4914	persons
			SAY 4914	persons
	Water requirement		@ 172.50	Lit / Head / Day
			8,47,665	LPD
			SAY 848	KLD (a)
b) Community center / Common facilities				
	Daily water requirement	1.4138	@ 25,000	Acres Lit/Acre /Day
	Therefore daily water requirement		35,345	Litres
			35.40	KLD (b)
c) No. of Convenient Shopping (Comm.)				
	Area of Convenient Shopping	1	0.5655	Acres
	Daily water requirement		@ 32,000	Lit/Acre /Day
	Therefore daily water requirement		18,096	Litres
			18.10	KLD (c)
d) No. of Milk Booth. misc.				
	Daily water requirement	1	@ 5,000	Lit / Day
	Therefore daily water requirement		1,000	Lit / Day
			5.00	KLD (d)
ii) Total Daily Water Requirement for (a+b+c+d)				
			900.50	KLD say 910.14
a) Domestic Water Requirement @				
		65%	589.22	KLD
		Say	586.70	KLD 590
b) Flushing Water Requirement @				
		35%	315.88	KLD 317.27
		Say	315.90	KLD
			320.0	
iii) Water usage from STP				
a) Area under Parks				
	Daily water requirement	1.0653	@ 25,000	Acres Lit/Acre /Day
			26,633	Lit / Day
			SAY 26.63	KLD
b) Area under Roads & Open Parking Area				
	Daily water requirement	2.6 Acres	5,000	Lit/Acre /Day
			13,025	Lit / Day
			SAY 13.09	KLD
c) Under Road+ Parks [ii (b) + iii (c)]				
			Total 39.73	KLD
			Say 39.70	KLD
iv) Total treated water requirement [ii (b) + iii (c)]				
			356.00	KLD
			366	
v) Total Daily Requirement [ii (a) + iv]				
			942.70	KLD
			950	



For Sadan Realtch Pvt. Ltd.
Director/Authorised Signatory

2	Underground Tanks					
2.1	Domestic Underground Tank					
	Daily fresh water requirement for domestic use		=	586.70	KL	590.0
	Capacity of under ground tank @ 60% storage except fire fighting	587x60%	=	352.02	KL	354.0
			Say Total	360.00	KL	
2.2	Fire water tank demand					
	Water requirement for fire use where P is population in thousands	= 1/3 (100 sqrt(P))	=	73.89	KL	
		=100-v(4914/1000)*1/3				
			Sat Total	75.00	KL	
	Capacity of under ground tank for including fire fighting		TOTAL	435.00	KL	
It is proposed to provide 1 no. under ground tank of capacity 180 KL for raw water, 1 no. underground tank capacity of 180 KL for domestic and another 75 KL capacity for fire fighting. Total Capacity of underground water tank will be 435 KL.						
Tank will have three compartments, one for fire, one for raw and one for domestic use. The water first enters the Fire compartment, then over flows to the raw water use compartement so that the water in the fire compartment shall remain fresh.						
2.3	STP Underground Tank					
	Daily recycled water requirement for flushing & irrigation use		=	356.00	KL	360.0
	Capacity of Treated water tank @ 60% storage	356x60%	=	213.60	KL	216.0
			SAY	214.00	KL	220
It is proposed to provide under ground tank of following capacity						
a)	FIRE WATER TANK			75.00	KL	
b)	RAW WATER TANK			180.00	KL	
c)	DOMESTIC WATER TANK			180.00	KL	
d)	FLUSHING, HORTICULTURE & ROAD WASHING (PART OF STP)			214.00	KL	220
	PROPOSED CAPACITY OF STP (80% OF DOMESTIC AND FLUSHING WATER) + 5% MARGINAL FACTOR			722.00	KLD	725
	=(902.50 x 80%) + 5%			36.10		910
				758.10	KLD	764.40
			Say Total	760.00	KLD	

For Sadan Realltech Pvt. Ltd.

 Director/Authorised Signatory



3	DOMESTIC WATER PUMPS - LOCATED IN PUMP ROOM				
a.)	RAW WATER FILTER FEED PUMP				
	Daily requirement for domestic use		=	586.7	KL
	Assuming 12 hours running 1 pump (with one standby)				
	Discharge/hour	589.22 586.70 / 12 / 1	=	49.10 48.89	KL/HR
			=	818.33 814.86	LPM
			SAY	820.00	LPM
	Head of pump				
	i) Suction lifts		=	0.0	m
	ii) Friction loss in M<main & specials		=	0.0	m
	iii) Clear head		=	35.0	m
			SAY	35	m
	BHP of motor	48.89166667 x1000x35/ 4500x60x 0.60		10.66	HP
			SAY	12.5	HP
b.)	Domestic Water Transfer Pumps				
	Daily requirement for domestic use overhead tank filling		=	586.70	KL
	Assuming 8 hours running 2 pumps (with one standby)				
	Discharge/hour	589.22 586.70 / 8 / 2	=	36.82 36.67	KL/HR
			=	613.66 611.15	LPM
			SAY	620.00	LPM
	Head of pump				
	i) Suction lifts		=	0.0	m
	ii) Friction loss in M<main & specials		=	22.0	m
	iii) Clear head		=	16.5	m
	iv) Residual head		=	16.5	m
			=	55.00	m
	Adding Safety factor @20%		=	65.99	m
			SAY	66.0	m
	BHP of motor	620.00x66/75x60x0.60		15.16	HP
			SAY	15.0	HP
4	FLUSHING & HORTICULTURE WATER PUMPS - LOCATED IN STP				
	Daily requirement for flushing use <i>incl. Hort</i>		=	356.00	KL
	Assuming 8 hours running 2 pumps (with one standby)				
	Discharge/hour	360 356.00 / 8 / 2	=	22.50 22.50	KL/HR
			=	375 370.83	LPM
			SAY	380.00	LPM
	Head of pump				
	i) Suction lifts		=	0.0	m
	ii) Friction loss in M<main & specials		=	13.5	m
	iii) Clear head		=	16.5	m
	iv) Residual head		=	16.5	m
			=	46.45	m
	Adding Safety factor @20%		=	55.75	m
			SAY	60	m
	BHP of motor	380.00x60/75x60x0.60		8.44	HP
			SAY	8.00	HP

For Sadan Realtech Pvt. Ltd.

Jgika
Director/Authorised Signatory



5	Capacity of Gen Set	Nos.	HP			
a.)	Raw Water Transfer Pumps (1 Working + 1 Standby)	1	12.5	=	12.5	HP
b.)	Domestic water transfer pumps (2 Working + 1 Standby)	2	15.0	=	30	HP
c.)	Flushing & Horticulture water transfer pumps (2 Working + 1 Standby)	2	10.0	=	20	HP
e.)	Lighting			=	25	HP
					87.5	HP
	or		87.5 ⁰			
			102.5x0.746x1.50		97.91	KVA
			Say		100	KVA
Requirement of 100 KVA capacity will be added in to the main D.G. set to provide standby supply.						

For Sadan Realtech Pvt. Ltd.

Jgib

Director/Authorised Signatory



Approved Estimate	Addition/Deletion due to revision	Revised Estimate
DEEN DAYAL JAN AWAS YOJNA AFFORDABLE PLOTTED HOUSING COLONY AT SECTOR-10th, GURUGRAM (HARYANA)		
M/S SADAN REALTECH PVT. LTD.		
SUMMARY OF SUB WORK - I (WATER SUPPLY)		
Description	Amount (In Lakhs.)	Amount (In Lakhs.)
Sub Head - (I) Head Works	74.55	49.20 49.53
Sub Head - (II) Pumping Machinery	42.20	25.82 (25.35)
Sub Head - (III) Distribution System	53.46	40.50-40.80
Sub Head - (IV) Irrigation Scheme	1.15	53.46
Total	171.36	1.15
Add 3% Contingencies	5.14	144.31 144.94
Add 49% Departmental Charges	176.50	4.33 4.34
(CO to final abstract of cost)	86.49	148.64
Total	262.99	72.83 149.29
Say	262.99	221.47 73.16
		222.44



For Sadan Realtech Pvt. Ltd.

[Signature]

Director/Authorised Signatory





S. No.	Sub Work / Sub Head No. II	Description	Approved Estimate			Addition/Deletion due to revision			Revised Estimate					
			Unit	Qty	Rate	Amount (Rs.) (in Lakhs)	Unit	Qty	Rate	Amount (Rs.) (in Lakhs)	Unit	Qty	Rate	Amount (Rs.) (in Lakhs)
1		Providing & installing electricity driven electro or submersible pumping set capable of delivering 18 KL/hrs of water against a total head of 65 m complete with motor and other accessories. (7.5 HP)	Nos.	2	1,80,000	3.60	(2.00)	(1,80,000)	(3.60)	Nos.				
2		Providing & installing electricity driven pumping set against a total head of 35 m complete with motor and other accessories For Filter feed pump (1 working + 1 standby): In Old Estimate: capable of delivering 625 LPM of water - 10 HP In Rev. Estimate: capable of delivering 820 LPM of water - 12.5 HP	Nos.	2	1,80,000	3.60	-	20,000	0.40	Nos.	2	2,00,000	4.00	
3		Providing & installing electricity driven pumping set against a total head of 66 m complete with motor and other accessories (For Domestic) (2 working + 1 standby) : In Old Estimate: capable of delivering 500 LPM of water - 12.5 HP In Rev. Estimate: capable of delivering 620 LPM of water - 15 HP	Nos.	3	2,00,000	6.00	-	20,000	0.60	Nos.	3	2,20,000	6.50	
		Providing & installing electricity driven pumping set total head of 60 m complete with motor and other accessories (For Flushing) (2 working + 1 standby) In Old Estimate: capable of delivering 294 LPM of water - 7.5 HP In Rev. Estimate: capable of delivering 380 LPM of water - 10 HP	Nos.	3	1,50,000	4.50	-	50,000	-0.90 1.50	Nos.	3	1,80,000 2.00	5.40 6.00	

For Sadan Realtech Pvt. Ltd.

(Signature)
Director/Authorised Signatory



		Approved Estimate		Addition/Deduction due to revision		Revised Estimate		
5	Provision for diesel engine generator set each for standby Arrangements for booster pump complete with gear head arrangements of following capacities. 1 No. - 100 KVA	KVA	100	LS	12.50	-	-	15.00 12.50
6	Provision for cheap pressure type chlorination plant complete	Each	2	1,50,000	3.00	-	-	3.00
7	Provision for making foundations & erection of pumping machinery	LS			2.00	-	-	2.00
8	Provision for pipes, valves & specials inside the pump chamber	LS			2.00	-	-	2.00
9	Provision for electric services connection including electric fittings for tubewells chambers complete	LS			3.00	-	-	3.00
10	Provision for carriage for materials and other unforeseen items	LS			2.00	-	-	2.00
	(C.D. to abstract of cost of Sub-work No.1)							
			Total		42.20			40.50
			Suby		42.20			40.50
						1.40 (4.70)		43.60
						1.40		43.60



For Sadan Realetech Pvt. Ltd.

[Signature]
Director/Authorised Signatory



S. No.	Sub Work / Sub Head (No. III)	Description	Approved Estimate			Addition/Deduction due to revision			Revised Estimate				
			Unit	Qty	Rate	Amount (Rs.) (in Lakhs)				Unit	Qty	Rate	Amount (Rs.) (in Lakhs)
												Water Supply	
												Distribution System/ Rising Main	
1	i)	Providing laying & testing of DI K-9 pipes including cost of excavation complete as per ISI marked. (For Domestic Water Main Ring Line)	M	1502	1,460	21.93	-	-	-	M	1502	1,460	21.93
2	i)	Providing, laying, jointing & testing DI K-9 pipes including cost of excavation complete as per ISI marked (Flushing water supply line)	M	1461	1,460	21.33	-	-	-	M	1461	1,460	21.33
3	i)	Providing, fixing & Testing Sluice valves including cost of complete in all respects.	Nos.	18	12,000	2.16	-	-	-	Nos.	18	12,000	2.16
4	i)	Providing, fixing & Testing Non Return valves (NRY) including cost of complete in all respects.	Nos.	1	14,000	0.14	-	-	-	Nos.	1	14,000	0.14
	ii)	80 mm i/d	Nos.	1	10,000	0.10	-	-	-	Nos.	1	10,000	0.10
5		Providing and fixing air valves and scour valves including cost of complete in all respects.	Nos.	4	10,000	0.40	-	-	-	Nos.	4	10,000	0.40
6		Providing and fixing indicating plates for sluice valve, air valve etc.	Nos.	24	1,000	0.24	-	-	-	Nos.	24	1,000	0.24
7		Providing and fixing draw out 4 way connection with all accessories for the fire brigade	LS	1	-	0.20	-	-	-	LS	1	-	0.20



For Sadan Realtech Pvt. Ltd.

gibz

Director/Authorised Signatory



	Approved Estimate		Addition/Deduction due to revision		Revised Estimate			
	LS	1			LS	1		
8	Provision for carriage of material and unforseen items		2.00			2.00		
9	Provision for cutting the roads and making to its original conditions.	LS	2.00		LS	2.00		
10	providing laying jointing & testing of DIK-9 pipes including cost of excavation complete as per ISI marked for HSNP main line and tubewells to UG Tank							
11	100 mm i/d	M	1,460	1.46	M	100	1,460	1.46
	Providing and fixing fire hydrant with accessories	Each	15,000	1.50	Each	10	15,000	1.50
	(C.O. to abstract of cost of Sub-work No.1)							
			Total	53.46			Total	53.46
			Say	53.46			Say	53.46

For Sadan Realtech Pvt. Ltd.

[Signature]
Director/Authorised Signatory



		Approved Estimate				Addition/Deletion due to revision				Revised Estimate			
S. No.	Description	Unit	Qty	Rate	Amount (Rs.) (in Lakhs)					Unit	Qty	Rate	Amount (Rs.) (in Lakhs)
	Sub Work I												
	Sub Head/No. IV												
1	Providing, laying, jointing & testing HDPE PE 80 pipe line conforming to IS 4984 including cost of Excavation etc. complete in all respect.	M	100	300	0.30								
i)	25 mm dia												
2	Providing and fixing 20mm dia Irrigation hydrant valve complete in all respect.	Nos.	10	3,500	0.35						10	3,500	0.35
3	Provision for carriage of materials etc. and other unforeseen items	LS			0.50								0.50
	(C.O. to abstract of cost of Sub-work No.1)												
				Total	1.15						Total		1.15
				Say	1.15						Say		1.15



For Sadan Realttech Pvt. Ltd.

[Signature]
Director/Authorised Signatory





Sub Work - III		Approved Estimate				Addition/Deletion due to revision				Revised Estimate			
S. No.	Description	Unit	Qty	Rate	Amount (Rs.) (in Lakhs)					Unit	Qty	Rate	Amount (Rs.) (in Lakhs)
1	Providing, lowering, jointing, cutting RCC NP3 pipes and specials into trenches including cost of excavation, cost of manholes, ventilating chambers etc. complete in all respects.												
	1) 400 mm i/d												
	a) Average depth upto 1.5 m	M	964	2,500	24.10					M	964	2,500	24.10
	b) Average depth 1.5 m to 4.5 m	M	390	2,600	10.14					M	390	2,600	10.14
2	Provision for Road Gully & Drain	LS	-	-	7.50					LS	-	-	7.50
3	Provision for Rain water Harvesting modular type complete in all respect (Exemption for Rain Water Harvesting has been granted by the Hydrologist, Ground Water Cell, Gurugram vide Letter No.: 637 Dated 17.08.2023)	LS	14	3,50,000	49.00	(14.00)				LS		3,50,000	0.00
4	Provision for cutting of roads and carriage of materials etc. and other unforeseen items	LS	-	-	2.00					LS	-	-	2.00
5	Provision for lighting, watching and temporary diversion of traffic	LS	-	-	2.00					LS	-	-	2.00
6	Provision for connection with HSVP line 400 mm i/d (Average depth 1.5 m to 4.5m)	M	10	2,600	0.26					M	10	2,600	0.26
7	Provision for Storm Water drainage connection with HSVP drainage line	LS	-	-	2.00					LS	-	-	2.00
8	Provision for timbering and shoring	LS	-	-	1.00					LS	-	-	1.00
	Add 3% contingencies			Total	98.00			(49.00)				Total	49.00
					2.94			(1.47)					1.47
	Add 49% Deptt. Charges				100.94			(50.47)					50.47
					49.46			(24.73)					24.73
				Total	150.40			(75.20)				Total	75.20
				Say	150.40			(75.20)				Say	75.20

For Sadan Realtech Pvt. Ltd.


Director/Authorised Signatory






Sub Work IV		Approved Estimate				Addition/Deletion due to revision				Revised Estimate			
S. No.	Description	Unit	Qty	Rate	Amount (Rs.) (in Lakhs)					Unit	Qty	Rate	Amount (Rs.) (in Lakhs)
1	Provision for leveling & earth filling as per site condition	Acres	14.1375	1,75,000	24.74	-	-	-	-	Acres	14.1375	1,75,000	24.74
2	Construction of road by:- i) 200 mm thick GSB ii) 250 mm thick WMM iii) 80mm thick Pavers (M-35) / 50 mm thick DBM & 30 mm BC	Sq. mtr.	6710	1,500	100.65	-	-	-	-	Sq. mtr.	6710	1,500	100.65
3	Providing for kerbs & Chennels for 14.1375 acres)	M	2240	600	13.44	-	-	-	-	M	2240	600	13.44
4	Provision of foot path of 60mm thick paver block over 100 mm thick cement concrete for 14.1375 acres (18m & 12m wide road)	Sq. mtr.	461	1,000	4.61	-	-	-	-	Sq. mtr.	461	1,000	4.61
5	Provision for Carriage of material	LS.			2.00	-	-	-	-	LS.			2.00
6	Provision for traffic lighting and guide map/ indicators	LS.			2.00	-	-	-	-	LS.			2.00
7	Provision for plot indicator & demarcating burgies.	LS.			1.00	-	-	-	-	LS.			1.00
8	Parking & pavement in commercial area (50%) = 1144 sq. m. (with interlocking paver block over 100 mm thick cement concrete)	Sq. mtr.	1144	1,000	11.44	-	-	-	-	Sq. mtr.	1144	1,000	11.44
	Add 3% contingencies charges			Total	159.88	-	-	-	-	Total			159.88
				Say	160.88	-	-	-	-	Say			160.88
					4.83	-	-	-	-				4.83
	Add 49 % department charges			Total	165.71	-	-	-	-	Total			165.71
				SAY	81.20	-	-	-	-	SAY			81.20
				Total	246.90	-	-	-	-	Total			246.90
				SAY	246.90	-	-	-	-	SAY			246.90

For Sadan Realtch Pvt. Ltd.

Gihes
Director/Authorised Signatory



	Approved Estimate		Addition/Deletion due to revision		Revised Estimate	
No. of trees @ 12m c/c = $1120 \times 2 / 12 = 186.67$ say 187 Nos.)						
Cost of the trees @ Rs. 1800/- each	Nos.	187			Nos.	187
		1,800				1,800
		3.37				3.37
Add 3% contingency charges		Total			Total	4.96
		0.15				0.15
Add 49% Deptt. Charges		5.11				5.11
		2.51				2.51
		Total			Total	7.62
		SAY			SAY	7.63

For Sadan Realtech Pvt. Ltd.

Signature

Director/Authorised Signatory

Signature



Sub Work VII		Approved Estimate			Addition/Deletion due to revision			Revised Estimate				
S. No.	Description	Unit	Qty	Rate	Amount (Rs.) (in Lakhs)				Unit	Qty	Rate	Amount (Rs.) (in Lakhs)
1	Provision for maintenance charges for water supply, sewerage, storm water drainage, roads, street light, horticulture etc. complete including operation & establishments charges as per HUDA norms after completion & resurfacing of roads after 10 years or 1st phase.	per acre	14.1375	8,00,000	113.10	-	-	-	per acre	14.1375	8,00,000	113.10
2	Provision for resurfacing & strengthening of road after five years of 1st phase @ 660/- per sqm with 80mm thick Pavers (M-35) / 50 mm thick BM & 30 mm BC	Sq. mtr.	6,710	660	44.29	-	-	-	Sq. mtr.	6,710	660	44.29
3	Provision for resurfacing & strengthening of road after ten years of 2 nd phase @ 825/- per sqm with 80mm thick Pavers (M-35) / 50 mm thick BM & 30 mm BC	Sq. mtr.	6,710	825	55.36	-	-	-	Sq. mtr.	6,710	825	55.36
	Add 3% contingency & P.F. charges	Total			212.74	-	-	-	Total			212.74
	Add 45% Departmental charges	Total			6.38	-	-	-	Total			6.38
		Total			219.13	-	-	-	Total			219.13
		Total			107.37	-	-	-	Total			107.37
		SAY			326.50	-	-	-	Total			326.50
		SAY			326.50	-	-	-	SAY			326.50

For Sadan Realtech Pvt. Ltd.

Gilbert

Director/Authorised Signatory



**REVISED SERVICE ESTIMATE - DEEN DAYAL JAN AWAS YOJNA AFFORDABLE PLOTTED HOUSING COLONY
AT SECTOR-104, GURUGRAM (HARYANA)**

TITLE - SEWER QUANTITY SHEET

S.No.	Line No.		Length (mtr.)	Dia of Pipe (mm) (mtr.)		Slope	Fall mtr	Depth			Excavation Depth (cum.)	EXCAVATION			
	From	To		Start (mtr.)	End (mtr.)			Avg. (mtr.)	0.0 - 1.5 (mtr.)	1.5 - 3.0 (mtr.)		3.0 - 4.5 (mtr.)	4.5 - 6.0 (mtr.)		
	START														
1	SMH 01	SMH 01A	14.6	200	0.200	150	0.10	0.80	0.90	0.85	10.06	14.6	0.0	0.0	0.0
2	SMH 01A	SMH 01B	14.6	200	0.200	150	0.10	0.90	0.99	0.95	10.91	14.6	0.0	0.0	0.0
3	SMH 01B	SMH 01C	14.6	200	0.200	150	0.10	0.99	1.09	1.04	11.77	14.6	0.0	0.0	0.0
4	SMH 01C	SMH 01D	14.6	200	0.200	150	0.10	1.09	1.19	1.14	12.62	14.6	0.0	0.0	0.0
5	SMH 01D	SMH 01E	14.6	200	0.200	150	0.10	1.19	1.29	1.24	13.47	14.6	0.0	0.0	0.0
6	SMH 01E	SMH 01F	14.6	200	0.200	150	0.10	1.29	1.38	1.34	14.33	14.6	0.0	0.0	0.0
7	SMH 01F	SMH 01G	14.6	200	0.200	150	0.10	1.38	1.48	1.43	15.18	14.6	0.0	0.0	0.0
8	SMH 01G	SMH 01H	20.1	200	0.200	150	0.13	1.48	1.62	1.55	22.29	0.0	20.1	0.0	0.0
9	SMH 01H	SMH 01I	14.3	200	0.200	150	0.10	1.62	1.71	1.66	16.84	0.0	14.3	0.0	0.0
10	SMH 01I	SMH 01J	13.9	200	0.200	150	0.09	1.71	1.80	1.76	17.16	0.0	13.9	0.0	0.0
11	SMH 01J	SMH 01K	14.0	200	0.200	150	0.09	1.80	1.90	1.85	18.06	0.0	14.0	0.0	0.0
12	SMH 01K	SMH 01L	14.1	200	0.200	150	0.09	1.90	1.99	1.94	18.98	0.0	14.1	0.0	0.0
13	SMH 01L	SMH 01M	9.2	200	0.200	150	0.06	1.99	2.05	2.02	12.81	0.0	9.2	0.0	0.0
14	SMH 01M	SMH 02	20.8	200	0.200	150	0.14	2.05	2.19	2.12	30.22	0.0	20.8	0.0	0.0
	START														
15	SMH 02	SMH 02	11.3	200	0.200	150	0.08	0.80	0.88	0.84	7.71	11.3	0.0	0.0	0.0
16	SMH 02	SMH 05	20.5	200	0.200	150	0.14	2.19	2.33	2.26	31.48	0.0	20.5	0.0	0.0
	START														
17	SMH 04	SMH 04A	18.9	200	0.200	150	0.13	0.80	0.93	0.86	13.19	18.9	0.0	0.0	0.0
18	SMH 04A	SMH 04B	7.7	200	0.200	150	0.05	0.93	0.98	0.95	5.78	7.7	0.0	0.0	0.0
19	SMH 04B	SMH 04C	13.2	200	0.200	150	0.09	0.98	1.07	1.02	10.46	13.2	0.0	0.0	0.0
20	SMH 04C	SMH 04D	13.2	200	0.200	150	0.09	1.07	1.15	1.11	11.16	13.2	0.0	0.0	0.0
21	SMH 04D	SMH 04E	13.2	200	0.200	150	0.09	1.15	1.24	1.20	11.86	13.2	0.0	0.0	0.0
22	SMH 04E	SMH 04F	17.4	200	0.200	150	0.12	1.24	1.36	1.30	16.70	17.4	0.0	0.0	0.0
23	SMH 04F	SMH 04G	14.5	200	0.200	150	0.10	1.36	1.45	1.41	14.84	14.5	0.0	0.0	0.0
24	SMH 04G	SMH 04H	14.6	200	0.200	150	0.10	1.45	1.55	1.50	15.79	0.0	14.6	0.0	0.0
25	SMH 04H	SMH 04I	7.4	200	0.200	150	0.05	1.55	1.60	1.56	8.33	0.0	7.4	0.0	0.0
26	SMH 04I	SMH 04J	13.0	200	0.200	150	0.09	1.60	1.69	1.64	15.16	0.0	13.0	0.0	0.0
27	SMH 04J	SMH 04K	12.1	200	0.200	150	0.08	1.69	1.77	1.73	14.72	0.0	12.1	0.0	0.0
28	SMH 04K	SMH 05	8.3	200	0.200	150	0.06	1.77	1.82	1.80	10.44	0.0	8.3	0.0	0.0
29	SMH 05	SMH 05A	8.3	250	0.250	200	0.04	2.33	2.37	2.35	14.29	0.0	8.3	0.0	0.0
	START														
30	SMH 05	SMH 05A	27.6	200	0.200	150	0.18	0.80	0.88	0.89	19.74	27.6	0.0	0.0	0.0
30	SMH 05A	SMH 05B	15.2	250	0.250	200	0.08	2.37	2.44	2.41	26.74	0.0	15.2	0.0	0.0
31	SMH 05B	SMH 05C	15.2	250	0.250	200	0.08	2.44	2.52	2.48	27.49	0.0	15.2	0.0	0.0
32	SMH 05C	SMH 05D	15.2	250	0.250	200	0.08	2.52	2.60	2.56	28.25	0.0	15.2	0.0	0.0
33	SMH 05D	SMH 07	15.2	250	0.250	200	0.08	2.60	2.67	2.63	29.00	0.0	15.2	0.0	0.0
	START														
34	SMH 06	SMH 06A	13.0	200	0.200	200	0.07	0.80	0.87	0.83	8.83	13.0	0.0	0.0	0.0
35	SMH 06A	SMH 06B	13.0	200	0.200	200	0.07	0.87	0.93	0.90	9.34	13.0	0.0	0.0	0.0
36	SMH 06B	SMH 06C	13.1	200	0.200	200	0.07	0.93	1.00	0.96	9.93	13.1	0.0	0.0	0.0
37	SMH 06C	SMH 06D	20.4	200	0.200	200	0.10	1.00	1.10	1.05	16.48	20.4	0.0	0.0	0.0
38	SMH 06D	SMH 06E	16.3	200	0.200	200	0.08	1.10	1.18	1.14	14.07	16.3	0.0	0.0	0.0
39	SMH 06E	SMH 06F	15.4	200	0.200	200	0.08	1.18	1.26	1.22	14.02	15.4	0.0	0.0	0.0
40	SMH 06F	SMH 06G	13.2	200	0.200	200	0.07	1.26	1.32	1.29	12.58	13.2	0.0	0.0	0.0
41	SMH 06G	SMH 06H	14.0	200	0.200	200	0.07	1.32	1.39	1.36	13.92	14.0	0.0	0.0	0.0
42	SMH 06H	SMH 06I	13.8	200	0.200	200	0.07	1.39	1.46	1.43	14.30	13.8	0.0	0.0	0.0
43	SMH 06I	SMH 06J	13.9	200	0.200	200	0.07	1.46	1.53	1.50	14.98	13.9	0.0	0.0	0.0
44	SMH 06J	SMH 06K	13.9	200	0.200	200	0.07	1.53	1.60	1.57	15.56	0.0	13.9	0.0	0.0
45	SMH 06K	SMH 07	18.3	200	0.200	200	0.09	1.60	1.69	1.65	21.36	0.0	18.3	0.0	0.0
46	SMH 07	SMH 07A	14.2	300	0.300	250	0.06	2.67	2.73	2.70	29.83	0.0	14.2	0.0	0.0
47	SMH 07A	SMH 07B	12.7	300	0.300	250	0.05	2.73	2.78	2.76	27.16	0.0	12.7	0.0	0.0
48	SMH 07B	SMH 07C	13.0	300	0.300	250	0.05	2.78	2.83	2.81	28.27	0.0	13.0	0.0	0.0
49	SMH 07C	SMH 12C	7.3	300	0.300	250	0.03	2.83	2.86	2.85	16.08	0.0	7.3	0.0	0.0
	START														
50	SMH 08	SMH 08A	7.9	200	0.200	200	0.04	0.80	0.84	0.82	5.31	7.9	0.0	0.0	0.0
51	SMH 08A	SMH 08B	13.4	200	0.200	200	0.07	0.84	0.91	0.87	9.43	13.4	0.0	0.0	0.0
52	SMH 08B	SMH 08C	13.4	200	0.200	200	0.07	0.91	0.97	0.94	9.97	13.4	0.0	0.0	0.0
53	SMH 08C	SMH 08D	13.4	200	0.200	200	0.07	0.97	1.04	1.01	10.51	13.4	0.0	0.0	0.0
54	SMH 08D	SMH 08E	13.5	200	0.200	200	0.07	1.04	1.11	1.07	11.13	13.5	0.0	0.0	0.0
55	SMH 08E	SMH 08F	13.4	200	0.200	200	0.07	1.11	1.18	1.14	11.59	13.4	0.0	0.0	0.0
56	SMH 08F	SMH 08G	12.9	200	0.200	200	0.06	1.18	1.24	1.21	11.67	12.9	0.0	0.0	0.0
57	SMH 08G	SMH 08H	12.1	200	0.200	200	0.06	1.24	1.30	1.27	11.40	12.1	0.0	0.0	0.0
58	SMH 08H	SMH 08I	13.6	200	0.200	200	0.07	1.30	1.37	1.33	13.33	13.6	0.0	0.0	0.0
59	SMH 08I	SMH 08J	13.0	200	0.200	200	0.07	1.37	1.43	1.40	13.26	13.0	0.0	0.0	0.0
60	SMH 08J	SMH 08K	13.1	200	0.200	200	0.07	1.43	1.50	1.47	13.88	13.1	0.0	0.0	0.0
61	SMH 08K	SMH 10	8.1	200	0.200	200	0.04	1.50	1.54	1.52	8.84	0.0	8.1	0.0	0.0

For Sadan Realtech Pvt. Ltd.

Director/Authorised Signatory



S No.	Line No.		Length	Dia of Pipe		Slope	Fall	Depth			Excavation Depth (cum.)	EXCAVATION				
	From	To		(mtr.)	(mm)			(mtr.)	(mtr.)	Start (mtr.)		End (mtr.)	Avg. (mtr.)	0.0 - 1.5 (mtr.)	1.5 - 3.0 (mtr.)	3.0 - 4.5 (mtr.)
	START															
62	SMH 09	SMH 09A	13.3	200	0.200	200	0.07	0.80	0.87	0.83	9.04	13.3	0.0	0.0	0.0	0.0
63	SMH 09A	SMH 09B	13.4	200	0.200	200	0.07	0.87	0.93	0.90	9.65	13.4	0.0	0.0	0.0	0.0
64	SMH 09B	SMH 09C	13.4	200	0.200	200	0.07	0.93	1.00	0.97	10.19	13.4	0.0	0.0	0.0	0.0
65	SMH 09C	SMH 09D	13.4	200	0.200	200	0.07	1.00	1.07	1.03	10.73	13.4	0.0	0.0	0.0	0.0
66	SMH 09D	SMH 09E	13.0	200	0.200	200	0.07	1.07	1.13	1.10	10.92	13.0	0.0	0.0	0.0	0.0
67	SMH 09E	SMH 09F	12.2	200	0.200	200	0.06	1.13	1.19	1.16	10.71	12.2	0.0	0.0	0.0	0.0
68	SMH 09F	SMH 10	14.4	200	0.200	200	0.07	1.19	1.27	1.23	13.21	14.4	0.0	0.0	0.0	0.0
69	SMH 10	SMH 10A	13.3	200	0.200	200	0.07	1.54	1.61	1.57	14.94	0.0	13.3	0.0	0.0	0.0
70	SMH 10A	SMH 10B	13.4	200	0.200	200	0.07	1.61	1.67	1.64	15.59	0.0	13.4	0.0	0.0	0.0
71	SMH 10B	SMH 12	15.5	200	0.200	200	0.08	1.67	1.75	1.71	18.70	0.0	15.5	0.0	0.0	0.0
	START															
72	SMH 11	SMH 11A	13.1	200	0.200	200	0.07	0.80	0.87	0.83	8.90	13.1	0.0	0.0	0.0	0.0
73	SMH 11A	SMH 11B	13.1	200	0.200	200	0.07	0.87	0.93	0.90	9.42	13.1	0.0	0.0	0.0	0.0
74	SMH 11B	SMH 12	8.2	200	0.200	200	0.04	0.93	0.97	0.95	6.16	8.2	0.0	0.0	0.0	0.0
75	SMH 12	SMH 12A	11.5	200	0.200	200	0.06	1.75	1.81	1.78	14.34	0.0	11.5	0.0	0.0	0.0
76	SMH 12A	SMH 12B	13.2	250	0.250	200	0.07	1.81	1.87	1.84	18.37	0.0	13.2	0.0	0.0	0.0
77	SMH 12B	SMH 12C	11.1	250	0.250	200	0.06	1.87	1.93	1.90	15.88	0.0	11.1	0.0	0.0	0.0
78	SMH 12C	SMH 13	18.2	250	0.250	200	0.09	2.83	2.92	2.88	37.59	0.0	18.2	0.0	0.0	0.0
79	SMH 13	SMH 13A	14.3	300	0.300	250	0.06	2.92	2.98	2.95	32.55	0.0	14.3	0.0	0.0	0.0
80	SMH 13A	SMH 17	13.9	300	0.300	250	0.06	2.98	3.04	3.01	32.19	0.0	0.0	13.9	0.0	0.0
	START															
81	SMH 14	SMH 14A	13.4	200	0.200	200	0.07	0.90	0.87	0.83	9.11	13.4	0.0	0.0	0.0	0.0
82	SMH 14A	SMH 14B	13.4	200	0.200	200	0.07	0.87	0.93	0.90	9.65	13.4	0.0	0.0	0.0	0.0
83	SMH 14B	SMH 14C	13.4	250	0.250	250	0.05	0.93	0.99	0.96	10.96	13.4	0.0	0.0	0.0	0.0
84	SMH 14C	SMH 16	7.0	250	0.250	250	0.03	0.99	1.02	1.00	5.92	7.0	0.0	0.0	0.0	0.0
	START															
85	SMH 15	SMH 15A	14.5	200	0.200	200	0.07	0.80	0.87	0.84	9.89	14.5	0.0	0.0	0.0	0.0
86	SMH 15A	SMH 15B	14.6	200	0.200	200	0.07	0.87	0.95	0.91	10.59	14.6	0.0	0.0	0.0	0.0
87	SMH 15B	SMH 15C	14.5	200	0.200	250	0.06	0.95	1.00	0.97	11.09	14.5	0.0	0.0	0.0	0.0
88	SMH 15C	SMH 16	15.0	200	0.200	250	0.06	1.00	1.06	1.03	12.00	15.0	0.0	0.0	0.0	0.0
89	SMH 16	SMH 16A	36.6	200	0.200	200	0.18	1.06	1.25	1.16	31.95	36.6	0.0	0.0	0.0	0.0
90	SMH 16A	SMH 17	17.6	200	0.200	250	0.07	1.25	1.32	1.28	16.70	17.6	0.0	0.0	0.0	0.0
91	SMH 17	SMH 17A	13.9	300	0.300	250	0.06	3.04	3.09	3.06	32.73	0.0	0.0	13.9	0.0	0.0
92	SMH 17A	SMH 17B	13.9	300	0.300	250	0.06	3.09	3.15	3.12	33.27	0.0	0.0	13.9	0.0	0.0
93	SMH 17B	SMH 17C	13.4	300	0.300	250	0.05	3.15	3.20	3.17	32.59	0.0	0.0	13.4	0.0	0.0
94	SMH 17C	SMH 17D	6.6	300	0.300	250	0.03	3.20	3.23	3.21	16.24	0.0	0.0	6.6	0.0	0.0
95	SMH 17D	SMH 19	10.8	300	0.300	250	0.04	3.23	3.27	3.25	26.83	0.0	0.0	10.8	0.0	0.0
	START															
96	SMH 18	SMH 18A	13.6	200	0.200	200	0.07	0.80	0.87	0.83	9.25	13.6	0.0	0.0	0.0	0.0
97	SMH 18A	SMH 19	8.9	200	0.200	200	0.04	0.87	0.91	0.89	6.36	8.9	0.0	0.0	0.0	0.0
98	SMH 19	SMH 19A	18.2	300	0.300	250	0.07	3.27	3.34	3.31	45.95	0.0	0.0	18.2	0.0	0.0
99	SMH 19A	STP	5.0	300	0.300	250	0.02	3.34	3.36	3.35	12.79	0.0	0.0	5.0	0.0	0.0
	Total		1381.0								1598.0	835.0	450.0	96.0	0.0	0.0
Pipe in excavation depth																
			(0.0 - 1.5)	(1.5 - 3.0)	(3.0 - 4.5)	(4.5 - 6.0)										
200 mm Dia pipe			815.0	277.0	0.0	0.0										
250 mm Dia pipe			21.0	112.0	0.0	0.0										
300 mm Dia pipe			0.0	62.0	95.7	0.0										

For Sadan Realtech Pvt. Ltd.


Director/Authorised Signatory



**REVISED SERVICE ESTIMATE - DEEN DAYAL JAN AWAS YOJNA AFFORDABLE PLOTTED HOUSING COLONY
AT SECTOR-104, GURUGRAM (HARYANA)**

TITLE - STORM QUANTITY SHEET

S.No.	Line No.		Length (mtr.)	Dia of Pipe (mm) (mtr.)		Slope	Depth			Excavation Depth (cum.)	EXCAVATION					
							Start	End	Avg.		0.0 - 1.5	1.5 - 3.0	3.0 - 4.5	4.5 - 6.0		
							(mtr.)	(mtr.)	(mtr.)		(mtr.)	(mtr.)	(mtr.)	(mtr.)	(mtr.)	
From	To															
	START															
1	ST 01	ST 01A	12.2	400	0.400	400	0.90	0.93	0.92	11.86	12.2	0.0	0.0	0.0		
2	ST 01A	RWHP 01	4.6	400	0.400	400	0.93	0.94	0.94	4.55	4.6	0.0	0.0	0.0		
3	RWHP 01	ST 01B	6.3	400	0.400	400	0.84	0.96	0.95	6.30	6.3	0.0	0.0	0.0		
4	ST 01B	ST 01C	13.4	400	0.400	400	0.96	0.99	0.97	13.66	13.4	0.0	0.0	0.0		
5	ST 01C	ST 03	13.4	400	0.400	400	0.99	1.02	1.01	14.02	13.4	0.0	0.0	0.0		
	START															
6	ST 02	ST 02A	13.4	400	0.400	400	0.90	0.93	0.92	13.04	13.4	0.0	0.0	0.0		
7	ST 02A	RWHP 02	5.2	400	0.400	400	0.93	0.95	0.94	5.16	5.2	0.0	0.0	0.0		
8	RWHP 02	ST 02B	6.0	400	0.400	400	0.95	0.96	0.95	6.02	6.0	0.0	0.0	0.0		
9	ST 02B	ST 02C	13.4	400	0.400	400	0.96	1.00	0.98	13.70	13.4	0.0	0.0	0.0		
10	ST 02C	ST 03	13.5	400	0.400	400	1.00	1.03	1.01	14.17	13.5	0.0	0.0	0.0		
11	ST 03	ST 03A	25.4	400	0.400	400	1.03	1.09	1.06	27.65	25.4	0.0	0.0	0.0		
12	ST 03A	RWHP 03	8.4	400	0.400	400	1.09	1.11	1.10	9.43	8.4	0.0	0.0	0.0		
13	RWHP 03	ST 05	9.8	400	0.400	400	1.11	1.14	1.13	11.18	9.8	0.0	0.0	0.0		
	START															
13	ST 04	ST 04A	6.7	400	0.400	400	0.90	0.92	0.91	6.40	6.7	0.0	0.0	0.0		
14	ST 04A	ST 04B	13.6	400	0.400	400	0.90	0.93	0.92	13.24	13.6	0.0	0.0	0.0		
15	ST 04B	ST 04C	13.6	400	0.400	400	0.93	0.97	0.95	13.61	13.6	0.0	0.0	0.0		
16	ST 04C	RWHP 04	5.5	400	0.400	400	0.97	0.98	0.97	5.61	5.5	0.0	0.0	0.0		
17	RWHP 04	ST 04D	6.9	400	0.400	400	0.98	1.00	0.99	7.12	6.9	0.0	0.0	0.0		
18	ST 04D	ST 04E	13.6	400	0.400	400	1.00	1.03	1.02	14.32	13.6	0.0	0.0	0.0		
19	ST 04E	ST 04F	13.7	400	0.400	400	1.03	1.07	1.05	14.80	13.7	0.0	0.0	0.0		
20	ST 04F	ST 05	8.3	400	0.400	400	1.07	1.09	1.08	9.15	8.3	0.0	0.0	0.0		
21	ST 05	ST 05A	14.3	400	0.400	400	1.14	1.17	1.16	16.65	14.3	0.0	0.0	0.0		
22	ST 05A	ST 11	13.4	400	0.400	400	1.17	1.21	1.19	15.98	13.4	0.0	0.0	0.0		
	START															
23	ST 06	ST 06A	13.4	400	0.400	400	0.90	0.93	0.92	13.04	13.4	0.0	0.0	0.0		
24	ST 06A	ST 06B	13.4	400	0.400	400	0.93	0.97	0.95	13.40	13.4	0.0	0.0	0.0		
25	ST 06B	RWHP 05	13.4	400	0.400	400	0.97	1.00	0.98	13.76	13.4	0.0	0.0	0.0		
26	RWHP 05	ST 06C	13.4	400	0.400	400	1.00	1.03	1.02	14.12	13.4	0.0	0.0	0.0		
27	ST 06C	ST 06D	13.5	400	0.400	400	1.03	1.07	1.05	14.59	13.5	0.0	0.0	0.0		
28	ST 06D	ST 06E	13.4	400	0.400	400	1.07	1.10	1.08	14.84	13.4	0.0	0.0	0.0		
29	ST 06E	ST 06F	13.5	400	0.400	400	1.10	1.14	1.12	15.32	13.5	0.0	0.0	0.0		
30	ST 06F	ST 08	13.4	400	0.400	400	1.14	1.17	1.15	15.56	13.4	0.0	0.0	0.0		
	START															
31	ST 07	ST 07A	7.8	400	0.400	400	0.90	0.92	0.91	7.55	7.8	0.0	0.0	0.0		
32	ST 07A	ST 07B	13.4	400	0.400	400	0.92	0.95	0.94	13.25	13.4	0.0	0.0	0.0		
33	ST 07B	RWHP 06	6.3	400	0.400	400	0.95	0.97	0.96	6.35	6.3	0.0	0.0	0.0		
34	RWHP 06	ST 07C	7.8	400	0.400	400	0.97	0.99	0.98	7.98	7.8	0.0	0.0	0.0		
35	ST 07C	ST 07D	13.4	400	0.400	400	0.99	1.02	1.01	13.99	13.4	0.0	0.0	0.0		
36	ST 07D	ST 07E	13.4	400	0.400	400	1.02	1.06	1.04	14.35	13.4	0.0	0.0	0.0		
37	ST 07E	ST 07F	13.5	400	0.400	400	1.06	1.09	1.07	14.82	13.5	0.0	0.0	0.0		
38	ST 07F	ST 07G	13.4	400	0.400	400	1.09	1.12	1.11	15.07	13.4	0.0	0.0	0.0		
39	ST 07G	ST 07H	13.4	400	0.400	400	1.12	1.16	1.14	15.43	13.4	0.0	0.0	0.0		
40	ST 07H	ST 07I	6.8	400	0.400	400	1.16	1.17	1.16	7.97	6.8	0.0	0.0	0.0		
41	ST 07I	ST 07J	9.4	400	0.400	400	1.17	1.20	1.18	11.17	9.4	0.0	0.0	0.0		
42	ST 07J	ST 07K	13.0	400	0.400	400	1.20	1.23	1.21	15.73	13.0	0.0	0.0	0.0		
43	ST 07K	ST 07L	13.0	400	0.400	400	1.23	1.26	1.25	16.07	13.0	0.0	0.0	0.0		
44	ST 07L	ST 07M	7.2	400	0.400	400	1.26	1.28	1.27	9.05	7.2	0.0	0.0	0.0		
45	ST 07M	ST 08	11.5	400	0.400	400	1.28	1.31	1.29	14.66	11.5	0.0	0.0	0.0		
46	ST 08	ST 08A	13.4	400	0.400	400	1.31	1.34	1.33	17.42	13.4	0.0	0.0	0.0		
47	ST 08A	ST 08B	13.4	400	0.400	400	1.34	1.38	1.36	17.78	13.4	0.0	0.0	0.0		
48	ST 08B	ST 10	13.4	400	0.400	400	1.38	1.41	1.39	18.14	13.4	0.0	0.0	0.0		
	START															
49	ST 09	ST 09A	13.2	400	0.400	400	0.90	0.93	0.92	12.85	13.2	0.0	0.0	0.0		
50	ST 09A	ST 09B	12.9	400	0.400	400	0.93	0.97	0.95	12.89	12.9	0.0	0.0	0.0		
51	ST 09B	ST 10	15.8	400	0.400	400	0.97	1.00	0.99	16.24	15.8	0.0	0.0	0.0		
52	ST 10	ST 10A	13.4	400	0.400	400	1.41	1.44	1.43	18.50	13.4	0.0	0.0	0.0		
53	ST 10A	RWHP 07	5.6	400	0.400	400	1.44	1.46	1.45	7.84	5.6	0.0	0.0	0.0		
54	RWHP 07	ST 10B	5.9	400	0.400	400	1.46	1.47	1.46	8.32	5.9	0.0	0.0	0.0		
55	ST 10B	ST 10C	13.4	400	0.400	400	1.47	1.50	1.49	19.16	13.4	0.0	0.0	0.0		
56	ST 10C	ST 11	13.5	400	0.400	400	1.50	1.54	1.52	19.67	0.0	13.5	0.0	0.0		
57	ST 11	ST 11A	10.3	400	0.400	400	1.54	1.56	1.55	15.25	0.0	10.3	0.0	0.0		
58	ST 11A	ST 11B	7.6	400	0.400	400	1.56	1.58	1.57	11.39	0.0	7.6	0.0	0.0		
59	ST 11B	ST 11C	13.0	400	0.400	400	1.58	1.62	1.60	19.75	0.0	13.0	0.0	0.0		
60	ST 11C	ST 11D	12.1	400	0.400	400	1.62	1.65	1.63	18.69	0.0	12.1	0.0	0.0		
61	ST 11D	ST 13	15.4	400	0.400	400	1.65	1.68	1.67	24.21	0.0	15.4	0.0	0.0		

For Sadan Realties Pvt. Ltd.

Director/Authorised Signatory

Studio ATK Architects Pvt. Ltd.
Krim Engineering Services Pvt. Ltd.

S No.	Line No.		Length (mtr.)	Dia of Pipe (mm) (mtr.)		Slope	Depth			Excavation Depth (cum.)	EXCAVATION			
	From	To		Start (mtr.)	End (mtr.)		Avg. (mtr.)	0.0 - 1.5 (mtr.)	1.5 - 3.0 (mtr.)		3.0 - 4.5 (mtr.)	4.5 - 6.0 (mtr.)		
	START													
62	ST 12	ST 12A	13.1	400	0.400	400	0.90	0.93	0.92	12.75	13.1	0.0	0.0	0.0
63	ST 12A	ST 12B	13.1	400	0.400	400	0.93	0.97	0.95	13.09	13.1	0.0	0.0	0.0
64	ST 12B	ST 12C	12.9	400	0.400	400	0.97	1.00	0.98	13.23	12.9	0.0	0.0	0.0
65	ST 12C	ST 12D	12.9	400	0.400	400	1.00	1.03	1.01	13.56	12.9	0.0	0.0	0.0
66	ST 12D	ST 12E	17.2	400	0.400	400	1.03	1.07	1.05	18.60	17.2	0.0	0.0	0.0
67	ST 12E	ST 12F	8.2	400	0.400	400	1.07	1.09	1.08	9.07	8.2	0.0	0.0	0.0
68	ST 12F	ST 12G	13.9	400	0.400	400	1.09	1.13	1.11	15.69	13.9	0.0	0.0	0.0
69	ST 12G	ST 12H	13.9	400	0.400	400	1.13	1.16	1.15	16.08	13.9	0.0	0.0	0.0
70	ST 12H	RWHP 08	7.1	400	0.400	400	1.16	1.18	1.17	8.36	7.1	0.0	0.0	0.0
71	RWHP 08	ST 12I	7.7	400	0.400	400	1.18	1.20	1.19	9.18	7.7	0.0	0.0	0.0
72	ST 12I	ST 12J	13.9	400	0.400	400	1.20	1.23	1.22	16.87	13.9	0.0	0.0	0.0
73	ST 12J	ST 12K	13.9	400	0.400	400	1.23	1.27	1.25	17.26	13.9	0.0	0.0	0.0
74	ST 12K	ST 13	7.3	400	0.400	400	1.27	1.29	1.28	9.22	7.3	0.0	0.0	0.0
75	ST 13	ST 13A	13.7	400	0.400	400	1.68	1.72	1.70	21.94	0.0	13.7	0.0	0.0
76	ST 13A	ST 13B	15.2	400	0.400	400	1.72	1.76	1.74	24.78	0.0	15.2	0.0	0.0
77	ST 13B	RWHP 09	5.5	400	0.400	400	1.76	1.77	1.76	9.08	0.0	5.5	0.0	0.0
78	RWHP 09	ST 13C	7.2	400	0.400	400	1.77	1.79	1.78	11.98	0.0	7.2	0.0	0.0
78	ST 13C	ST 13D	15.5	400	0.400	400	1.79	1.83	1.81	26.13	0.0	15.5	0.0	0.0
79	ST 13D	ST 16	20.2	400	0.400	400	1.83	1.88	1.85	34.78	0.0	20.2	0.0	0.0
	START													
80	ST 14	ST 14A	7.9	400	0.400	400	0.90	0.92	0.91	7.65	7.9	0.0	0.0	0.0
81	ST 14A	RWHP 10	6.7	400	0.400	400	0.92	0.94	0.93	6.58	6.7	0.0	0.0	0.0
82	RWHP 10	ST 14B	5.8	400	0.400	400	0.94	0.95	0.94	5.77	5.8	0.0	0.0	0.0
82	ST 14B	ST 14C	13.2	400	0.400	400	0.95	0.98	0.97	13.38	13.2	0.0	0.0	0.0
83	ST 14C	ST 14D	13.2	400	0.400	400	0.98	1.02	1.00	13.73	13.2	0.0	0.0	0.0
84	ST 14D	ST 14E	17.3	400	0.400	400	1.02	1.06	1.04	18.53	17.3	0.0	0.0	0.0
85	ST 14E	ST 14F	14.5	400	0.400	400	1.06	1.10	1.08	15.99	14.5	0.0	0.0	0.0
86	ST 14F	ST 14G	14.5	400	0.400	400	1.10	1.13	1.11	16.41	14.5	0.0	0.0	0.0
87	ST 14G	ST 14H	13.8	400	0.400	400	1.13	1.17	1.15	16.01	13.8	0.0	0.0	0.0
88	ST 14H	RWHP 11	6.4	400	0.400	400	1.17	1.18	1.18	7.55	6.4	0.0	0.0	0.0
89	RWHP 11	ST 14I	5.5	400	0.400	400	1.18	1.20	1.19	6.56	5.5	0.0	0.0	0.0
89	ST 14I	ST 16	10.8	400	0.400	400	1.20	1.22	1.21	13.05	10.8	0.0	0.0	0.0
	START													
90	ST 15	ST 16	33.0	400	0.400	400	1.00	1.08	1.04	35.41	33.0	0.0	0.0	0.0
91	ST 16	ST 17	34.9	400	0.400	400	1.88	1.96	1.92	62.01	0.0	34.9	0.0	0.0
91	ST 17	ST 17A	9.3	400	0.400	400	1.96	1.99	1.98	16.94	0.0	9.3	0.0	0.0
92	ST 17A	RWHP 12	5.7	400	0.400	400	1.99	2.00	2.00	10.47	0.0	5.7	0.0	0.0
93	RWHP 12	ST 17B	7.4	400	0.400	400	2.00	2.02	2.01	13.68	0.0	7.4	0.0	0.0
93	ST 17B	ST 17C	14.2	400	0.400	400	2.02	2.06	2.04	26.57	0.0	14.2	0.0	0.0
94	ST 17C	ST 17D	14.0	400	0.400	400	2.06	2.09	2.07	26.59	0.0	14.0	0.0	0.0
95	ST 17D	ST 17E	14.0	400	0.400	400	2.09	2.13	2.11	26.98	0.0	14.0	0.0	0.0
96	ST 17E	ST 17F	20.2	400	0.400	400	2.13	2.18	2.15	39.82	0.0	20.2	0.0	0.0
97	ST 17F	ST 17G	14.7	400	0.400	400	2.18	2.21	2.20	29.34	0.0	14.7	0.0	0.0
98	ST 17G	RWHP 13	6.9	400	0.400	400	2.21	2.23	2.22	13.92	0.0	6.9	0.0	0.0
99	RWHP 13	ST 17H	7.0	400	0.400	400	2.23	2.25	2.24	14.22	0.0	7.0	0.0	0.0
99	ST 17H	ST 17I	14.6	400	0.400	400	2.25	2.28	2.27	29.98	0.0	14.6	0.0	0.0
100	ST 17I	ST 17J	14.6	400	0.400	400	2.28	2.32	2.30	30.40	0.0	14.6	0.0	0.0
101	ST 17J	ST 17K	14.6	400	0.400	400	2.32	2.36	2.34	30.83	0.0	14.6	0.0	0.0
102	ST 17K	ST 17L	14.8	400	0.400	400	2.36	2.39	2.38	31.69	0.0	14.8	0.0	0.0
103	ST 17L	RWHP 14	7.7	400	0.400	400	2.39	2.41	2.40	16.66	0.0	7.7	0.0	0.0
104	RWHP 14	ST 17M	7.6	400	0.400	400	2.41	2.43	2.42	16.56	0.0	7.6	0.0	0.0
104	ST 17M	ST 18	8.4	400	0.400	400	2.43	2.45	2.44	18.44	0.0	8.4	0.0	0.0
105	ST 18	Ext.	10.0	400	0.400	400	2.45	2.48	2.47	22.13	0.0	10.0	0.0	0.0
	Total		1354.0							1780.0	964.0	390.0	0.0	0.0
Pipe in excavation depth														
			(0.0 - 1.5)	(1.5 - 3.0)	(3.0 - 4.5)		(4.5 - 6.0)							
400 mm Dia pipe			964.0	390.0	0.0		0.0							
500 mm Dia pipe			0.0	0.0	0.0		0.0							

For Sadan Realtech Pvt. Ltd.

[Signature]

Director/Authorised Signatory



HYDRAULIC STATEMENT OF DOMESTIC WATER SUPPLY - DEEN DAYAL JAN AWAS YOJNA AFFORDABLE PLOTTED HOUSING COLONY AT SECTOR-104, SOHNA, GURUGRAM (HARYANA)

S.no	Line Reference	Unit / plot	Populati on @ 18 person per unit	Water Requir ment @172.5 LPCD	Other Water Requirement i.e Commercial, Community Centre in LPD	Total Water Requirement (in LPH)	Domestic Water requirement @97% of total water requirement	Average Domestic Water Requirement (Total / 24)	Peak Flow in LPH (Average x 3)	Peak Flow in MG/Hr (Average x 3)	Velocity (m/s)	Size of the pipe (in mm)	Unit head Loss (in W/M)	Length in (m)	Loss of head in line (m)			Previous Cumulativ e	Total head loss (m)
															From	To	Self		
1	UGT D 20	0	273	847865	54441	902106	604411	25184	75552	75552	2.87	100	0.0698	8.0	0.526	0.105	0.830	11.366	11.988
2	D 20 D 19	0	273	847865	54441	902106	604411	25184	75552	75552	2.87	100	0.0698	87.4	4.421	0.884	5.306	6.091	11.368
3	D 19 D 18	0	273	847865	0	847865	567348	23654	70992	70992	2.81	100	0.0595	21.2	1.239	0.248	1.487	3.435	4.822
4	D 18 D 17	11	28	86940	0	86940	59250	2427	7281	7281	2.26	100	0.0009	63.2	0.054	0.011	0.065	0.17	0.062
5	D 17 D 16	11	11	34765	0	34765	22884	954	2862	2862	1.83	100	0.0002	92.2	0.014	0.003	0.017	0.000	0.017
6	D 16 D 15	18	168	548565	0	548565	369272	15319	46029	46029	1.69	100	0.0003	56.8	1.488	0.288	1.786	1.657	3.353
7	D 15 D 14	4	59	184815	0	184815	131082	5461	16383	16383	1.10	100	0.0002	34.2	0.132	0.026	0.158	0.194	0.342
8	D 14 D 13	25	83	1134	0	1134	77824	2167	6501	6501	0.23	100	0.0007	83.7	0.068	0.012	0.070	0.000	0.070
9	D 13 D 12	0	34	104570	0	104570	70733	2947	8841	8841	0.31	100	0.0012	45.8	0.087	0.011	0.089	0.046	0.113
10	D 12 D 11	6	18	49880	0	49880	33298	1387	4161	4161	0.15	100	0.0003	54.1	0.017	0.003	0.020	0.000	0.020
11	D 11 D 10	18	324	55890	0	55890	37444	1560	4680	4680	0.17	100	0.0004	66.4	0.021	0.004	0.025	0.000	0.025
12	D 10 D 9	8	95	1740	0	1740	1173	460	1387	1387	0.11	100	0.0003	53.9	0.446	0.089	0.505	0.688	1.225
13	D 09 D 08	12	12	37260	0	37260	24984	1040	3120	3120	0.11	100	0.0002	41.8	0.007	0.001	0.009	0.000	0.009
14	D 08 D 07	5	76	1360	0	1360	9235	835	19503	19503	0.89	100	0.0053	35.0	0.187	0.001	0.234	0.498	0.680
15	D 07 D 06	41	41	127305	0	127305	89294	3574	10662	10662	0.38	100	0.0017	167.7	0.293	0.089	0.381	0.000	0.381
16	D 06 D 05	29	29	522	0	522	30045	2514	7642	7642	0.37	100	0.0017	94.8	0.087	0.089	0.274	0.498	0.551
17	D 04 D 04	7	68	211140	0	211140	177988	7414	22242	22242	0.79	100	0.0009	50.9	0.347	0.017	0.105	0.000	0.105
18	D 04 D 03	0	0	0	54441	265581	12704	533	1599	1599	0.06	100	0.0001	49.4	0.003	0.001	0.003	0.000	0.003
19	D 03 D 02	35	61	18405	0	18405	12074	6274	18922	18922	0.57	100	0.0050	10.0	0.050	0.010	0.060	0.856	0.719
20	D 03 D 02	35	36	630	35345	144070	96493	4091	12063	12063	1.43	100	0.0012	104.4	0.381	0.072	0.433	0.000	0.433
21	D 03 D 01	26	26	81730	0	81730	54083	2214	6762	6762	0.24	100	0.0008	350.6	0.198	0.038	0.238	0.000	0.238

= 0.0
 = 0.0
 = 0.0
 = 0.0
 = 1502.00
 = 3502.00
 = 16.50 MTR
 = 16.80 MTR
 = 12.00 MTR
 = 10.00 MTR
 = 65.00
 = 66 MTR say

LENGTH OF 40MM DIA PIPE
 LENGTH OF 50MM DIA PIPE
 LENGTH OF 65MM DIA PIPE
 LENGTH OF 80MM DIA PIPE
 LENGTH OF 100MM DIA PIPE
 TOTAL LENGTH OF LOOP
 HEIGHT OF BUILDING FROM FFL
 PRESSURE REQUIRED AT TERRACE TO FILL TANK
 MAXIMUM HEAD LOSS IN THE LOOP
 LOSS IN PLATROOM
 HEAD REQUIRED AT PUMP FOR FILLING OHT
 ADDING SAFETY FACTOR 20%



For Sadan Realiech Pvt. Ltd.

Signature
Director/Authorised Signatory



