

Design Statement of Water Supply

Design of Pipe Line

Sr No.	Name of Road	Length of Pipe	Diameter of Pipe	Total Water Demand	Net Water Demand (Total Water Demand - Total Horticulture Water Demand)	Net Water Demand			Total Water Demand	Head Loss per M	Total Head Loss	Head Loss Progressive	Terminal Head
						self	previous	total					
						KLD	KLD	KLD					
		m	mm	L	L	KLD	KLD	KLD	20 HRS	m	m	m	m
358	A41-E6	20	250	7749	6986	6.99	1335.53	1342.51	2796.90	0.0062	0.124	4.202	25.80
359	E6-E4	211	150	77425	69376	69.38	293.72	363.09	756.45	0.0066	1.393	5.595	24.41
360	E4-E14	113	100	66858	62548	62.55	231.17	293.72	611.91	0.0321	3.628	9.223	20.78
361	E14-E13	56	100	5626	3490	3.49	227.68	231.17	481.60	0.0206	1.154	10.377	19.62
362	E13-E13	115	100	48804	44418	44.42	0.00	44.42	92.54	0.0010	0.112	10.489	19.51
363	E13-E11	28	100	7726	6658	6.66	176.61	183.26	381.80	0.0134	0.375	10.753	19.25
364	E11-E12	47	100	23173	21380	21.38	0.00	21.38	44.54	0.0003	0.012	10.764	19.24
365	E11-E10	30	100	1144	0	0.00	155.23	155.23	323.39	0.0099	0.296	11.048	18.95
366	E10-E2	160	100	71651	65548	65.55	26.96	92.51	192.72	0.0038	0.605	11.653	18.35
367	E2-E2	113	100	31269	26959	26.96	0.00	26.96	56.16	0.0004	0.044	11.697	18.30
368	E2-E1	49	100	1869	0	0.00	0.00	0.00	0.00	0.0000	0.000	11.653	18.35
369	E10-E8	49	100	10527	4908	4.91	57.81	62.72	130.66	0.0018	0.090	11.138	18.86
370	E8-E1	160	100	63914	57811	57.81	0.00	57.81	120.44	0.0016	0.253	11.392	18.61
371	E1-B'12	56	100	2136	0	0.00	0.00	0.00	0.00	0.0000	0.000	11.392	18.61
372	E6-A42	37	250	9648	8236	8.24	964.20	972.43	2025.90	0.0034	0.126	4.328	25.67
373	A42-A56	13	250	5153	4658	4.66	959.54	964.20	2008.74	0.0033	0.043	4.372	25.63
374	A56-E3	83	100	30125	26959	26.96	0.00	26.96	56.16	0.0004	0.032	4.404	25.60
375	A56-A43	40	250	12262	6986	6.99	925.59	932.58	1942.88	0.0031	0.126	4.497	25.50
376	A43-A58	55	100	14255	12158	12.16	0.00	12.16	25.33	0.0001	0.005	4.502	25.50
377	A43-A57	9	250	843	500	0.50	912.94	913.44	1902.99	0.0030	0.027	4.525	25.48
378	A57-A44	49	250	16592	14723	14.72	898.21	912.94	1901.95	0.0030	0.148	4.673	25.33
379	A44-A54	100	100	25273	21459	21.46	0.00	21.46	44.71	0.0003	0.025	4.698	25.30
380	A44-E1	209	100	72691	59719	59.72	0.00	59.72	124.41	0.0017	0.351	5.024	24.98
381	A44-A45	55	250	16070	13973	13.97	803.06	817.04	1702.16	0.0025	0.135	4.808	25.19
382	A45-A46	71	100	12366	9658	9.66	26.21	35.87	74.72	0.0007	0.046	4.855	25.15
383	A46-B'1	57	100	12739	10565	10.57	0.00	10.57	22.01	0.0001	0.004	4.858	25.14

Sheet No:- 14

Ky consultants Pvt Ltd

Authorised Signatory

Design Statement of Water Supply

Design of Pipe Line

Sr No.	Name of Road	Length of Pipe m	Diameter of Pipe mm	Total Water Demand L	Net Water Demand (Total Water Demand - Total Horticulture Water Demand)	Net Water Demand			Total Water Demand	Head Loss per M	Total Head Loss	Head Loss Progressive	Terminal Head
						self	previous	total					
				L	L	KLD	KLD	KLD	LPM	m	m	m	m
384	A46-A'47	52	100	17627	15644	15.64	0.00	15.64	32.59	0.0001	0.007	4.862	25.14
385	A45-B'12	208	250	45499	29315	29.32	737.88	767.20	1598.33	0.0022	0.456	5.264	24.74
386	B'12-B'12	24	250	5573	4658	4.66	733.23	737.88	1537.26	0.0020	0.049	5.313	24.69
387	B12-C10	206	150	39145	31288	31.29	254.99	286.28	596.42	0.0042	0.875	6.188	23.81
388	C10-C11	64	100	14085	11644	11.64	0.00	11.64	24.26	0.0001	0.005	6.194	23.81
389	C10-C7	84	100	9454	6250	6.25	237.10	243.35	506.98	0.0227	1.904	8.092	21.91
390	C7-C8	29	100	11106	10000	10.00	194.25	204.25	425.51	0.0164	0.475	8.567	21.43
391	C8-C12	120	100	198824	194246	194.25	0.00	194.25	404.68	0.0149	1.792	10.359	19.64
392	C7-C6	55	100	2348	250	0.25	32.60	32.85	68.44	0.0006	0.031	8.123	21.88
393	C6-C13	182	100	58295	32603	32.60	0.00	32.60	67.92	0.0005	0.100	8.222	21.78
394	B12-B13	23	150	877	0	0.00	446.95	446.95	931.14	0.0097	0.223	5.536	24.46
395	B13-B14	43	150	12126	10486	10.49	436.46	446.95	931.14	0.0097	0.417	5.953	24.05
396	B14-B17	46	150	17162	15408	15.41	421.05	436.46	909.29	0.0093	0.427	6.380	23.62
397	B17-B27	8	150	305	0	0.00	421.05	421.05	877.19	0.0087	0.069	6.449	23.55
398	B27-B19	56	150	14544	12408	12.41	408.64	421.05	877.19	0.0087	0.486	6.935	23.06
399	B19-B'21	40	150	7933	6408	6.41	402.24	408.64	851.34	0.0082	0.329	7.264	22.74
400	B'21-B'22	14	150	534	0	0.00	402.24	402.24	837.99	0.0080	0.112	7.376	22.62
401	B'22-B'5	87	150	3319	0	0.00	402.24	402.24	837.99	0.0080	0.694	8.070	21.93
402	83B'5-B'5	223	100	57451	48945	48.95	31.62	80.56	167.84	0.0029	0.652	8.722	21.28
403	B'5-B'4	78	100	2975	0	0.00	31.62	31.62	65.87	0.0005	0.040	8.763	21.24
404	B'4-B'6	64	100	24400	21959	21.96	0.00	21.96	45.75	0.0003	0.017	8.779	21.22
405	B'4-B'3	56	100	4136	2000	2.00	7.66	9.66	20.12	0.0001	0.003	8.766	21.23
406	B'3-B'2	18	100	8344	7658	7.66	0.00	7.66	15.95	0.0000	0.001	8.766	21.23
407	SECTOR 84-												
408	83B'5-84D17	72	150	2746	0	0.00	321.68	321.68	670.16	0.0053	0.380	8.449	21.55
409	84D17-D4	149	100	37221	27538	27.54	0.00	27.54	57.37	0.0004	0.060	8.509	21.49
409	D17-D18	46	150	6412	4658	4.66	289.48	294.14	612.79	0.0045	0.206	8.655	21.35
410	D18-D6	30	100	12709	11565	11.57	0.00	11.57	24.09	0.0001	0.002	8.657	21.34

Design Statement of Water Supply

Sr No.	Name of Road	Length of Diameter of Pipe	Total Water Demand	Net Water Demand (Total Water Demand - Total Horticulture Water Demand)	Design of Pipe Line				Total Head Loss	Head Loss Progressive	Terminal Head
					self	previous	total	Total Water Demand	Head Loss per M		
		m	L	L	KLD	KLD	KLD	20 HRS LPM	m	m	m
411	D18-D3	128	4880	43918	43.92	0.00	43.92	91.49	0.0010	8.777	21.22
412	D18-D19	129	28801	23880	23.88	0.00	23.88	49.75	0.0003	8.695	21.31
413	D18-D22	44	1678	0	0.00	210.12	210.12	437.74	0.0024	8.760	21.24
414	D22-D5	37	13416	12005	12.01	0.00	12.01	25.01	0.0001	8.764	21.24
415	D22-D21	166	36707	30375	30.38	167.74	198.11	412.73	0.0021	9.117	20.88
416	D21-D7	22	839	0	0.00	167.74	167.74	349.45	0.0114	9.368	20.63
417	D7-D23	74	4323	1500	1.50	57.34	58.84	122.58	0.0016	9.489	20.51
418	D23-A7	92	35797	32288	32.29	25.05	57.34	119.45	0.0016	9.632	20.37
419	A7-E1	59	2251	0	0.00	25.05	25.05	52.19	0.0003	9.652	20.35
420	E1-E2	22	7664	6825	6.83	18.23	25.05	52.19	0.0003	9.659	20.34
421	E2-E3	50	16057	12150	12.15	0.00	12.15	25.31	0.0001	9.664	20.34
422	E2-E4	30	7219	6075	6.08	0.00	6.08	12.66	0.0000	9.660	20.34
423	D7-D20	90	17406	13973	13.97	94.93	108.90	226.88	0.0051	9.828	20.17
424	D20-D19	143	12441	6986	6.99	87.94	94.93	197.77	0.0040	10.395	19.61
425	D19-D2	108	62578	20959	20.96	66.98	87.94	183.21	0.0034	10.766	19.23
426	D2-A2	61	6077	3750	3.75	63.23	66.98	139.55	0.0021	10.893	19.11
427	A2-D1	27	8687	7658	7.66	0.00	7.66	15.95	0.0000	10.894	19.11
428	A2-A2	62	12272	9908	9.91	0.00	9.91	20.64	0.0001	10.897	19.10
429	A2-A1	53	12837	10815	10.82	34.85	45.67	95.14	0.0010	10.947	19.05
430	84A1-84A11	153	23637	17801	17.80	17.05	34.85	72.61	0.0006	11.042	18.96
431	A11-A12	53	16865	4658	4.66	12.39	17.05	35.52	0.0002	11.051	18.95
432	A12-A12	53	9008	6986	6.99	0.00	6.99	14.55	0.0000	11.053	18.95
433	84A12-84A13	18	6094	5408	5.41	0.00	5.41	11.27	0.0000	11.051	18.95
Total Length		31372	3264170	2652856							
Road Length		36006	9233495	7306186	7306						

For VATIKA LIMITED
Authorised Signatory

Sector 83 VATIKA (Gurgaon) Design Statement of Roads

Sr No.	Name of Road	Length of Road	Width of Road	Natural Surface Levels		Slope Character	Longitudinal Slope	Formation Levels		Quantity	Earthwork in Filling	Excavation in Cutting	Road Length			
				Upstream Level	Downstream Level			Upstream Level	Downstream Level				12 M Wide Road	15 M Wide Road	18 M Wide Road	24 M Wide Road
1	2	3	4	5	6	7	8	9	10	14	15	16	17	18	19	20
				Natural Surface Levels				Formation Levels								
	SECTOR 83															
1	A47-A46	58	24	231.000	230.750	1	300	231.099	230.906	177.16	177.16	0.00				58
2	A46-A45	67	24	230.750	230.250	-1	330	230.906	230.703	488.98	488.98	0.00				67
3	A44-A45	62	24	230.250	230.750	1	230	230.703	230.972							62
4	A57-A44	47	24	230.750	230.750	1	225	230.972	231.181							47
5	A43-A57	8	24	230.750	230.500	1	200	231.181	231.221	110.60	110.60	0.00				8
6	A56-A43	42	24	230.500	231.000	1	225	231.221	231.408	568.88	568.88	0.00				42
7	A42-A56	13	24	231.000	231.250	1	225	231.408	231.465	97.21	97.21	0.00				13
8	E6-A42	37	24	231.250	231.250	1	225	231.465	231.630	264.35	264.35	0.00				37
9	A41-E6	18	24	231.250	231.250	1	150	231.630	231.750	190.05	190.05	0.00				18
10	E7-A41	32	24	231.250	231.500	1	200	231.750	231.910	349.38	349.38	0.00				32
11	A37-E7	23	24	231.500	231.250	1	225	231.910	232.012	323.49	323.49	0.00				23
12	E21-E20	45	24	232.500	232.750	1	250	233.099	233.279	609.59	609.59	0.00				45
13	E22-E21	48	24	232.750	233.000	1	200	233.279	233.519	604.15	604.15	0.00				48
14	A22-E22	74	24	233.000	233.250	1	200	233.519	233.889	1029.08	1029.08	0.00				74
15	E23-A22	13	24	233.250	233.500	1	200	233.889	233.954	170.64	170.64	0.00				13
16	E23-A17	6	24	233.500	233.750	1	125	233.954	234.002	50.89	50.89	0.00				6
17	E23-E25	38	24	233.500	233.750	-1	350	233.954	233.846	250.94	250.94	0.00				38
18	E25-E24	26	24	233.750	233.500	-1	350	233.846	233.772	114.64	114.64	0.00				26
19	A14-A11	55	24	234.250	234.250	1	185	234.341	234.638	316.28	316.28	0.00				55
20	A11-A11	17	24	234.250	234.500	1	200	234.638	234.723	124.75	124.75	0.00				17
21	A5-A2	96	24	235.000	235.500	1	175	235.241	235.790	611.47	611.47	0.00				96

Sector 83 VATIKA (Gurgaon) Design Statement of Roads

Sr No.	Name of Road	Length of Road m	Width of Road m	Natural Surface Levels		Slope Character	Longitudinal Slope	Formation Levels		Quantity cum	Earthwork in Filling cum	Excavation in Cutting cum	Road Length			
				Upstream Level	Downstream Level			Upstream Level	Downstream Level				12 M Wide Road m	15 M Wide Road m	18 M Wide Road m	24 M Wide Road m
22	A2-A26	186	24	235.500	235.000	1	225	235.790	236.616	4254.25	4254.25	0.00				186
23	A2-A25	64	24	235.500	236.250	1	125	235.790	236.302	262.16	262.16	0.00				64
24	A25-A24	75	24	236.250	236.250	1	200	236.302	236.677	430.52	430.52	0.00				75
25	A24-A'23	179	24	236.250	237.250	1	200	236.677	237.572	1607.48	1607.48	0.00				179
26	A45-A'52	53	24	230.250	230.250	-1	200	230.703	230.438	407.14	407.14	0.00				53
27	A'53-B'12	140	24	230.250	229.750	-1	200	230.438	229.738	294.26	294.26	0.00				140
28	B'12-B12	24	24	229.750	229.500	-1	175	229.738	229.600	25.35	25.35	0.00				24
29	B12-C10	211	24	229.500	228.500	-1	220	229.600	228.641	612.18	612.18	0.00				211
30	C10-C7	75	24	228.500	228.000	-1	225	228.641	228.308	404.42	404.42	0.00				75
31	C7-C8	20	24	228.000	228.250	1	300	228.308	228.375	103.84	103.84	0.00				20
32	C8-C9	47	24	228.250	228.500	1	250	228.375	228.563	105.67	105.67	0.00				47
33	C7-C6	63	24	228.000	227.750	-1	350	228.308	228.128	518.63	518.63	0.00				63
34	C6-C5	25	24	227.750	227.750	-1	225	228.128	228.017	193.47	193.47	0.00				25
35	A46-B'1	54	12	230.750	230.500	1	2000	230.906	230.933	190.58	190.58	0.00	54			
36	A55-A'48	14	12	231.000	231.250	-1	475	232.290	232.260	193.21	193.21	0.00	14			
37	A'48-A'49	77	12	231.250	231.500	-1	475	232.260	232.098	743.13	743.13	0.00	77			
38	A'49-A'50	165	12	231.500	231.750	-1	500	232.098	231.768	610.24	610.24	0.00	165			
40	A'50-A42	152	12	231.750	231.250	-1	500	231.768	231.464	211.96	211.96	0.00	152			
39	A'50-A'51	51	12	231.750	231.800	-1	725	231.768	231.698	25.69	25.69	25.69	51			
40	A'51-A40	29	15	231.800	232.000	-1	750	231.698	231.659	96.34	96.34	96.34		29		
41	A40-A38	19	18	232.000	232.000	1	100	231.659	231.849	84.07	84.07	84.07			19	
42	A38-A'39	20	12	232.000	232.000	1	100	231.849	232.049	12.19	12.19	12.19	20			
43	A38-A'36	49	18	232.000	232.250	1	1200	231.849	231.890	225.26	225.26	225.26			49	
44	A'36-A37	137	12	232.250	231.250	1	1125	231.890	232.012	330.30	330.30	0.00	137			
45	A38-A'32	95	18	232.000	232.500	-1	1000	231.849	231.754	766.61	766.61	766.61			95	
46	A'32-A33	64	18	232.500	232.750	1	5000	231.754	231.767	995.80	995.80	995.80			64	
47	A33-A29	150	12	232.750	233.250	1	5000	231.767	231.797	2192.41	2192.41	2192.41	150			

Authorised Signatory

Sector 83 VALIKA (Gurgaon) Design Statement of Roads

Sr No.	Name of Road	Length of Road m	Width of Road m	Natural Surface Levels		Slope Character	Longitudinal Slope	Formation Levels		Quantity cu.m	Earthwork in Filling cu.m	Excavation in Cutting cu.m	Road Length			
				Upstream Level	Downstream Level			Upstream Level m	Downstream Level m				12 M Wide Road m	15 M Wide Road m	18 M Wide Road m	24 M Wide Road m
48	A29-A30	19	12	233.250	233.250	1	5000	231.797	231.801	330.85	0.00	330.85	19			
49	A33-A34	71	18	232.750	232.750	1	5000	231.767	231.781	1247.21	0.00	1247.21			71	
50	A34-A31	63	15	232.750	232.500	-1	4300	231.781	231.767	804.32	0.00	804.32		63		
51	A32-A31	100	18	232.500	232.500	1	8500	231.754	231.766	1331.87	0.00	1331.87			100	
52	A31-A28	55	18	232.500	232.750	1	1400	231.766	231.805	831.01	0.00	831.01				55
53	A28-A27	21	12	232.750	233.000	1	5000	231.805	231.809	269.05	0.00	269.05	21			
54	A28-A35	22	18	232.750	233.000	1	5000	231.805	231.810	422.75	0.00	422.75			22	
55	A51-A41	135	15	232.000	231.250	1	2600	231.698	231.750	200.11	200.11	0.00		135		
56	A56-E3	98	12	231.000	230.750	1	5000	231.408	231.427	637.98	637.98	0.00	98			
57	A43-A58	55	15	230.500	231.250	1	700	231.221	231.300	317.89	317.89	0.00		55		
58	A57-E1	53	12	230.750	230.750	1	5000	231.181	231.192	277.51	277.51	0.00	53			
59	A44-A54	101	12	230.750	231.000	1	800	230.972	231.098	194.24	194.24	0.00	101			
60	A44-E1	213	12	230.750	230.000	-1	200	230.972	229.907	165.22	165.22	0.00	213			
61	B12-E1	62	15	229.750	230.000	1	365	229.738	229.907	48.82	0.00	48.82		62		
62	E1-E8	162	12	230.000	228.750	-1	685	229.907	229.671	804.61	804.61	0.00	162			
63	E8-E10	50	12	228.750	229.000	1	265	229.671	229.859	533.99	533.99	0.00	50			
64	E1-E2	49	15	230.000	230.000	-1	3300	229.907	229.893	73.49	0.00	73.49		49		
65	E2-E2	111	12	230.000	230.500	1	5000	229.893	229.915	461.28	0.00	461.28	111			
66	E2-E10	162	12	230.000	229.000	-1	5000	229.893	229.860	731.70	731.70	0.00	162			
67	E2-E3	33	15	230.000	230.250	1	5000	229.893	229.899	113.41	0.00	113.41		33		
68	E10-E11	33	12	229.000	229.250	1	250	229.859	229.991	316.93	316.93	0.00	33			

Sector 83 VAHIKA (Gurgaon) Design Statement of Roads

Sr No.	Name of Road	Length of Road m	Width of Road m	Natural Surface Levels		Slope Character	Longitudinal Slope	Formation Levels		Quantity cu.m	Earthwork in Filling cu.m	Excavation in Cutting cu.m	Road Length			
				Upstream Level	Downstream Level			Upstream Level	Downstream Level				12 M Wide Road	15 M Wide Road	18 M Wide Road	24 M Wide Road
69	E11-E12	61	12	229.250	228.750	1	5000	229.991	230.004	730.11	730.11	0.00	61			
70	E11-E13	38	12	229.250	229.250	1	375	229.991	230.093	361.15	361.15	0.00	38			
71	E13-E13	114	12	230.250	229.250	1	775	230.093	230.240	569.37	569.37	0.00	114			
72	E13-E14	55	12	229.250	229.700	1	115	230.093	230.571	565.48	565.48	0.00	55			
73	E14-E4	118	12	229.250	230.000	-1	700	230.571	230.402	1220.07	1220.07	0.00	118			
74	E4-E4	40	15	230.000	229.500	-1	250	230.402	230.242	343.41	343.41	0.00	40			
75	E4-E6	215	12	230.000	231.250	1	175	230.402	231.631	1010.41	1010.41	0.00	215			
76	E4-E5	49	15	230.000	230.500	1	180	230.402	230.675	212.02	212.02	0.00	49			
77	E5-E7	216	12	230.500	231.500	1	175	230.675	231.909	756.12	756.12	0.00	216			
78	E5-E15	76	12	230.500	230.250	1	2200	230.675	230.709	288.96	288.96	0.00	76			
79	E15-E16	115	12	230.250	230.000	1	825	230.709	230.849	902.26	902.26	0.00	115			
80	E15-E17	114	12	230.250	230.750	1	950	230.709	230.829	368.15	368.15	0.00	114			
81	E21-E31	79	12	232.750	232.750	-1	8000	233.279	233.270	497.22	497.22	0.00	79			
82	E31-E27	82	12	232.750	232.750	-1	8000	233.270	233.259	506.20	506.20	0.00	82			
83	E27-E33	75	12	232.750	232.250	1	5000	233.270	233.285	699.35	699.35	0.00	75			
84	E33-E34	49	12	232.250	232.250	1	5000	233.285	233.294	611.20	611.20	0.00	49			
85	E34-E35	61	12	232.250	232.500	1	5000	233.294	233.307	677.44	677.44	0.00	61			
86	E27-E29	100	12	232.750	232.500	-1	900	233.259	233.148	694.51	694.51	0.00	100			
87	E34-E29	36	12	232.250	232.500	-1	250	233.294	233.150	366.06	366.06	0.00	36			
88	E29-E30	29	12	232.500	232.750	-1	900	233.148	233.116	176.47	176.47	0.00	29			
89	E26-E27	59	12	232.750	233.000	-1	1400	233.259	233.217	257.17	257.17	0.00	59			
90	E26-E28	91	12	233.000	233.000	-1	1400	233.217	233.152	201.66	201.66	0.00	91			
91	E26-E32	82	12	233.000	233.750	1	150	233.217	233.764	113.65	113.65	0.00	82			

Authorised Signatory

Sector 83 VATIKA (Gurgaon) Design Statement of Roads

Sr No.	Name of Road	Length of Road m	Width of Road m	Natural Surface Levels		Slope Character	Longitudinal Slope	Formation Levels		Quantity	Earthwork in Filling cum	Excavation in Cutting cum	Road Length			
				Upstream Level	Downstream Level			Upstream Level	Downstream Level				12 M Wide Road m	15 M Wide Road m	18 M Wide Road m	24 M Wide Road m
92	E23-A21	82	12	233.500	233.750	1	5000	233.954	233.971	332.23	332.23	0.00	82			
93	E25-A14	98	12	233.750	234.250	1	200	233.846	234.336	106.86	106.86	0.00	98			
94	A14-A59	115	12	234.250	234.500	1	500	234.336	234.566	104.69	104.69	0.00	115			
95	A59-A60	102	12	234.500	234.000	1	5000	234.566	234.586	399.10	399.10	0.00	102			
96	A10-A11	178	15	234.250	235.000	1	700	234.638	234.893	374.86	374.86	0.00	178			
97	A13-A10	52	18	235.000	234.750	1	5000	234.893	234.903	21.29	21.29	0.00			52	
98	A9-A10	177	15	235.000	235.250	1	500	234.893	235.247	147.24	0.00	147.24	177			
99	A12-A9	55	12	235.250	235.000	-1	200	235.247	234.972	10.53	0.00	10.53	55			
100	A12-A19	65	12	235.000	234.750	1	5000	234.972	234.985	80.37	80.37	0.00	65			
101	A15-A12	53	12	235.000	234.750	-1	175	234.972	234.669	34.91	0.00	34.91	53			
102	A15-A16	53	12	234.750	234.500	1	5000	234.669	234.679	31.15	31.15	0.00	53			
103	A18-A15	34	12	234.750	234.500	1	5000	234.669	234.675	19.21	19.21	0.00	34			
104	A9-A6	55	12	235.250	235.500	1	195	235.247	235.529	8.29	8.29	0.00	55			
105	A6-A20	55	12	235.500	235.500	1	5000	235.529	235.540	22.50	22.50	0.00	55			
106	A6-A3	55	12	235.500	236.000	1	190	235.529	235.818	50.60	0.00	50.60	55			
107	A3-A3	55	15	236.000	236.000	1	5000	235.818	235.829	145.56	0.00	145.56			55	
108	A3-A1	36	12	236.000	236.250	1	5000	235.818	235.825	131.04	0.00	131.04	36			
109	A10-A7	55	18	235.000	235.250	1	225	234.893	235.137	109.13	0.00	109.13			55	
110	A7-A20	65	12	235.250	235.500	1	5000	235.137	235.150	180.58	0.00	180.58	65			
111	A7-A7	116	12	235.250	234.750	1	5000	235.137	235.160	206.83	206.83	0.00	116			
112	A7-A4	55	18	235.250	235.500	1	140	235.137	235.530	41.17	0.00	41.17			55	
113	A4-A8	71	15	235.500	236.000	1	5000	235.530	235.544	226.91	0.00	226.91			71	
114	A4-A4	30	12	235.500	235.750	1	5000	235.530	235.536	33.18	0.00	33.18	30			

Sector 83 VATIKA (Gungzon) Design Statement of Roads

Sr No.	Name of Road	Length of Road	Width of Road	Natural Surface Levels		Slope Character	Longitudinal Slope	Formation Levels		Quantity	Earthwork in Filling	Excavation in Cutting	Road Length			
				Upstream Level	Downstream Level			Upstream Level	Downstream Level				12 M Wide Road	15 M Wide Road	18 M Wide Road	24 M Wide Road
		m	m					m	m	cu.m	cu.m	cu.m	m	m	m	m
115	A4-A5	194	15	235.500	225.000	-1	675	235.530	235.242	396.17	396.17	0.00			194	
116	C10-C11	81	12	228.500	228.500	1	775	228.641	228.746	188.18	188.18	0.00	81			
117	C6-C13	212	12	227.750	228.750	1	1025	228.128	228.335	47.26	0.00	47.26	212			
118	C8-C12	151	12	228.250	228.750	1	975	228.375	228.530	86.77	0.00	86.77	151			
119	B12-B13	19	15	229.500	229.250	1	175	229.600	229.709	79.72	79.72	0.00			19	
120	B13-B13	37	12	229.250	229.500	1	5000	229.709	229.716	149.94	149.94	0.00	37			
121	B13-B14	43	15	229.250	229.250	-1	190	229.709	229.483	223.07	223.07	0.00			43	
122	B14-B15	55	12	229.250	229.000	1	5000	229.483	229.494	239.70	239.70	0.00	55			
123	B14-B17	54	15	229.250	229.000	-1	250	229.483	229.267	202.25	202.25	0.00			54	
124	B17-B25	53	12	229.000	229.250	1	5000	229.267	229.277	93.49	93.49	0.00	53			
125	B17-B27	11	15	229.000	229.000	1	200	229.267	229.322	48.54	48.54	0.00			11	
126	B27-B18	52	15	229.000	229.250	1	5000	229.322	229.332	157.47	157.47	0.00			52	
127	B27-B19	55	15	229.000	229.000	1	175	229.322	229.636	395.04	395.04	0.00			55	
128	B19-B20	20	12	229.000	229.000	1	5000	229.636	229.640	153.11	153.11	0.00	20			
129	B19-B24	48	12	229.000	229.000	1	5000	229.636	229.646	369.09	369.09	0.00	48			
130	B19-B21	34	15	229.000	229.250	1	200	229.636	229.806	303.95	303.95	0.00			34	
131	B21-B22	19	15	229.250	228.750	1	200	229.806	229.901	243.24	243.24	0.00			19	
132	B22-B'5	47	12	228.750	228.750	1	400	229.901	230.018	682.28	682.28	0.00	47			
133	B'5-B5	246	12	228.750	228.500	1	375	230.018	230.674	5081.79	5081.79	0.00	246			
134	B5-B4	88	12	228.500	229.000	1	1200	230.674	230.748	2070.97	2070.97	0.00	88			
135	B4-B6	62	12	229.000	229.250	1	5000	230.748	230.760	1211.98	1211.98	0.00	62			
136	B4-B3	59	12	229.000	228.000	1	5000	230.748	230.760	1595.63	1595.63	0.00	59			
137	B3-B2	28	15	228.000	228.500	1	5000	230.760	230.765	1055.21	1055.21	0.00			28	
Total		10065								39330.9	50908.2	-11577.3	5936	1505	637	1987

Authorised Signatory

Sector 84 VATIKA (Gurgaon) Design Statement of road

Sr No.	Name of Road	Length of Road m	Width of Road m	Natural Surface Levels		Slope Character	Longitudinal Slope	Formation Levels		Depth		Quantity	Earthwork in Filling cu.m	Excavation in Cutting cu.m	Length of Roads			
				Upstream Level	Downstream Level			Upstream Level	Downstream Level	upper	down				12 M Wide Road m	18 M Wide Road m	24 M Wide Road m	
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	19	20
1	A1-A2	53	24	229.250	229.250	-1	275	229.688	229.495	0.44	0.24	0.34	434.10	434.10	0.00			53
2	A3-A'4	58	24	228.750	228.500	-1	175	229.230	228.898	0.48	0.40	0.44	611.36	611.36	0.00			58
3	A7-D23	93	24	228.000	227.500	1	300	228.375	228.065	0.37	0.56	0.47	1048.84	1048.84	0.00			93
4	A1-A11	147	12	229.250	230.000	1	5000	229.688	229.717	0.44	-0.28	0.08	136.42	136.42	0.00	147		
5	A11-A12	53	12	230.000	230.000	1	8000	229.717	229.724	-0.28	-0.28	-0.28	177.86	0.00	177.86	53		
6	A12-A'13	33	12	230.000	229.750	1	8000	229.724	229.728	-0.28	-0.02	-0.15	59.11	0.00	59.11	33		
7	A12-A'12	56	12	230.000	229.750	1	5000	229.724	229.735	-0.28	-0.02	-0.15	97.94	0.00	97.94	56		
8	A2-A'2	62	12	229.250	229.500	1	5000	229.495	229.507	0.24	0.01	0.13	93.83	0.00	93.83	62		
9	A2-D1	52	12	229.250	228.750	1	5000	229.495	229.505	0.24	0.76	0.50	312.07	0.00	312.07	52		
10	A2-D2	62	12	229.250	228.750	1	725	229.495	229.580	0.24	0.83	0.54	400.03	0.00	400.03	62		
11	D2-D19	112	12	228.750	228.250	1	725	229.580	229.735	0.83	1.48	1.16	1555.91	0.00	1555.91	112		
12	D19-D18	121	12	228.250	227.750	1	8000	229.735	229.750	1.48	2.00	1.74	2530.07	0.00	2530.07	121		
13	D18-D3	136	12	227.750	228.500	1	5000	229.750	229.777	2.00	1.28	1.64	2674.25	0.00	2674.25	136		
14	D18-D17	49	12	227.750	228.250	-1	5000	229.750	229.740	2.00	1.49	1.75	1026.14	0.00	1026.14	49		
15	D17-D'16	32	12	228.250	228.250	1	5000	229.740	229.747	1.49	1.50	1.49	573.48	0.00	573.48	32		
16	D17-D4	164	12	228.250	228.000	1	5000	229.740	229.773	1.49	1.77	1.63	3211.06	0.00	3211.06	164		
17	D19-D20	143	12	228.250	228.000	-1	175	229.735	228.918	1.48	0.92	1.20	2061.50	0.00	2061.50	143		
18	D20-A'4	20	12	228.000	228.500	-1	1000	228.918	228.898	0.92	0.40	0.66	157.86	0.00	157.86	20		
19	D20-D7	85	12	228.000	227.750	1	5000	228.918	228.935	0.92	1.18	1.05	1072.29	0.00	1072.29	85		
17	D18-D6	49	12	227.750	227.750	1	5000	229.750	229.760	2.00	2.01	2.00	1178.90	0.00	1178.90	49		
18	D18-D'22	45	18	227.750	227.750	-1	125	229.750	229.390	2.00	1.64	1.82	1474.23	0.00	1474.23	45		
19	D'22-D5	46	18	227.750	227.500	-1	100	229.390	228.930	1.64	1.43	2.64	2185.95	0.00	2185.95	46		
20	D'22-D21	152	18	227.750	227.500	-1	350	229.390	228.956	1.64	1.46	1.55	4235.04	0.00	4235.04	152		
21	D21-D7	28	12	227.500	227.750	-1	1300	228.956	228.934	1.46	1.18	1.32	443.51	0.00	443.51	28		
22	D7-D23	80	12	227.750	227.500	-1	95	228.934	228.092	1.18	0.59	0.89	852.63	0.00	852.63	80		
23	A7-E1	53	12	228.000	227.500	-1	200	228.375	228.110	0.37	0.61	0.49	313.17	0.00	313.17	53		
24	E1-E2	21	12	227.500	227.500	1	5000	228.110	228.114	0.61	0.61	0.61	154.23	0.00	154.23	21		
25	E2-E3	50	12	227.500	227.500	1	5000	228.114	228.124	0.61	0.62	0.62	371.47	0.00	371.47	50		
26	E2-E4	28	12	227.500	227.250	1	5000	228.114	228.120	0.61	0.87	0.74	249.28	0.00	249.28	28		
Total		2083								0.910	0.871	0.928	29023	-335	29358	1636	243	204

FOR VATIKA LIMITED

Handwritten Signature
Authorised Signatory

Sector-85 VATIKA (Gurgaon) Design Statement of Roads

Sr No.	Name of Road	Length of Road m	Width of Road m	Natural Surface Levels		Slope Character	Longitudinal Slope	Formation Levels		Quantity cu.m	Earthwork in Filling cu.m	Excavation in Cutting cu.m	Length of Roads			
				Upstream Level	Downstream Level			Upstream Level	Downstream Level				12 M Wide Road m	15 M Wide Road m	24 M Wide Road m	
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	
1	B1-B2	22	24	230.750	230.000	-1	100	231.237	231.017	396.93	396.93	0.00			22	
2	B2-B3	162	12	230.000	230.000	1	2000	231.017	231.098	2055.32	2055.32	0.00	162			
3	B3-B8	27	12	230.000	230.000	1	5000	231.098	231.103	356.55	356.55	0.00	27			
4	B3-B4	30	12	230.000	230.500	1	2000	231.098	231.113	307.90	307.90	0.00	30			
5	B4-B5	67	12	230.500	230.250	1	5000	231.113	231.126	598.55	598.55	0.00	67			
6	B4-B5	49	15	230.500	230.000	1	1000	231.113	231.162	652.14	652.14	0.00	49			
7	B5-B10	48	12	230.000	230.750	1	5000	231.162	231.171	455.94	455.94	0.00	48			
8	B5-B6	33	15	230.000	230.500	1	1000	231.162	231.195	459.49	459.49	0.00	33			
9	B6-B11	58	12	230.500	230.250	1	5000	231.195	231.206	574.59	574.59	0.00	58			
10	B6-B7	65	15	230.500	229.750	1	5000	231.195	231.208	1049.36	1049.36	0.00	65			
11	B7-B12	48	12	229.750	230.250	1	5000	231.208	231.217	698.44	698.44	0.00	48			
12	B7-B14	52	12	229.750	229.500	1	5000	231.208	231.218	990.89	990.89	0.00	52			
13	B14-B15	42	12	229.500	229.500	1	5000	231.218	231.227	868.07	868.07	0.00	42			
14	B15-B22	103	12	229.500	230.250	1	5000	231.227	231.247	1683.26	1683.26	0.00	103			
15	B15-B36	176	12	229.500	229.500	-1	500	231.227	230.875	3274.79	3274.79	0.00	176			
16	B15-B16	25	12	229.500	229.750	1	175	231.227	231.369	501.90	501.90	0.00	25			
17	B16-B35	178	12	229.750	229.500	-1	300	231.369	230.776	3092.40	3092.40	0.00	178			
18	B16-B17	50	12	229.750	229.750	-1	5000	231.369	231.359	968.65	968.65	0.00	50			
19	B17-B34	166	12	229.750	229.750	-1	300	231.359	230.806	2654.85	2654.85	0.00	166			
20	B17-B18	32	12	229.750	229.750	-1	5000	231.359	231.353	616.79	616.79	0.00	32			
21	B17-B23	84	12	229.750	230.250	1	5000	231.359	231.376	1378.76	1378.76	0.00	84			
22	B18-B33	152	12	229.750	230.000	-1	300	231.353	230.846	2233.83	2233.83	0.00	152			
23	B18-B19	40	12	229.750	230.000	-1	5000	231.353	231.345	707.53	707.53	0.00	40			
24	B19-B31	135	12	230.000	230.000	-1	700	231.345	231.152	2022.72	2022.72	0.00	135			
25	B19-B20	41	12	230.000	230.000	-1	5000	231.345	231.337	659.73	659.73	0.00	41			
26	B20-B30	98	12	230.000	230.000	-1	700	231.337	231.197	1489.78	1489.78	0.00	98			
27	B20-B24	53	12	230.000	230.500	1	5000	231.337	231.347	694.59	694.59	0.00	53			
28	B20-B21	43	12	230.000	230.250	-1	5000	231.337	231.328	623.08	623.08	0.00	43			
29	B21-B29	56	12	230.250	230.250	-1	700	231.328	231.248	697.68	697.68	0.00	56			

Authorised Signatory

Sector 85 VATIKA (Gurgaon) Design Statement of Roads

Sr No.	Name of Road	Length of Road	Width of Road	Natural Surface Levels		Slope Character	Longitudinal Slope	Formation Levels		Earthwork in Filling	Excavation in Cutting	Length of Roads		
				Upstream Level	Downstream Level			Upstream Level	Downstream Level			12 M Wide Road	15 M Wide Road	24 M Wide Road
		m	m					m	m	cu.m	cu.m	m	m	m
30	B21-B25	76	12	230.250	230.500	1	5000	231.328	231.343	876.27	0.00	76		
31	B21-B28	56	12	230.250	230.250	-1	5000	231.328	231.317	720.80	0.00	56		
32	B28-B27	24	12	230.250	230.250	1	3000	231.317	231.325	308.45	0.00	24		
33	B27-B26	131	12	230.250	230.750	-1	6300	231.325	231.304	1280.59	0.00	131		
34	B28-B29	49	12	230.250	230.250	-1	700	231.317	231.247	606.83	0.00	49		
35	B29-B30	46	12	230.250	230.000	-1	900	231.247	231.196	605.25	0.00	46		
36	B30-B31	40	12	230.000	230.000	-1	900	231.196	231.151	563.37	0.00	40		
37	B31-B32	22	12	230.000	230.000	1	110	231.151	231.351	330.39	0.00	22		
38	B33-B34	37	12	230.000	229.750	-1	925	230.846	230.806	422.40	0.00	37		
39	B34-B35	37	12	229.750	229.500	-1	1200	230.806	230.776	517.68	0.00	37		
40	B35-B36	39	12	229.500	229.500	1	400	230.776	230.873	619.76	0.00	39		
41	B36-C1	63	12	229.500	229.000	-1	70	230.873	229.973	886.80	0.00	63		
42	C1-C2	35	24	229.000	229.000	-1	450	229.973	229.895	784.67	0.00			35
43	C2-C3	33	24	229.000	229.000	-1	450	229.895	229.822	679.99	0.00			33
44	C3-C4	20	24	229.000	229.000	-1	450	229.822	229.777	383.85	0.00			20
45	C4-C5	18	24	229.000	229.000	-1	450	229.777	229.737	327.23	0.00			18
46	C5-C6	72	24	229.000	228.750	-1	450	229.737	229.577	1352.10	0.00			72
47	C6-C7	102	24	228.750	228.750	-1	550	229.577	229.392	1798.64	0.00			102
48	C7-C8	25	24	228.750	228.750	1	700	229.392	229.428	395.92	0.00			25
49	C6-C9	47	24	228.750	228.500	1	5000	229.577	229.587	1079.68	0.00			47
50	C9-C10	55	24	228.500	228.250	1	5000	229.587	229.598	1606.92	0.00			55

Section 85 VALIKA (Gurgaon) Design Statement of Roads

Sr No.	Name of Road	Length of Road	Width of Road	Natural Surface Levels		Slope Character	Longitudinal Slope	Formation Levels		Quantity	Earthwork in Filling	Excavation in Cutting	Length of Roads		
				Upstream Level	Downstream Level			Upstream Level	Downstream Level				12 M Wide Road	15 M Wide Road	24 M Wide Road
		m	m					m	m	cu.m	cu.m	cu.m	m	m	m
51	C10-C11	42	24	228.250	228.000	1	5000	229.598	229.606	1488.88	1488.88	0.00			42
52	C11-C12	43	24	228.000	228.000	1	6000	229.606	229.613	1661.36	1661.36	0.00			43
53	C2-C15	27	12	229.000	228.750	-1	400	229.895	229.828	319.62	319.62	0.00	27		
54	C15-C19	56	12	228.750	228.750	1	5000	229.828	229.839	728.01	728.01	0.00	56		
55	C15-C16	49	12	228.750	228.500	-1	500	229.828	229.730	678.40	678.40	0.00	49		
56	C16-C18	44	12	228.500	228.750	1	5000	229.730	229.739	585.63	585.63	0.00	44		
57	C16-C17	75	12	228.500	228.000	-1	850	229.730	229.642	1292.06	1292.06	0.00	75		
58	C3-B40	18	12	229.000	229.000	1	120	229.822	229.972	193.73	193.73	0.00	18		
59	B40-B41	138	12	229.000	229.000	1	150	229.972	230.892	2371.24	2371.24	0.00	138		
60	B40-B42	149	15	229.000	229.250	1	5000	229.972	230.002	1926.15	1926.15	0.00		149	
61	C4-C20	105	12	229.000	228.500	1	5000	229.777	229.798	1307.84	1307.84	0.00	105		
62	C5-B37	115	12	229.000	229.000	1	5000	229.737	229.760	1033.57	1033.57	0.00	115		
63	B37-B38	55	12	229.000	229.000	1	5000	229.760	229.771	505.54	505.54	0.00	55		
64	B38-B39	89	12	229.000	229.500	1	5000	229.771	229.789	566.43	566.43	0.00	89		
65	C9-C7	116	12	228.500	228.750	-1	600	229.587	229.394	1204.36	1204.36	0.00	116		
66	C10-C14	97	12	228.250	228.500	1	5000	229.598	229.617	1434.71	1434.71	0.00	97		
67	C10-C17	83	12	228.250	228.000	1	1900	229.598	229.642	1488.73	1488.73	0.00	83		
68	C11-C21	42	12	228.000	228.000	1	5000	229.606	229.615	811.67	811.67	0.00	42		
69	B1-A1	156	12	230.750	230.500	-1	250	231.237	230.613	561.16	561.16	0.00	156		
70	A1-A2	43	12	230.500	230.500	-1	225	230.613	230.422	8.88	8.88	0.00	43		
71	A2-A3	68	12	230.500	230.750	1	275	230.422	230.669	65.04	0.00	65.04	68		
72	A2-A4	47	12	230.500	230.500	-1	225	230.422	230.213	103.09	0.00	103.09	47		
73	A4-A5	97	12	230.500	230.000	1	5000	230.213	230.232	32.05	0.00	32.05	97		
74	A5-A6	55	12	230.000	230.000	1	5000	230.232	230.243	156.86	156.86	0.00	55		
75	A3-A32	128	12	230.750	230.250	1	200	230.669	231.309	750.99	750.99	0.00	128		
		5099								69787.742	69987.933	-200.1905	4289	296	514

Authorised Signatory

Sector 82A VATIKA (Gurgaon)

Sr No.	Name of Road	Length of Road	Natural Surface Levels		Slope Character	Longitudinal Slope	Formation Levels		Quantity	Earthwork in Filling	Excavation in Cutting	Length of road		
			Upstream Level	Downstream Level			Upstream Level	Downstream Level				12 M Wide Road	15 M Wide Road	24 M Wide Road
		m					m	m	cu.m	cu.m	cu.m	m	m	m
	1	2	4	5	6	7	8	9	10	11	12	13	14	15
1	A1-A2	56	234.750	235.000	1	225	235.153	235.402	541	541	0	0	0	56
2	A2-A3	14	235.000	235.000	1	225	235.402	235.464	146	146	0	0	0	14
3	A59-A60	45	235.000	235.750	1	225	235.999	236.199	782	782	0	0	0	45
4	A61-A5	48	235.750	236.000	1	375	236.199	236.327	448	448	0	0	0	48
5	A5-A6	65	236.000	236.250	1	375	236.327	236.501	451	451	0	0	0	65
6	A4-A14	59	235.500	235.500	1	5000	235.999	236.011	716	716	0	0	0	59
7	A14-A10	97	235.500	235.750	1	3000	236.011	236.044	937	937	0	0	0	97
8	A10-A22	94	235.750	236.250	1	3500	236.044	236.070	129	129	0	0	0	94
9	A6-A37	16	236.250	236.500	1	110	236.501	236.646	76	76	0	0	0	16
10	A37-A37	109	236.500	236.500	1	275	236.646	237.043	901	901	0	0	0	109
11	A6-A32	39	236.250	236.500	1	125	236.501	236.813	264	264	0	0	0	39
12	A32-A31	55	236.500	236.750	1	75	236.813	237.546	732	732	0	0	0	55
13	A31-A49	27	236.750	236.750	1	100	237.546	237.816	603	603	0	0	0	27
14	A50-A51	39	237.750	238.000	1	65	237.816	238.416	226	226	0	0	0	39
15	A1-A55	163	234.750	234.250	1	225	235.153	235.878	1986	1986	0	163	0	0
16	A56-A57	262	234.750	236.250	1	250	236.701	237.749	5423	5423	0	262	0	0
17	A1-A7	47	234.750	234.500	1	6000	235.153	235.161	300	300	0	47	0	0
18	A7-A64	253	234.500	235.250	1	6000	235.161	235.203	932	932	0	253	0	0
19	A64-A43	100	235.250	235.500	1	6000	235.203	235.220	196	0	196	100	0	0
20	A43-A62	13	235.500	235.500	1	5000	235.220	235.222	44	0	44	13	0	0
21	A62-A44	81	235.500	236.000	1	5000	235.222	235.239	505	0	505	81	0	0

VATIKA

Sr No.	Name of Road	Length of Road m	Natural Surface Levels		Slope Character	Longitudinal Slope	Formation Levels		Quantity cu.m	Earthwork in Filling cu.m	Excavation in Cutting cu.m	Length of road			
			Upstream Level	Downstream Level			Upstream Level	Downstream Level				12 M Wide Road	15 M Wide Road	24 M Wide Road	
22	A62-A63	70	235.500	235.750	1	5000	235.222	235.236	332	0	332	70	0	0	
23	A63-A45	23	235.750	235.500	1	5000	235.236	235.241	107	0	107	23	0	0	
24	A63-A46	57	235.750	236.000	1	5000	235.236	235.248	433	0	433	57	0	0	
25	A2-A2	49	235.000	234.750	1	5000	235.402	235.412	313	313	0	49	0	0	
26	A3-A58	62	235.000	235.000	-1	650	235.464	235.369	310	310	0	62	0	0	
27	A58-A9	98	235.000	235.250	-1	650	235.369	235.218	198	198	0	98	0	0	
28	A9-A8	16	235.250	235.250	1	5000	235.218	235.221	6	0	6	16	0	0	
29	A9-A12	34	235.250	235.500	1	5000	235.218	235.225	63	0	63	34	0	0	
30	A9-A10	62	235.250	235.750	1	75	235.218	236.045	98	98	0	62	0	0	
31	A22-A23	94	236.250	236.750	1	3500	236.070	236.097	469	0	469	94	0	0	
32	A23-A24	97	236.750	237.000	1	5000	236.097	236.117	894	0	894	97	0	0	
33	A24-A25	62	237.000	237.000	1	5000	236.117	236.129	653	0	653	62	0	0	
34	A25-A26	88	237.000	237.500	1	5000	236.129	236.147	1468	0	1468	88	0	0	
35	A26-A27	73	237.500	236.750	1	5000	236.147	236.161	851	0	851	73	0	0	
36	A27-A28	91	236.750	236.500	1	5000	236.161	236.180	620	0	620	91	0	0	
37	A14-A15	34	235.500	235.500	1	300	236.011	236.125	232	232	0	34	0	0	
38	A15-A16	80	235.500	236.000	1	325	236.125	236.371	478	478	0	80	0	0	
39	A15-A20	24	235.500	235.750	1	1000	236.125	236.149	147	147	0	24	0	0	
40	A20-A21	25	235.750	236.250	1	1000	236.149	236.174	48	48	0	25	0	0	
41	A20-A16	73	235.750	236.000	1	325	236.149	236.373	338	338	0	73	0	0	
42	A16-A17	32	236.000	236.000	-1	2300	236.371	236.357	140	140	0	32	0	0	
43	A17-A18	18	236.000	236.250	1	5000	236.357	236.360	50	50	0	18	0	0	
44	A17-A5	66	236.000	236.000	-1	2200	236.357	236.327	271	271	0	66	0	0	
45	A31-A33	87	236.750	237.250	-1	1300	237.546	237.479	535	535	0	87	0	0	
46	A33-A34	25	237.250	237.500	1	5000	237.479	237.484	32	32	0	25	0	0	
47	A33-A35	50	237.250	236.500	-1	1300	237.479	237.441	351	351	0	50	0	0	
48	A35-A32	63	236.500	236.500	-1	100	237.441	236.811	473	473	0	63	0	0	
49	A35-A36	50	236.500	236.500	-1	75	237.441	236.774	364	364	0	50	0	0	
50	A36-A37	39	236.500	236.500	-1	300	236.774	236.644	98	98	0	39	0	0	
Total		3324						236.646	13428.65	20068.53	6639.8799	2382	179	763	

For VATIKA LIMITED

Ky Consultants Pvt Ltd

Sheet No:-22

(Director)