

AREA CALCULATION OF BASEMENT-02

NO.	A		B		C			s	AREA OF = S(S-A)(S-B)(S-C)	Area
GROSS - A										
2	2.255	+	147.900	+	149.345	/ 2	=	149.75	16548.967	128.643 SQM
3	6.100	+	77.210	+	72.700	/ 2	=	78.005	23816.604	153.804 SQM
4	77.210	+	133.735	+	103.830	/ 2	=	157.3875	15585274.376	3998.159 SQM
5	149.345	+	133.735	+	179.515	/ 2	=	231.3175	957773178.800	9786.602 SQM
6	26.335	+	104.790	+	121.330	/ 2	=	126.2275	1323839.935	1150.582 SQM
7	6.125	+	121.330	+	118.890	/ 2	=	123.1725	113757.691	337.280 SQM
8	10.495	+	179.515	+	186.970	/ 2	=	188.51	4627.82.900	680.281 SQM
9	118.890	+	186.970	+	226.295	/ 2	=	266.0775	113250534.551	11101.826 SQM
10	77.305	+	226.295	+	168.250	/ 2	=	235.935	24388176.975	4938.479 SQM
11	5.000	+	49.250	+	49.500	/ 2	=	51.875	15159.760	123.125 SQM
12	49.500	+	168.250	+	196.150	/ 2	=	206.95	13616934.624	3690.383 SQM
13	20.815	+	196.150	+	211.695	/ 2	=	214.33	1986682.098	1409.568 SQM
14	67.800	+	211.695	+	187.945	/ 2	=	233.72	39096590.613	6252.727 SQM
15	3.575	+	18.345	+	18.005	/ 2	=	19.9625	1035.795	32.184 SQM
17	50.100	+	105.630	+	92.995	/ 2	=	124.3625	5426685.552	2329.525 SQM
18	169.609	+	75.515	+	105.630	/ 2	=	175.3725	7056235.674	2655.228 SQM
19	24.450	+	75.515	+	63.920	/ 2	=	81.9425	545729.618	738.735 SQM
20	35.710	+	63.920	+	38.275	/ 2	=	68.9525	353813.012	594.872 SQM
21	21.295	+	38.275	+	24.310	/ 2	=	41.94	55544.073	236.529 SQM
								TOTAL	=	60338.632 SQM

SERVICE AREA

NO.	A		B		C			s	AREA OF = S(S-A)(S-B)(S-C)	Area
GROSS - C										
s1	2.465	+	3.735	+	4.475	/ 2	=	5.3375	21.101	4.603 SQM
s2	2.285	+	10.690	+	10.924	/ 2	=	11.9525	149.165	12.213 SQM
s3	3.390	+	10.930	+	12.570	/ 2	=	13.445	297.501	17.248 SQM
s4	7.385	+	12.570	+	10.230	/ 2	=	15.0925	1426.808	37.773 SQM
s5	5.080	+	9.560	+	10.825	/ 2	=	12.7325	589.635	24.282 SQM
s6	6.125	+	10.825	+	8.255	/ 2	=	12.6025	630.831	25.116 SQM
s7	3.970	+	8.275	+	8.280	/ 2	=	10.25	253.626	15.926 SQM
s8	0.975	+	3.970	+	3.850	/ 2	=	4.3975	3.523	1.877 SQM
s10	5.330	+	10.520	+	11.790	/ 2	=	13.82	786.006	28.036 SQM
s11	5.330	+	10.515	+	11.790	/ 2	=	13.8125	782.314	27.970 SQM
s19a	6.480	+	11.045	+	12.805	/ 2	=	15.165	1280.623	35.786 SQM
s21	15.245	+	22.970	+	27.570	/ 2	=	32.8925	30656.096	175.089 SQM
s21a	17.375	+	27.570	+	31.305	/ 2	=	38.125	56946.963	238.636 SQM
s40	5.355	+	8.490	+	10.035	/ 2	=	11.94	516.742	22.732 SQM
s42	11.180	+	19.035	+	22.295	/ 2	=	15.755	2251.118	47.446 SQM
s43	1.710	+	2.505	+	3.035	/ 2	=	3.625	4.587	2.142 SQM
s45	9.060	+	10.815	+	13.325	/ 2	=	16.6	2371.341	48.696 SQM
s46	6.565	+	12.630	+	10.815	/ 2	=	15	1260.227	35.500 SQM
s47	6.280	+	10.980	+	12.620	/ 2	=	14.94	1188.644	34.477 SQM
s48	6.120	+	8.340	+	10.350	/ 2	=	12.405	651.290	25.520 SQM
s49	4.845	+	8.380	+	10.350	/ 2	=	11.7875	400.849	20.021 SQM
s50	6.020	+	9.900	+	8.380	/ 2	=	12.15	631.772	25.135 SQM
s51	5.320	+	8.400	+	9.900	/ 2	=	11.81	499.209	22.343 SQM
s60	14.025	+	16.155	+	21.480	/ 2	=	25.83	12833.072	113.283 SQM
s61	2.680	+	21.480	+	19.345	/ 2	=	21.7525	272.176	16.498 SQM
s62	11.060	+	14.040	+	19.345	/ 2	=	22.2225	5840.577	76.424 SQM
s63	5.440	+	14.040	+	15.230	/ 2	=	17.355	1456.620	38.166 SQM
s64	5.925	+	15.230	+	14.025	/ 2	=	17.59	1726.323	41.549 SQM
s68	6.120	+	15.350	+	8.350	/ 2	=	12.41	652.853	25.551 SQM
s69	5.420	+	8.380	+	10.350	/ 2	=	12.075	512.199	22.632 SQM
s70	6.020	+	9.900	+	8.380	/ 2	=	12.15	631.772	25.135 SQM
s71	5.320	+	8.400	+	9.900	/ 2	=	11.81	499.209	22.343 SQM
s72	7.200	+	14.250	+	15.965	/ 2	=	18.7075	2631.690	51.300 SQM
s73	7.200	+	14.250	+	15.965	/ 2	=	18.7075	2631.690	51.300 SQM
s79	9.050	+	14.550	+	11.540	/ 2	=	17.55	2725.487	52.206 SQM
s80	7.440	+	11.135	+	14.550	/ 2	=	16.5425	1654.965	40.681 SQM
s81	7.660	+	13.530	+	11.135	/ 2	=	16.1625	1814.761	42.647 SQM
s82	7.970	+	11.625	+	13.530	/ 2	=	16.5625	2130.852	46.161 SQM
s90	5.150	+	7.795	+	9.345	/ 2	=	11.145	402.890	20.072 SQM
s92	5.870	+	7.825	+	9.405	/ 2	=	11.55	524.184	22.895 SQM
s93	5.250	+	7.800	+	9.405	/ 2	=	11.2275	419.225	20.475 SQM
s102	7.200	+	14.250	+	15.965	/ 2	=	18.7075	2631.690	51.300 SQM
s103	7.200	+	15.965	+	14.250	/ 2	=	18.7075	2631.690	51.300 SQM
s105	5.770	+	8.330	+	10.140	/ 2	=	12.12	577.538	24.032 SQM
s106	5.600	+	10.140	+	13.920	/ 2	=	14.83	1284.594	24.170 SQM
s107	8.350	+	10.915	+	13.920	/ 2	=	16.5925	2075.132	45.554 SQM
s108	8.020	+	17.200	+	18.980	/ 2	=	22.1	4757.136	68.972 SQM
s109	7.130	+	18.980	+	22.620	/ 2	=	24.365	3946.016	62.817 SQM
s110	14.195	+	22.620	+	17.540	/ 2	=	27.1775	15497.402	124.489 SQM
s134	5.985	+	8.000	+	9.980	/ 2	=	11.9825	573.121	23.940 SQM
s125	5.390	+	9.980	+	13.715	/ 2	=	14.5425	502.516	22.417 SQM
s126	5.510	+	13.715	+	9.760	/ 2	=	14.4025	478.996	21.886 SQM
s127	5.415	+	9.760	+	8.000	/ 2	=	11.5875	468.921	21.655 SQM
s135	6.870	+	15.345	+	16.855	/ 2	=	19.535	2778.225	52.709 SQM
s136	6.980	+	16.855	+	20.450	/ 2	=	22.1425	3004.530	54.814 SQM
s137	13.350	+	20.450	+	15.120	/ 2	=	24.46	10127.984	100.886 SQM
s139	5.545	+	12.255	+	13.450	/ 2	=	15.625	1154.436	33.977 SQM
s140	2.450	+	13.450	+	14.515	/ 2	=	15.3075	236.123	15.366 SQM
s141	5.160	+	14.515	+	12.435	/ 2	=	16.055	975.140	31.227 SQM
s142	2.145	+	12.250	+	12.435	/ 2	=	13.415	172.610	13.138 SQM
s149	4.400	+	10.660	+	11.535	/ 2	=	13.2975	549.996	23.452 SQM
s150	7.030	+	11.535	+	7.425	/ 2	=	12.995	630.369	25.107 SQM
s151	6.130	+	12.085	+	13.545	/ 2	=	15.88	1371.999	37.041 SQM
s152	7.885	+	13.545	+	7.425	/ 2	=	14.4275	583.314	24.152 SQM
s152a	4.570	+	7.030	+	7.265	/ 2	=	9.4325	238.841	15.454 SQM
s152b	1.185	+	7.115	+	7.265	/ 2	=	7.7825	17.736	4.211 SQM
s153	3.120	+	11.050	+	11.870	/ 2	=	13.02	292.018	17.089 SQM
s154	9.830	+	11.870	+	13.285	/ 2	=	17.4925	3170.852	56.310 SQM
s155	5.125	+	13.285	+	11.980	/ 2	=	15.195	939.603	30.653 SQM
s156	1.645	+	11.980	+	12.135	/ 2	=	12.87	97.074	9.853 SQM
s157	5.125	+	8.100	+	9.160	/ 2	=	11.1925	426.852	20.660 SQM
s159	5.105	+	7.610	+	9.160	/ 2	=	10.9375	377.312	19.425 SQM
s183	7.370	+	10.180	+	14.510	/ 2	=	16.03	1234.386	35.134 SQM
s184	3.625	+	16.990	+	14.510	/ 2	=	17.5625	427.762	20.682 SQM
s185	10.710	+	12.485	+	16.990	/ 2	=	20.0925	4449.450	66.704 SQM
s192	5.120	+	8.300	+	9.750	/ 2	=	11.585	491.477	21.248 SQM
s193	5.815	+	9.750	+	8.330	/ 2	=	11.9475	582.441	24.134 SQM
s194	5.220	+	8.330	+	10.190	/ 2	=	11.87	469.445	21.667 SQM
s195	5.915	+	10.190	+	8.300	/ 2	=	12.2025	602.567	24.547 SQM
s199	5.175	+	8.480	+	9.770	/ 2	=	11.7125	480.796	21.927 SQM
s201	5.445	+	6.110	+	5.770	/ 2	=	10.6625	226.037	15.035 SQM
s202	6.110	+	13.200	+	14.605	/ 2	=	16.9575	1625.998	40.324 SQM
s203	6.520	+	16.395	+	20.050	/ 2	=	21.4825	2342.546	48.400 SQM
s204	8.680	+	16.395	+	18.225	/ 2	=	21.65	5050.953	71.091 SQM
s205	7.990	+	16.380	+	18.225	/ 2	=	21.2975	4282.145	65.438 SQM
s206	2.080	+	6.365	+	6.015	/ 2	=	7.23	39.133	6.256 SQM
s207	3.065	+	5.860	+	6.365	/ 2	=	7.645	80.000	8.944 SQM
s208	6.285	+	8.925	+	7.465	/ 2	=	11.3375	535.158	23.133 SQM
s209	5.060	+	6.940	+	8.925	/ 2	=	10.4625	306.123	17.496 SQM
								TOTAL	+	3340.844 SQM

AREA CALCULATION OF BASEMENT-02	=	GROSS – A	+	GROSS – B		
	=	50338.532	+	49.330		
GROSS –1	=	50387.861	SQM			
SERVICE AREA OF BASEMENT-02	=	GROSS – C	+	GROSS – D	-	GROSS – E
	=	3340.844	+	6751.320	-	56.017
GROSS-2	=	10036.147	SQM			
NET PARKING AREA OF BASEMENT-2	=	GROSS – 1	-	GROSS-2		
	=	50387.861	-	10036.147		
	=	40351.714	SQM			
NO. OF PARKING ACHIEVABLE OF BASEMENT-2	=	40351.714	/	32		
	=	1260.991				
OR SAY	=	1261		ECS		

DEDUCTION														
AAC AREA														
GROSS – E														
d1	3.14	X	12.68	X	12.68	X	45	/ 360	-	0.5	X	10.88	1.719	X 12.808 = 11.49981 SQM
d2	3.14	X	12.705	X	12.705	X	90	/ 360	-	0.5	X	10.705	3.439	X 10.816 = 6.562762 SQM
														TOTAL = 56.017 SQM

AREA CALCULATION OF BASEMENT-02

GROSS –B								
1	1	X	85.760	X	0.500	=	42.880	SQM
1B	1	X	0.195	X	3.895	=	0.760	SQM
1Ba	1	X	5.690	X	1.000	=	5.690	SQM
TOTAL						=	49.330	SQM
SERVICE AREA								
GROSS –D								
s8	1	X	1.500	X	0.900	=	1.350	SQM
s12	24	X	1.050	X	1.500	=	37.800	SQM
s13	1	X	5.725	X	8.950	=	51.239	SQM
s14	1	X	5.300	X	52.450	=	278.012	SQM
s15	3.14	X	7.405	X	7.405	=	172.179	SQM
s16	1	X	5.305	X	52.550	=	278.807	SQM
s17	3.14	X	7.405	X	7.405	=	172.179	SQM
s18	1	X	0.400	X	11.905	=	4.762	SQM
s19	1	X	6.480	X	11.905	=	77.144	SQM
s20	1	X	5.420	X	22.970	=	124.497	SQM
s22	1	X	11.185	X	31.295	=	349.409	SQM
s23	1	X	4.700	X	15.685	=	73.720	SQM
s24	1	X	2.035	X	7.785	=	15.842	SQM
s25	1	X	2.200	X	5.430	=	11.946	SQM
s26	1	X	5.700	X	8.100	=	41.310	SQM
s27	1	X	1.500	X	0.900	=	1.350	SQM
s28	1	X	1.500	X	1.200	=	1.800	SQM
s29	1	X	1.500	X	0.900	=	1.350	SQM
s30	1	X	1.950	X	10.200	=	19.890	SQM
s31	1	X	8.250	X	10.100	=	83.325	SQM
s32	1	X	1.500	X	0.900	=	1.350	SQM
s32a	1	X	1.800	X	0.900	=	1.620	SQM
s33	1	X	10.100	X	7.095	=	71.660	SQM
s34	1	X	1.500	X	0.900	=	1.350	SQM
s35	1	X	2.200	X	1.450	=	3.190	SQM
s36	1	X	1.900	X	3.150	=	5.143	SQM
s37	1	X	0.660	X	1.950	=	1.268	SQM
s38	1	X	2.800	X	3.500	=	9.800	SQM
s39	1	X	7.200	X	14.250	=	102.600	SQM
s39a	-1	X	4.950	X	3.630	=	17.919	SQM
s44	1	X	0.600	X	1.145	=	0.687	SQM
s52	1	X	7.200	X	14.250	=	102.600	SQM
s53	1	X	1.400	X	1.100	=	1.540	SQM
s54	1	X	0.925	X	6.430	=	5.948	SQM
s55	1	X	8.945	X	6.335	=	56.667	SQM
s56	1	X	4.935	X	3.600	=	17.766	SQM
s57	1	X	7.260	X	14.250	=	103.455	SQM
s58	1	X	4.045	X	3.600	=	0.785	SQM
s59	1	X	0.270	X	9.395	=	2.537	SQM
s60	1	X	6.425	X	7.295	=	46.710	SQM
s98	1	X	2.515	X	6.335	=	15.933	SQM
s97	1	X	1.400	X	1.100	=	1.540	SQM
s74	1	X	4.900	X	3.735	=	18.378	SQM
s75	1	X	7.200	X	7.230	=	52.056	SQM
s76	1	X	7.205	X	7.020	=	50.579	SQM
s77	0.5	X	(6.040+6.100)	X	3.245	=	19.705	SQM
s78	1	X	8.425	X	5.035	=	42.420	SQM
s80	1	X	6.645	X	7.270	=	48.309	SQM
s87	1	X	2.680	X	7.325	=	19.631	SQM
s88	1	X	1.300	X	1.100	=	1.430	SQM
s89	1	X	10.850	X	10.600	=	115.010	SQM
s94	1	X	2.275	X	7.550	=	17.176	SQM
s95	1	X	3.325	X	8.550	=	28.429	SQM
s96	1	X	3.525	X	9.550	=	33.664	SQM
s97	1	X	2.675	X	8.550	=	22.871	SQM
s98	1	X	1.050	X	1.500	=	1.575	SQM
s99	1	X	1.825	X	8.900	=	16.243	SQM
s100	1	X	6.950	X	11.200	=	76.720	SQM
s101	1	X	1.825	X	8.900	=	16.243	SQM
s104	1	X	2.710	X	4.000	=	12.466	SQM
s111	1	X	4.145	X	8.710	=	36.104	SQM
s112	1	X	8.950	X	1.760	=	15.752	SQM
s113	1	X	6.230	X	5.755	=	35.854	SQM
s114	1	X	1.120	X	4.785	=	5.359	SQM
s115	1	X	1.400	X	4.770	=	6.678	SQM
s116	1	X	7.200	X	14.250	=	102.600	SQM
s117	1	X	7.200	X	14.250	=	102.600	SQM
s118	1	X	13.830	X	11.620	=	158.381	SQM
s121	1	X	6.425	X	0.925	=	5.943	SQM
s122	1	X	8.950	X	6.525	=	58.399	SQM
s128	1	X	5.780	X	2.700	=	15.606	SQM
s129	1	X	7.200	X	14.250	=	102.600	SQM
s130	1	X	1.400	X	6.525	=	9.135	SQM
s131	1	X	1.120	X	6.525	=	7.308	SQM
s132	1	X	6.430	X	7.450	=	47.904	SQM
s133	1	X	0.200	X	3.175	=	0.635	SQM
s134	1	X	4.680	X	9.135	=	42.752	SQM
s138	1	X	7.200	X	14.800	=	106.560	SQM
s143	1	X	3.000	X	2.100	=	6.300	SQM
s144	1	X	8.000	X	0.600	=	4.800	SQM
s145	1	X	7.800	X	14.550	=	113.490	SQM
s146	1	X	10.830	X	8.600	=	93.138	SQM
s147	1	X	5.975	X	9.125	=	54.522	SQM
s148	1	X	4.400	X	1.135	=	4.994	SQM
s158	1	X	0.810	X	1.500	=	0.915	SQM
s160	1	X	1.600	X	0.900	=	1.440	SQM
s161	1	X	0.300	X	1.200	=	0.360	SQM
s162	1	X	7.045	X	6.565	=	46.250	SQM
s163	0.5	X	(7.045+4.195)	X	3.255	=	18.293	SQM
s164	1	X	0.825	X	1.800	=	1.485	SQM
s165	1	X	0.190	X	8.105	=	1.540	SQM
s166	1	X	4.970	X	14.380	=	71.369	SQM
s167	1	X	9.400	X	7.175	=	67.445	SQM
s168	1	X	16.085	X	7.185	=	115.571	SQM
s169	1	X	8.710	X	0.195	=	1.308	SQM
s170	1	X	0.905	X	1.500	=	1.358	SQM
s171	1	X	0.995	X	2.305	=	2.293	SQM
s172	1	X	8.105	X	6.500	=	52.683	SQM
s173	1	X	1.000	X	0.900	=	1.350	SQM
s174	1	X	1.385	X	4.650	=	6.717	SQM
s175	1	X	0.425	X	0.600	=	0.340	SQM
s176	1	X	19.875	X	6.500	=	127.888	SQM
s177	1	X	13.500	X	6.425	=	86.738	SQM
s178	1	X	1.500	X	0.100	=	0.150	SQM
s179	1	X	0.800	X	1.800	=	1.440	SQM
s180	0.5	X	(10.430+9.200)	X	6.700	=	65.761	SQM
s181	1	X	0.900	X	1.500	=	1.350	SQM
s182	1	X	1.350	X	1.050	=	1.418	SQM
s186	1	X	2.780	X	4.935	=	13.821	SQM
s187	1	X	0.835	X	7.670	=	6.404	SQM
s188	1	X	10.800	X	10.850	=	117.180	SQM
s189	1	X	2.720	X	0.100	=	0.272	SQM
s190	1	X	8.245	X	7.220	=	66.749	SQM
s191	1	X	0.025	X	1.960	=	0.049	SQM
s196	0.5	X	(11.530+12.210)	X	8.075	=	95.850	SQM
s197	1	X	0.200	X	7.215	=	1.443	SQM
s198	1	X	10.600	X	10.850	=	115.010	SQM
s200	1	X	2.940	X	3.795	=	11.157	SQM
s210	1	X	6.930	X	6.775	=	46.951	SQM
s211	1	X	5.350	X	3.660	=	19.581	SQM
s212	1	X	0.100	X	2.720	=	0.272	SQM
s214	1	X	10.910	X	13.410	=	146.323	SQM
s215	1	X	1.325	X	0.590	=	0.782	SQM
s216	1	X	14.180	X	3.240	=	45.943	SQM
s217	1	X	2.050	X	1.010	=	2.071	SQM
s217a	1	X	1.050	X	1.430	=	1.502	SQM
s220	1	X	5.300	X	52.355	=	277.482	SQM
s221	3.14	X	7.400	X	7.400	=	171.946	SQM
s222	1	X	5.300	X	52.400	=	277.747	SQM
s222a	0.5	X	(5.980+6.200)	X	0.990	=	6.029	SQM
s222b	1	X	2.110	X	6.200	=	13.082	SQM
s223	3.14	X	7.400	X	7.400	=	171.946	SQM
s224	1	X	9.800	X	4.245	=	41.601	SQM
s225	1	X	10.020	X	2.200	=	22.044	SQM
s226	1	X	0.200	X	1.200	=	0.240	SQM
s227	1	X	0.945	X	1.500	=	1.418	SQM
s228	1	X	5.055	X	7.800	=	39.429	SQM
s229	1	X	0.200	X	1.400	=	0.280	SQM
s230	1	X	1.560	X	0.240	=	0.374	SQM
s230a	1	X	6.710	X	1.350	=	9.059	SQM
s230b	1	X	10.280	X	2.810	=	28.831	SQM
s231	1	X	15.800	X	10.200	=	161.160	SQM
s232	1	X	1.300	X	1.500	=	1.950	SQM
s233	1	X	3.100	X	8.000	=	24.800	SQM
			TOTAL			=	6751.320	SQM

NOTES:

- BUILDING WILL BE DESIGNED STRUCTURALLY AS PER RELEVANT IS CODES FOR EARTH QUAKE RESISTANCE.
- BUILDING HAS AUTOMATIC SPRINKLER SYSTEM ON ALL FLOORS.
- THE BUILDING IS FULLY MECHANICALLY VENTILATED & CENTRALLY AIR CONDITIONED WITH 100% POWER BACKUP.
- MSL 249.200 CONSIDERED AS ±00.00.
- ALL DIMENSIONS ARE IN MM UNLESS NOTED OTHERWISE.

DESIGN CONSULTANT:

RSP Design Consultants (I) Pvt. Ltd.

RSP UNIT 103 FIRST FLOOR BESTECH BUSINESS TOWER, SOHNA ROAD, SECTOR 48, GURUGRAM, HARYANA 122018

OWNER: DLF LIMITED
THE SHOPPING MALL,DLF QUTAB ENCLAVE(PHASE-I) GURGAON, HARYANA 122002

ASSOCIATE ARCHITECT:

SBA Design N Code LLP
Architecture·Codes·Interiors
(Formerly known as RSNS)
69,Nora Niwas Bhawani Kunj, (Behind D2), Vasant Kunj, New Delhi-110070.
Mob.: 9810791652,9811077209

STRUCTURAL ENGINEER:

LERA CONSULTING STRUCTURAL ENGINEERS (INDIA) PVT LTD
THE RUBY,NORTH WING, FLOOR 23,29 (SENPATI BAPAT MARG, DADAR (W) MUMBAI MAHARASHTRA INDIA 400 028

MEP CONSULTANT:

ARUP INDIA PRIVATE LIMITED
5TH FLOOR, JET PRIME, NEAR METRO STATION, SUREN ROAD, NEAR OFF.:, WESTERN EXPRESS HIGHWAY, ANDHERI EAST, MUMBAI, MAHARASHTRA INDIA 400 093

TITLE:-

REVISED BUILDING PLAN OF PHASE-R16 (THE DAHLIAS) FALLING IN GROUP HOUSING COLONY OVER AN AREA MEASURING 476.6015 ACRES NAMELY DLF-5 (EARLIER KNOWN AS ZONE-10, DLF CITY PHASE-V) IN SECTOR-42, 43, 53 & 54 GURUGRAM MANESAR URBAN COMPLEX BEING DEVELOPED BY DLF LIMITED.

PROJECT:- THE DAHLIAS

This is a "PROVISIONAL BUILDING PLAN" approved only for the purpose of inviting objections from the general public.
B.TP (HQ) Member Secretary B.P.A.C. | B.TP (O) Member B.P.A.C. | C.TP (HL) Chairman, B.P.A.C.
DTP(HQ) JD. | PA. | ATP(HQ)
JD(HQ) | JD (T) MEMBER BPAC

TO BE READ WITH THIS OFFICE MEMO NO.:- 41323
DATED:- 29-10-2025

ARCHITECT'S SEAL & SIGNATURE	OWNER'S SEAL & SIGNATURE

Date : JULY.2025 | Scale :1:400

Drawing Title:- BASEMENT-02 AREA CALCULATION

Drawing No:- BS-06

DLF5

03-30092025