w/s (Domi)

Checked subject to comments in forwarding letter No. 111161 Dt. 05.07.2022 and notes attached with the estimate

Superintending Engineer (HQ) for Chief Engineer-I HSVP, Panchkula 7.7.2022

SOE(U/G) 7/7/2022

FROM TANKER INLET CONNECTION FROM MUNICIPAL CONNECTION

6M MOTORABLE ROAD

100Φ DOMESTIC WATER SUPPLY

FROM MUNICIPAL CONNECTION 100Φ

6.0m MOTORABLE FIRE TENDER PATH

OPEN TO SKY COURTYARD AT GROUND FLOOR LVL +450MM

COURTYARD AT GROUND FLOOR LVL +450MM

OPEN TO SKY

6M WIDE FIRE TENDER ROAD FIRE CONTROL ROOM @ GROUND FLOOR LVL

12 M WIDE SERVICE ROAD

60 M WIDE UTILITY CORRIDOR

75 M WIDE ROAD

12 M WIDE SERVICE ROAD

60 M WIDE ROAD

LEGEND FOR PLUMBING
— DOMESTIC WATER SUPPLY

DOMESTIC WATER SUPPLY

This is a "PROVISIONAL BUILDING PLAN" approved only for the purpose of inviting objections from the general public

Superintending Engineer, HSVP, Circle, Gurugram

Only For Service Plan Estimate

Executive Engineer HSVP, Division No. Gurugram

ACPL Design Ltd

DRAWING TITLE: SITE PLAN | SCALE: 1:200 | NORTH | DRAWING NO: 01

KULMEET DHANOJAM ARCHITECT CA/92/21743

OWNER'S SIGNATURE | ARCHITECT'S SIGNATURE

TABLE 3.0

PARKING REQUIRED				
	AREA (SQM.)		1 ECS	CAR NUMBERS
TOTAL FAR AREA	78906.15		50	1579.323
				REQUIRED= 1580
PARKING PROPOSED				
UPPER BASEMENT 01				
NORMAL PARKING				580
LOWER BASEMENT 02				
STACK PARKING	155x2			310
NORMAL PARKING				600
G. TOTAL		PROPOSED=		1580

TABLE 2.0

BUILT UP AREA	
	AREA (SQM.)
UPPER BASMENT 01	28228.929
LOWER BASEMENT 02	32819.048
HYPER MARKET (UPPER BASEMENT	5824.559
GROUND FLOOR	23,910.155
FIRST FLOOR	18961.26
SECOND FLOOR	16594.935
THIRD FLOOR	9265.343
FOURTH FLOOR	5249.918
MUMTY & MACHINE ROOM	3611.526
TOTAL BUILT UP AREA	**144465.673**
NON FAR AREA	
	AREA (SQM.)
UPPER BASMENT 01	28228.929
LOWER BASEMENT 02	32819.048
MUMTY & MACHINE ROOM	3611.526
TOTAL	64,659.503

TABLE 1.0

AREA STATEMENT			
		ACRE	SQM.
TOTAL AREA OF THE SITE		10.4375	42238.996
PERMISSIBLE F.A.R	175%		73918.243
ADDITIONAL IGBC(GOLD RATING) F.A.R	12%		5068.68
TOTAL PERMISSIBLE FAR	187%		78986.923
PERMISSIBLE GROUND COVERAGE	60%		25,343.398
PROPOSED			
GROUND COVERAGE	56.000%		23,910.155
PROPOSED FAR	186.951%		78906.15
FAR AREA			
HYPER MARKET LOWER BASEMENT-01			5824.559
GROUND FLOOR AREA			23833.451
FIRST FLOOR AREA			18959.35
SECOND FLOOR AREA			16568.067
THIRD FLOOR AREA			8530.81
FOURTH FLOOR AREA			5249.918
TOTAL FAR AREA			78966.15
PROPOSED BASEMENT AREA			
IST. BASEMENT AREA			28228.929
2ND. BASMENT AREA			32819.048
TOTAL BASEMENT AREA			61047.977

PROJECT
REVISED BUILDING PLAN OF COMMERCIAL COLONY MEASURING 10.4375 ACRES (LICENCE NO.56 OF 2013 DATED 10.07.2013) IN SECTOR -88 , GURUGRAM MANESAR URBAN COMPLEX BEING DEVELOPED BY AMB INFRABUILD PVT. LTD.

NOTES:
1. ALL DIMENSIONS ARE IN MM.
2. GATE AND BOUNDARY WALL SHALL BE AS PER STANDARD DESIGN.
3. SPRINKLERS WILL BE PROVIDED IN ENTIRE BREDING INCLUDING BASEMENTS AS PER N.B.C.
4. RAIN WATER HARVESTING SYSTEM WILL BE PROVIDED AS PER APPLICABLE NORMS.
5. STAND BY POWER BACK UP WILL BE PROVIDED FOR LIFTS & ESSENTIAL SERVICE AREAS.
6. DISABLED RAMP @ 1:12 SLOPE WITH 900MM HIGH RAILING.
7. ALL BASEMENTS ARE MECHANICALLY VENTILATED.
8. BUILDING WILL BE DESIGNED (STRUCTURES) AS PER RELEVANT I.S.CODES FOR EARTHQUAKE RESISTANCE.