



1 SCHOOL & EWS- ELEVATION A
1:100



2 SCHOOL & EWS- ELEVATION B
1:100

TO BE READ WITH OUR LETTER MEMO NO. 21899 DATED : 24-06-2026

This is a "PROVISIONAL BUILDING PLAN" approved only for the purpose of inviting Objections from the general public

EWS SCHOOL SCHEDULE					
DOORS					
ROUGH OPENINGS (MASONRY)					
Type	Width	Height	Lintel	Sill	
D01	2000	2300	2300	0	
D02	1000	2300	2300	0	
D02a	1000	1750	1750	0	
D03	1000	2300	2300	0	
D04	600	2150	2300	150	
D05	750	2000	2200	0	
D06	1000	2200	2200	0	
D06a	1000	2000	2200	200	
D07	1125	2150	2300	150	
D08	600	2150	2300	150	
D09	1000	2300	2300	0	

FIRE DOORS					
ROUGH OPENINGS (MASONRY)					
Type	Width	Height	Lintel	Sill	F. Rating
FD01	1250	2300	2300	0	2HR
FD01a	1250	2200	2200	0	2HR
FD01b	1250	1750	2200	0	2HR
FD01c	1250	1900	2200	0	2HR
FD02	1000	2300	2300	0	2HR
FD03	900	2150	2300	150	2HR
FD03a	900	1600	1750	150	2HR
FD03b	900	2050	2200	150	2HR
FD04	900	2150	2300	150	2HR
FD04a	900	2050	2200	150	2HR
FD05	1200	2000	2000	0	2HR
FD06	2500	2150	2300	150	2HR
FD06a	2500	2050	2200	150	2HR

DOOR WINDOW				
ROUGH OPENINGS (MASONRY)				
Type	Width (D+W)	Height (D/W)	Lintel	Window Sill
DW01	800 + 400	2200 / 950	2200	1250
DW02	800 + 405	2200 / 950	2200	1250
DW03	800 + 290	2200 / 950	2200	1250

WINDOW				
ROUGH OPENINGS (MASONRY)				
Type	Width	Height	Lintel	Sill
W01	1800	1300	1000	2300
W02	1780	1300	1000	2300
W03	1100	1300	1000	2300
W04	980	550	1650	2200
W05	1630	1300	1000	2300
W06	900	1300	1000	2300
W07	450	550	1650	2200

SUBMISSION DRAWINGS
FOR APPROVAL AND STAMPING

This is a "PROVISIONAL BUILDING PLAN" approved only for the purpose of inviting objections from the general public

AD JD. PA. ATP

NOTES:
1. All fixture provided in toilets are as per N.B.C.
2. Basement will be mechanically ventilated.
3. All spaces (parking basement, services basement etc.) Will be artificially lit.
4. Standby generating capacity will be provided for the electrical requirement of the total scheme. This therefore includes standby generation for all common services, fire services, lifts etc. And also the entire electrical load for the ventilation.
5. Fire safety measures as per NBC includes smoke detector, heat detector, sprinkler spacing in compliance with code.
6. All eternal walls are 200mm and all internal walls are 100mm thick. (Valid for all drawings)

ARCHITECT
MORPHOGENESIS
41, Industrial Estate, Okhla Phase - III,
New Delhi 110020
TEL: 91 11 41828070
E Mail: studio@morphogenesis.org

CONSULTING STRUCTURAL ENGINEER
WHITBY WOOD
WHITBY WOOD PRITHWIDASANU
Unit No. 101, 1st Floor, Shantiniketan, Sod Vihar Road, Opp. Powai Market Gate, Mumbai - 400072, India
T: +91 9820 186878
E: prithwidasanu@whitbywood.com

CONSULTING MEP
PROION
Proion Consultants (India) Private Limited
Address : B2, Tushkev Khuc
New Delhi - 110 017, India
Telephone : 011-2652 4400
E-Mail : info@proion.net
Web : www.proion.net

CONSULTING LANDSCAPE ARCHITECT
MORPHOGENESIS
41, Industrial Estate, Okhla Phase - III,
New Delhi 110020
TEL: 91 11 41828070
E Mail: studio@morphogenesis.org

KEY PLAN

PROJECT
Revised / Proposed building plan for Mixed Land Use Colony (15% Residential and 5% Commercial) under TOD policy over an area measuring 14.20625 acres in the revenue estate of village Hayatpur Sector-89, Gurugram being developed by Godrej Properties Ltd.
(Lic No151 of 2023 Dated 20-07-2023)

DEVELOPER
Godrej Properties Ltd.
Unit No. 101, 1st Floor, Godrej One, Pirojshanagar, Eastern Express Highway, Mumbai - 400 079

DEVELOPER'S SIGNATURE :

AUTHORIZED SIGNATORY

ARCHITECT'S SIGNATURE :
KIRAN YADAV
CA/2016/69910

DRAWING NAME
SCHOOL & EWS
ELEVATIONS

DRAWING NO.
S-64

SCALE	1:100
DATE	05.11.2025